

Town of Manlius
Planning Board Agenda
February 10, 2020
6:30pm

1. Pledge Of Allegiance
2. Approval Of Minutes - January 27, 2020

Documents:

[JANUARY 27, 2020.PDF](#)

3. Nicholas Corbishley & Kira Gridley, 93 Collidge Road, N. Syracuse, NY 13212 PUBLIC HEARING - 2-Lot Subdivision – 5700 Townsend Road, Fayetteville, NY 13066 Tax Map # 091.-02-26.1

Documents:

[2-LOT SUBDIVISION - CORBISHLEY - GRIDLEY - 5700 TOWNSEND ROAD.PDF](#)
[CORBISHLEY - GRIDLEY 2- LOT SUBDIVISION.PDF](#)
[TOWNSEND RD TAX MAP.PDF](#)

4. WJC Works, LLC - 112 Pickard Drive, Syracuse, NY 13211 - PUBLIC HEARING - Site Plan - 6985 Collamer Road, East SYracuse, NY 13057 Tax Map # 036.-01-04.0

Documents:

[6985 COLLAMER ROAD - SITE PLAN.PDF](#)

5. Signarama - 102 Headson Drive, Syracuse, NY 13214 Site Review - Sign - 4719 Kehoe Lane, Manlius, NY 13104 Tax Map # 114.-04-82.0

Documents:

[SIGNARAMA - SITE REVIEW.PDF](#)

6. 3Gi – Central New York Inland Port, Vacant Rural Property To The South Of Kirkville Road Between Girden Rd. And Fremont Rd. Continued Recommendation For Zone Change Tax Map #'s 054.-01-28.1, 054.-01-06.1, 054.-01-04.1 & 054.-01-2.1

Documents:

[1- 3GI - KIRKVILLE ROAD - COMMENT RESPONSE LETTER 2019-12-10.PDF](#)
[2- 3GI - KIRKVILLE ROAD - PROJECT NARRATIVE.PDF](#)
[3- 3GI - KIRKVILLE ROAD - SITE PLAN APPLICATION - SIGNED.PDF](#)
[4- 3GI - KIRKVILLE ROAD - ZONE CHANGE APPLICATION \(3GI SIGNED\).PDF](#)
[5- 3GI - KIRKVILLE ROAD - PROPERTY LEGAL DESCRIPTIONS.PDF](#)
[8- 3GI - KIRKVILLE ROAD- LEHR - ZONE CHANGE MAPS.PDF](#)
[9- 3GI - KIRKVILLE ROAD- LEHR - SURVEY TOPO MAPS.PDF](#)
[10- 3GI - KIRKVILLE ROAD - SHORT EAF - SIGNED.PDF](#)
[6- 3GI - KIRKVILLE ROAD - EIS REPORT_2019-08-27.PDF](#)
[7- 3GI - KIRKVILLE ROAD - SITE PLANS 2019-12-18.PDF](#)

7. Brolex Properties - 5912 North Burdick Street, East Syracuse, NY 13057 Recommendation For Zone Change - Bridle Path/Megnin Farms Apartments - Corner Of Strawmount Trail And State Route 5, Chittenango, NY Tax Map #'s 082.-02-02 And 082.-02-03.0

Documents:

12-13-19 MEGNIN APARTMENTS - CONCEPT PLAN UPDATE - BRIDAL
PATH.PDF
PARCEL DESCRIPTION - BRIDLE PATH.PDF
SHORT ENVIRONMENTAL ASSESSMENT FORM - BRIDAL PATH.PDF
SURVEY - BRIDAL PATH.PDF
TAX MAP - BRIDLE PATH.PDF
ZONE CHANGE APPLICATION - BRIDLE PATH.PDF




8. Other Business

9. Adjournment

This meeting is being recorded and the audio recording will be posted to the Town Website at
www.townofmanlius.org

TOWN OF MANLIUS
PLANNING BOARD AGENDA
January 27, 2020
6:30PM


1. Pledge of Allegiance
2. Approval of Minutes –January 6, 2020
3. Nicholas Corbishley & Kira Gridley, 93 Collidge Road, N. Syracuse, NY 13212
2-Lot Subdivision – 5700 Townsend Road, Fayetteville, NY 13066
Tax Map # 091.-02-26.1
4. WJC Works, LLC – 112 Pickard Drive, Syracuse, NY 13211
Site Plan – 6985 Collamer Road, East Syracuse, NY 13057
Tax Map # 036.-01-04.0
5. Syracuse Signarama – 102 Headson Drive, Syracuse, NY 13214
Site Review – Sign – Manlius Academy Apartments – 4719 Kehoe Lane,
Manlius, NY 13104
Tax Map # 114.-04-82.0
6. 3Gi – Central New York Inland Port, Vacant rural property to the south of Kirkville
Road between Girden Rd. and Fremont Rd.
Recommendation for Zone Change
Tax Map #'s 054.-01-28.1, 054.-01-06.1, 054.-01-04.1 & 054.-01-2.1
7. Other Business
8. Adjournment



I HEREBY APPROVE THIS TRACT MAP.

GRIDLEY FARMS, LLC
5700 TOWNSEND ROAD
FAYETTEVILLE, NY 13066

ZONED: RA - RESTRICTED AGRICULTURE
MIN. AREA = 100,000 S.F.
MIN. FRONTAGE = 200'
MIN. SETBACKS
FRONT = 40'
REAR = 40'
SIDES = 20'



TOWNSHIP & RANGE (TOWNSHIP) [R.91-2-27 B.2P] ©20191104CONCEPT-RJ-DWG


- CONCEPT PLAN -			
CORBISHLEY - GRIDLEY SUBDIVISION			
PART OF LOT 68 - TOWN OF MANLIUS			
ONONDAGA COUNTY, NEW YORK			
I.D: 91-02-26.1	FILE: ROLL: 91-2-27	BIN: 2P	
DATE: 11-04-2019	SCALE: 1" = 100'	B/P: 415/55	
REVISIONS			

COTTRELL LAND SURVEYORS, P.C.
7308 STATE RTE 173, MANLIUS, NY 13104
(315)682-8121, WWW.COTTRELLSURVEYORS.COM



THE UNDERSIGNED CERTIFIES THAT
THIS MAP WAS MADE FROM AN
ACTUAL SURVEY ON 11-04-2019
VOID WITHOUT SIGNER'S EMBOSSED SEAL.

NOT A VALID SUBDIVISION WITHOUT RECORDING
DATA OF THE MAP FILING WITH THE ONONDAGA
COUNTY CLERK'S OFFICE.




COUNTY HEALTH DEPARTMENT APPROVAL
SUBDIVISION OF LAND
PLANNING BOARD CHAIRPERSON TOWN OF MANLIUS

Expected
Fee:

360 pd
1-15-2020

TOWN OF MANLIUS
PLANNING DEPARTMENT
INITIAL APPEARANCE APPLICATION



DATE: 1/15/20

Name of Project: Corbiskey/
Gridley Subdivision

Applicant must submit 12 copies of all site plans, surveys, and supporting data with the final application before a planning board meeting can be scheduled.

Location of Project: _____

Type of Project:

2-Lot
☐ Division of Land ☒ Subdivision ☐ Accessory Use ☐ Zone Change ☐ Site Review ☐ Other

Developer: _____ Phone: _____

Address: 5700 Townsend Rd Fayetteville Zip: 13066

Tax Map Number(#)/s: 091.-02-26-1

Present Zoning: RA-Restricted Agriculture Desired Zoning: _____

Total Acreage: 71.07 Total Number of Lots: _____

Property Owner/s: Gridley Farms Inc. O. George Gridley (pres) Phone: 315 436 6610

Address: 5800 Townsend Rd, Fayetteville N.Y. Zip: 13066

Tax Map#(s): _____ Owner's Signature: O. George Gridley (pres)

Printed Name: O. George Gridley

Property Owner/s: Gridley Farms Inc, Edward Gridley Phone: 315-243-3021

Address: 248 Salt Spring St. Fayetteville NY Zip: 13066

Tax Map#(s): _____ Owner's Signature: Edward Gridley

Printed Name: Edward Gridley

Use next page for additional known property owners' information

Planning Board Meeting Date Assignment: _____

Fee: _____ Paid: _____ Per: ☐ Credit/Debit Card ☐ Check ☐ Cash

Planning Board - Initial

TOWN OF MANLIUS
PLANNING DEPARTMENT
INITIAL APPEARANCE APPLICATION
(continued)

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

617.20
Appendix B
Short Environmental Assessment Form

Instructions for Completing

Part 1 - Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 - Project and Sponsor Information		
Name of Action or Project: <i>Corbushley / Gridley Subdivision</i>		
Project Location (describe, and attach a location map): <i>SW corner of 091.-02-26.1</i>		
Brief Description of Proposed Action: <i>Plot subdivision for residence construction.</i>		
Name of Applicant or Sponsor: <i>Kira Gridley & Nicolas Corbushley</i>	Telephone: <i>(315) 243-6183, (315) 380-1492</i> E-Mail: <i>KiraLGridley@gmail.com</i> <i>Nicolas.Corbushley@gmail.com</i>	
Address: <i>93 Carridge Rd</i>		
City/PO: <i>North Syracuse, NY 13</i>	State: <i>NY</i>	Zip Code: <i>13212</i>
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.		NO YES ☒ ☐
2. Does the proposed action require a permit, approval or funding from any other governmental Agency? If Yes, list agency(s) name and permit or approval:		NO YES ☒ ☐
3.a. Total acreage of the site of the proposed action?		<i>71.07</i> acres
b. Total acreage to be physically disturbed?		<i>3</i> acres
c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor?		<i>0</i> acres
4. Check all land uses that occur on, adjoining and near the proposed action. ☐ Urban ☒ Rural (non-agriculture) ☐ Industrial ☐ Commercial ☒ Residential (suburban) ☐ Forest ☒ Agriculture ☐ Aquatic ☐ Other (specify): _____ ☐ Parkland		

5. Is the proposed action, a. A permitted use under the zoning regulations?	NO ☐	YES ☒	N/A ☐
b. Consistent with the adopted comprehensive plan?	☐	☒	☐
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?	NO ☐	YES ☒	
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area? If Yes, identify: _____	NO ☒	YES ☐	
8. a. Will the proposed action result in a substantial increase in traffic above present levels?	NO ☒	YES ☐	
b. Are public transportation service(s) available at or near the site of the proposed action?	☒	☐	
c. Are any pedestrian accommodations or bicycle routes available on or near site of the proposed action?	☒	☐	
9. Does the proposed action meet or exceed the state energy code requirements? If the proposed action will exceed requirements, describe design features and technologies: _____	NO ☐	YES ☒	
10. Will the proposed action connect to an existing public/private water supply? If No, describe method for providing potable water: _____	NO ☒	YES ☐	
11. Will the proposed action connect to existing wastewater utilities? If No, describe method for providing wastewater treatment: _____	NO ☒	YES ☐	
12. a. Does the site contain a structure that is listed on either the State or National Register of Historic Places?	NO ☒	YES ☐	
b. Is the proposed action located in an archeological sensitive area?	☒	☐	
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?	NO ☐	YES ☒	
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody? If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres: _____	☒	☐	
14. Identify the typical habitat types that occur on, or are likely to be found on the project site. Check all that apply: ☐ Shoreline ☐ Forest ☒ Agricultural/grasslands ☐ Early mid-successional ☐ Wetland ☐ Urban ☐ Suburban			
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or Federal government as threatened or endangered?	NO ☒	YES ☐	
16. Is the project site located in the 100 year flood plain?	NO ☒	YES ☐	
17. Will the proposed action create storm water discharge, either from point or non-point sources? If Yes, a. Will storm water discharges flow to adjacent properties? ☐ NO ☐ YES b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)? If Yes, briefly describe: _____	NO ☒	YES ☐	

18. Does the proposed action include construction or other activities that result in the impoundment of water or other liquids (e.g. retention pond, waste lagoon, dam)? If Yes, explain purpose and size: _____	NO ☒	YES ☐
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility? If Yes, describe: _____	NO ☒	YES ☐
20. Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or completed) for hazardous waste? If Yes, describe: _____	NO ☒	YES ☐
I AFFIRM THAT THE INFORMATION PROVIDED ABOVE IS TRUE AND ACCURATE TO THE BEST OF MY KNOWLEDGE Applicant/sponsor name: <u>Kira Gnidley</u> Date: <u>1/15/2020</u> Signature: <u>[Signature]</u>		

STOP

Part 2 - Impact Assessment. The Lead Agency is responsible for the completion of Part 2. Answer all of the following questions in Part 2 using the information contained in Part 1 and other materials submitted by the project sponsor or otherwise available to the reviewer. When answering the questions the reviewer should be guided by the concept "Have my responses been reasonable considering the scale and context of the proposed action?"

	No, or small impact may occur	Moderate to large impact may occur
1. Will the proposed action create a material conflict with an adopted land use plan or zoning regulations?	☐	☐
2. Will the proposed action result in a change in the use or intensity of use of land?	☐	☐
3. Will the proposed action impair the character or quality of the existing community?	☐	☐
4. Will the proposed action have an impact on the environmental characteristics that caused the establishment of a Critical Environmental Area (CEA)?	☐	☐
5. Will the proposed action result in an adverse change in the existing level of traffic or affect existing infrastructure for mass transit, biking or walkway?	☐	☐
6. Will the proposed action cause an increase in the use of energy and it fails to incorporate reasonably available energy conservation or renewable energy opportunities?	☐	☐
7. Will the proposed action impact existing:		
a. public / private water supplies?	☐	☐
b. public / private wastewater treatment utilities?	☐	☐
8. Will the proposed action impair the character or quality of important historic, archaeological, architectural or aesthetic resources?	☐	☐
9. Will the proposed action result in an adverse change to natural resources (e.g., wetlands, waterbodies, groundwater, air quality, flora and fauna)?	☐	☐

	No, or small impact may occur	Moderate to large impact may occur
10. Will the proposed action result in an increase in the potential for erosion, flooding or drainage problems?	☐	☐
11. Will the proposed action create a hazard to environmental resources or human health?	☐	☐

Part 3 - Determination of significance. The Lead Agency is responsible for the completion of Part 3. For every question in Part 2 that was answered "moderate to large impact may occur", or if there is a need to explain why a particular element of the proposed action may or will not result in a significant adverse environmental impact, please complete Part 3. Part 3 should, in sufficient detail, identify the impact, including any measures or design elements that have been included by the project sponsor to avoid or reduce impacts. Part 3 should also explain how the lead agency determined that the impact may or will not be significant. Each potential impact should be assessed considering its setting, probability of occurring, duration, irreversibility, geographic scope and magnitude. Also consider the potential for short-term, long-term and cumulative impacts.

☐	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action may result in one or more potentially large or significant adverse impacts and an environmental impact statement is required.
☐	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action will not result in any significant adverse environmental impacts.
Name of Lead Agency Date	
Print or Type Name of Responsible Officer in Lead Agency Title of Responsible Officer	
Signature of Responsible Officer in Lead Agency Signature of Preparer (if different from Responsible Officer)	

PRINT

TOWN OF MANLIUS

DISCLOSURE AFFIDAVIT

This affidavit is a part of and must be completed and attached to every application, petition, request submitted for a *site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit.*

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

I. _____, being duly sworn, deposes and says that (s) he is:

(applicant, petitioner, corporation officer, property owner, etc.)

II. That deponent has read and is familiar with the provisions of the General Municipal Law, Section 809 which states:

- A. Every application, petition or request submitted for a site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit, pursuant to the provisions or any ordinance, local law, rule or regulation constituting the zoning and planning regulations of a municipality shall state the name, residence and the nature and extent of the interest of any state officer or any officer or employee of such municipality is a part, in the person, partnership or association making such application, petition or request (hereinafter called the applicant) to the extent known to such applicant.
- B. For the purpose of this action an officer or employee shall be deemed to have an interest in the applicant when (s)he, his/her spouse, or their brothers, sisters, parents, children, grandchildren, or the spouse of any of them:
 - 1) is the applicant, or
 - 2) is an officer, director, partner or employee of the applicant, or
 - 3) legally or beneficially owns or controls stock of a corporate applicant or is a member of a partnership or association applicant, or
 - 4) is a party to an agreement with such an applicant, express or implied, whereby (s) he may receive any payment or other benefit, whether or not for services rendered, or contingent upon the favorable approval of such application, petition or request.
- C. Ownership of less than five percent (5%) of the stock of a corporation whose stock is listed on the New York or American Stock Exchanges shall not constitute an interest for the purposes of this section.
- D. A person who knowingly and intentionally violates this section shall be guilty of a misdemeanor.

III. That no Town of Manlius officer, employee or a relative of either, as defined in Section 809 General Municipal Law has any interest in this application.

-OR-

If a Town of Manlius officer, employee or relative of either as defined in Section 809 General Municipal law has any interest in this application, the full particulars are provided on an attached sheet.

Date: January 15, 2020

Date: _____, 20____.

Kira Gindley
(Print Name)

(Print Name)

[Signature]
(Signature)

(Signature)

(Entity Name)

(Entity Name)

By (Officer) _____ (Title)

By (Officer) _____ (Title)

93 Coolidge Rd. N. Syracuse NY
(Mailing Address of Applicant) 13212

(Mailing Address of Applicant)

(315) 243-6183
(Telephone Number)

(Telephone Number)


ACKNOWLEDGEMENTS

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

On this 15th day of January in the year 2020, before me, the undersigned, a notary public in and for said state, personally appeared Kira Gindley, and _____ personally known to me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within Petition and acknowledged to me the he/she/they executed the same in his/her/their capacity, and that by his/her/their signature(s) on the Petition, the individual or the persons upon behalf of which the individual acted executed the instrument.

[Signature]
Notary Public

DEBORAH J WITZEL
Notary Public, State of New York
No. 01W16162236
Qualified in Onondaga County
Commission Expires March 5, 2023



Expected
Fee: _____

TOWN OF MANLIUS
PLANNING DEPARTMENT
INITIAL APPEARANCE APPLICATION

DATE: January 16, 2020

Name of Project: Purchase of 6985 Collamer Road

Applicant must submit 12 copies of all site plans, surveys, and supporting data with the final application before a planning board meeting can be scheduled.

Location of Project: 6985 Collamer Road

Type of Project:

☐ Division of Land ☐ Subdivision ☐ Accessory Use ☐ Zone Change ☒ Site Review ☐ Other _____

Developer: N/A

Phone: _____

Address: _____

Zip: _____

Tax Map Number(#)/s: 036.-01-04.0

Present Zoning: Commercial Dist. A / 1 Desired Zoning: no change

Total Acreage: _____

Total Number of Lots: _____

Property Owner/s: Stephen G. Byer

Phone: 315-422-0314

Address: c/o Germain & Germain

p: _____

Tax Map#(s): same

Owner's Signature: _____

Printed Name: (seller)

Property Owner/s: WJC Works, LLC

Phone: _____

Address: 112 Pickard Drive, Syracuse, NY

Zip: 13211

Tax Map#(s): same

Owner's Signature: Matt Van Gen, atty for buyer

Printed Name: Joe Woodward (buyer)

Use next page for additional known property owners' information

Planning Board Meeting Date Assignment: _____

Fee: _____

Paid: _____

Per: ☐ Credit/Debit Card ☐ Check ☐ Cash

617.20
Appendix B
Short Environmental Assessment Form

Instructions for Completing

Part 1 - Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 - Project and Sponsor Information																		
Name of Action or Project: Purchase of 6985 Collamer Road																		
Project Location (describe, and attach a location map): 036.-01-04.0																		
Brief Description of Proposed Action: Purchase of 6985 Collamer Rd, a commercial property from Alan Byer Volvo / Stephen Byer, by WJC Works, LLC (Joe Woodward, sole member)																		
Name of Applicant or Sponsor: Melvin & Melvin for Woodward		Telephone: 315-422-1311 E-Mail: mvanryn@melvinlaw.com																
Address: 217 S. Salina St, 7th floor																		
City/PO: Syracuse		State: NY	Zip Code: 13202															
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.			<table border="1" style="width: 100%;"><tr><td style="width: 50%;">NO</td><td style="width: 50%;">YES</td></tr><tr><td style="text-align: center;">☐</td><td style="text-align: center;">☐</td></tr></table>	NO	YES	☐	☐											
NO	YES																	
☐	☐																	
2. Does the proposed action require a permit, approval or funding from any other governmental Agency? If Yes, list agency(s) name and permit or approval: Greater Syr. BDC - secondary lender - SBA loan			<table border="1" style="width: 100%;"><tr><td style="width: 50%;">NO</td><td style="width: 50%;">YES</td></tr><tr><td style="text-align: center;">☐</td><td style="text-align: center;">☒</td></tr></table>	NO	YES	☐	☒											
NO	YES																	
☐	☒																	
3.a. Total acreage of the site of the proposed action? 2.81 acres																		
b. Total acreage to be physically disturbed? 0 acres																		
c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor? 2.81 acres																		
4. Check all land uses that occur on, adjoining and near the proposed action. <table style="width: 100%;"><tr><td>☐ Urban</td><td>☐ Rural (non-agriculture)</td><td>☐ Industrial</td><td>☒ Commercial</td><td>☐ Residential (suburban)</td></tr><tr><td>☐ Forest</td><td>☐ Agriculture</td><td>☐ Aquatic</td><td colspan="2">☐ Other (specify): _____</td></tr><tr><td>☐ Parkland</td><td colspan="4"></td></tr></table>				☐ Urban	☐ Rural (non-agriculture)	☐ Industrial	☒ Commercial	☐ Residential (suburban)	☐ Forest	☐ Agriculture	☐ Aquatic	☐ Other (specify): _____		☐ Parkland				
☐ Urban	☐ Rural (non-agriculture)	☐ Industrial	☒ Commercial	☐ Residential (suburban)														
☐ Forest	☐ Agriculture	☐ Aquatic	☐ Other (specify): _____															
☐ Parkland																		

	NO	YES	N/A
5. Is the proposed action, a. A permitted use under the zoning regulations?	☐	☒	☐
b. Consistent with the adopted comprehensive plan?	☐	☒	☐
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?	☐	☒	☐
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area? If Yes, identify: _____	☐	☒	☐
8. a. Will the proposed action result in a substantial increase in traffic above present levels?	☒	☐	☐
b. Are public transportation service(s) available at or near the site of the proposed action?	☐	☒	☐
c. Are any pedestrian accommodations or bicycle routes available on or near site of the proposed action?	☐	☐	☐
9. Does the proposed action meet or exceed the state energy code requirements? If the proposed action will exceed requirements, describe design features and technologies: _____	☒	☐	☐
10. Will the proposed action connect to an existing public/private water supply? If No, describe method for providing potable water: _____	☐	☒	☐
11. Will the proposed action connect to existing wastewater utilities? If No, describe method for providing wastewater treatment: <u>septic (tested)</u>	☐	☒	☐
12. a. Does the site contain a structure that is listed on either the State or National Register of Historic Places?	☒	☐	☐
b. Is the proposed action located in an archeological sensitive area?	☒	☐	☐
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?	☒	☐	☐
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody? If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres: _____	☒	☐	☐
14. Identify the typical habitat types that occur on, or are likely to be found on the project site. Check all that apply: ☐ Shoreline ☐ Forest ☐ Agricultural/grasslands ☐ Early mid-successional ☐ Wetland ☐ Urban ☒ Suburban			
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or Federal government as threatened or endangered?	☒	☐	☐
16. Is the project site located in the 100 year flood plain?	☒	☐	☐
17. Will the proposed action create storm water discharge, either from point or non-point sources? If Yes, a. Will storm water discharges flow to adjacent properties? ☐ NO ☐ YES b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)? ☐ NO ☐ YES If Yes, briefly describe: <u>No changes to existing site. Paved parking area but sufficient unpaved adjacent land for run-off. See site plan.</u>	☒	☐	☐

not sure

18. Does the proposed action include construction or other activities that result in the impoundment of water or other liquids (e.g. retention pond, waste lagoon, dam)? If Yes, explain purpose and size: _____	NO	YES
	☒	☐
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility? If Yes, describe: _____	NO	YES
	☒	☐
20. Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or completed) for hazardous waste? If Yes, describe: <u>soil remediation was done in 2015, recent testing (Phase 2) by proposed buyer Woodward shows soil is clean and uncontaminated.</u>	NO	YES
	☐	☒
I AFFIRM THAT THE INFORMATION PROVIDED ABOVE IS TRUE AND ACCURATE TO THE BEST OF MY KNOWLEDGE		
Applicant/sponsor name: <u>Matthew Van Ryn, Melvin + Melvin</u> Date: <u>Jan 16, 2020</u>		
Signature: <u>Matt Van Ryn</u>		

STOP

Part 2 - Impact Assessment. The Lead Agency is responsible for the completion of Part 2. Answer all of the following questions in Part 2 using the information contained in Part 1 and other materials submitted by the project sponsor or otherwise available to the reviewer. When answering the questions the reviewer should be guided by the concept "Have my responses been reasonable considering the scale and context of the proposed action?"

	No, or small impact may occur	Moderate to large impact may occur
1. Will the proposed action create a material conflict with an adopted land use plan or zoning regulations?	☐	☐
2. Will the proposed action result in a change in the use or intensity of use of land?	☐	☐
3. Will the proposed action impair the character or quality of the existing community?	☐	☐
4. Will the proposed action have an impact on the environmental characteristics that caused the establishment of a Critical Environmental Area (CEA)?	☐	☐
5. Will the proposed action result in an adverse change in the existing level of traffic or affect existing infrastructure for mass transit, biking or walkway?	☐	☐
6. Will the proposed action cause an increase in the use of energy and it fails to incorporate reasonably available energy conservation or renewable energy opportunities?	☐	☐
7. Will the proposed action impact existing:	☐	☐
a. public / private water supplies?	☐	☐
b. public / private wastewater treatment utilities?	☐	☐
8. Will the proposed action impair the character or quality of important historic, archaeological, architectural or aesthetic resources?	☐	☐
9. Will the proposed action result in an adverse change to natural resources (e.g., wetlands, waterbodies, groundwater, air quality, flora and fauna)?	☐	☐

	No, or small impact may occur	Moderate to large impact may occur
10. Will the proposed action result in an increase in the potential for erosion, flooding or drainage problems?	☐	☐
11. Will the proposed action create a hazard to environmental resources or human health?	☐	☐

Part 3 - Determination of significance. The Lead Agency is responsible for the completion of Part 3. For every question in Part 2 that was answered "moderate to large impact may occur", or if there is a need to explain why a particular element of the proposed action may or will not result in a significant adverse environmental impact, please complete Part 3. Part 3 should, in sufficient detail, identify the impact, including any measures or design elements that have been included by the project sponsor to avoid or reduce impacts. Part 3 should also explain how the lead agency determined that the impact may or will not be significant. Each potential impact should be assessed considering its setting, probability of occurring, duration, irreversibility, geographic scope and magnitude. Also consider the potential for short-term, long-term and cumulative impacts.

☐	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action may result in one or more potentially large or significant adverse impacts and an environmental impact statement is required.
☐	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action will not result in any significant adverse environmental impacts.
Name of Lead Agency Date	
Print or Type Name of Responsible Officer in Lead Agency Title of Responsible Officer	
Signature of Responsible Officer in Lead Agency Signature of Preparer (if different from Responsible Officer)	

PRINT



Property Description Report For: 6985 Collamer Rd, Municipality of Town of Manlius

No Photo Available

Status: Active
Roll Section: Taxable
Swis: 313889
Tax Map ID #: 036.-01-04.0
Property #:
Property Class: 433 - Auto body
Site: COM 1
In Ag. District: No
Site Property Class: 433 - Auto body
Zoning Code: CA
Neighborhood Code: 00500
School District: E. Syracuse-Minoa
Total Assessment: 2019 - \$269,000
Property Desc: Fl 13
Deed Page: 933
Grid North: 1133682

Total Acreage/Size: 2.81
Land Assessment: 2019 - \$53,800
Full Market Value: 2019 - \$269,000
Equalization Rate: ----
Deed Book: 5377
Grid East: 645299

Owners

Stephen G Byer
 1230 W Genesee St
 Syracuse NY 13204

Randy Capriotti

Sales

Sale Date	Price	Property Class	Sale Type	Prior Owner	Value Usable	Arms Length	Addl. Parcels	Deed Book and Page
6/22/2016	\$195,500	433 - Auto body	Land & Building	Sutor, Pauline	No	No	No	5377/933
2/13/2003	\$230,000	433 - Auto body	Land & Building	Vaught, Glenn C	Yes	Yes	No	4766/477

Utilities

Sewer Type: Private
Water Supply: Comm/public
Utilities: Gas & elec

Inventory

Overall Eff Year Built: 0
Overall Condition: Normal
Overall Grade: Average
Overall Desirability: 3

Buildings

AC%	Sprinkler%	Alarm%	Elevators	Basement Type	Year Built	Condition	Quality	Gross Floor Area (sqft)	Stories
0	0	0	0		1970	Normal	Average-	7200	1

Improvements

Structure	Size	Grade	Condition	Year
Fence-chn lk	480 × 6	Average	Fair	1965
Pavng-asphlt	15000 × 4	Average	Normal	1965

Special Districts for 2019

Description	Units	Percent	Type	Value
LT001-Manl cons lgt dis #1	0	0%		0
WR001-Manl cons water dist	1	0%		0
FR004-Minoa fire	0	0%		0
CWR40-County water	0	0%		0


Exemptions

Year	Description	Amount	Exempt %	Start Yr	End Yr	V Flag	H Code	Own %
------	-------------	--------	----------	----------	--------	--------	--------	-------

Taxes


Year	Description	Amount
------	-------------	--------

*** Taxes reflect exemptions, but may not include recent changes in assessment.**



Stone circle
traffic divider
at entrance

Google Maps 6985 Collamer Rd



DUMPSTER

SNOW

stone

entrance

decoration/
traffic divider

(see attached)

Imagery ©2020 Maxar Technologies, New York GIS, Map data ©2020

50 ft



RELIANCE LETTER

January 8, 2020

To: Greater Syracuse Business Development Corporation
101 South Salina Street #10
Suite 1030
Syracuse, New York 13202

and

U.S. Small Business Administration ("SBA")

Re: Borrower Name: CNY Racing
Project Address ("Property"): 6985 Collamer Road, East Syracuse, New York 13057
Environmental Investigation Report Number(s): 19-290 Groundwater Sampling Report

Dear Lender and SBA:

Richard D. McKenna ("Environmental Professional") meets the definition of an Environmental Professional as defined by 40 C.F.R. § 312.10(b) and has performed or supervised the performance of the following "Environmental Investigation(s)" (check all that apply):

☐ A Transaction Screen of the Property dated _____, 20____, and any addendum(s) thereto, conducted in accordance with ASTM International's most recent standard (currently ASTM E1528-14);

☐ A Phase I (or an Updated Phase I) Environmental Site Assessment of the Property dated _____, 20____, and any addendum(s) thereto, conducted in accordance with ASTM International's most recent standard (currently ASTM E1527-13). In addition, the Environmental Professional has addressed the performance of the "additional inquiries" set forth at 40 C.F.R. § 312.22;

☒ A Phase II Environmental Site Assessment of the Property dated January 8, 2020, and any addendum(s) thereto, conducted in accordance with generally-accepted industry standards of practice and consisting of a scope of work that would be considered reasonable and sufficient to identify the presence, nature and extent of a Release as it impacts the Property.

Reliance by SBA and Lender. Environmental Professional (and Environmental Professional's firm, where applicable) understand(s) that the Property may serve as collateral for an SBA guaranteed loan, a condition for which is an Environmental Investigation of the Property by an Environmental Professional. Environmental Professional (and Environmental Professional's firm, where applicable) authorize(s) Lender and SBA to use and rely upon the Environmental Investigation. Further, Environmental

RELIANCE LETTER

Borrower Name: CNY Racing

Project Address ("Property"): 6985 Collamer Road, East Syracuse, New York 13057

Professional (and Environmental Professional's firm, where applicable) authorize(s) Lender and SBA to release a copy of the Environmental Investigation to the borrower for information purposes only. This letter is not an update or modification to the Environmental Investigation. Environmental Professional (and Environmental Professional's firm, where applicable) makes no representation or warranty, express or implied, that the condition of the Property on the date of this letter is the same or similar to the condition of the Property described in the Environmental Investigation.

Insurance Coverage. Environmental Professional (and/or Environmental Professional's firm, where applicable) certifies that he or she or the firm was covered as of the date of the Environmental Investigation by errors and omissions liability insurance with a minimum coverage of \$1,000,000 per claim (or occurrence) and that evidence of this insurance is attached. As to the Lender and SBA, Environmental Professional (and Environmental Professional's firm, where applicable) specifically waive(s) any dollar amount limitations on liability up to \$1,000,000 as well as any time limitations on liability, other than state or Federal statutes of limitation.

Waiver of Right to Indemnification. Environmental Professional and Environmental Professional's firm waive any right to indemnification from the Lender and SBA.

Impartiality. Environmental Professional certifies that (1) to the best of his or her knowledge, Environmental Professional is independent of and not a representative, nor an employee or affiliate of seller, borrower, operating company, or any person in which seller has an ownership interest; and (2) the Environmental Professional has not been unduly influenced by any person with regard to the preparation of the Environmental Investigation or the contents thereof.

Acknowledgment. The undersigned acknowledge(s) and agree(s) that intentionally falsifying or concealing any material fact with regard to the subject matter of this letter or the Environmental Investigations may, in addition to other penalties, result in prosecution under applicable laws including 18 U.S.C. § 1001.



Environmental Professional

Printed Name: Richard D. McKenna



Signature of representative of firm who is authorized to sign this letter

Printed Name & Title: Bryan Bowers, President

Name of Environmental Firm: Asbestos & Environmental Consulting Corporation

Enclosure: Evidence of Insurance



CERTIFICATE OF LIABILITY INSURANCE

DATE (MM/DD/YYYY)

9/9/2019

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED REPRESENTATIVE OR PRODUCER, AND THE CERTIFICATE HOLDER.

IMPORTANT: If the certificate holder is an ADDITIONAL INSURED, the policy(ies) must have ADDITIONAL INSURED provisions or be endorsed. If SUBROGATION IS WAIVED, subject to the terms and conditions of the policy, certain policies may require an endorsement. A statement on this certificate does not confer rights to the certificate holder in lieu of such endorsement(s).

PRODUCER OneGroup NY, Inc. 169 Main St. Oneida NY 13421	CONTACT NAME: Denise Conti, CISR, CRIS, MLIS	
	PHONE (A/C, No, Ext): (315) 280-6322 FAX (A/C, No): (315) 363-2183	
	E-MAIL ADDRESS: DConti@OneGroup.com	
	INSURER(S) AFFORDING COVERAGE	NAIC #
	INSURER A: Stratford Insurance Company	40436
	INSURER B: Travelers Casualty Ins. Comp. of Amer.	19046
	INSURER C:	
	INSURER D:	
	INSURER E:	
	INSURER F:	

INSURED
Asbestos & Environmental Consulting Corporation
Bowers Realty, LLC
Bowers Development, LLC
6308 Fly Road
East Syracuse NY 13057

ASBEN

COVERAGES**CERTIFICATE NUMBER:** 1244595063**REVISION NUMBER:**

THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED. NOTWITHSTANDING ANY REQUIREMENT, TERM OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.

INSR LTR	TYPE OF INSURANCE	ADDL INSD	SUBR WVD	POLICY NUMBER	POLICY EFF (MM/DD/YYYY)	POLICY EXP (MM/DD/YYYY)	LIMITS
A	☒ COMMERCIAL GENERAL LIABILITY ☐ CLAIMS-MADE ☒ OCCUR 5,000 GEN'L AGGREGATE LIMIT APPLIES PER: ☐ POLICY ☒ PROJECT ☒ LOC OTHER:	Y	Y	EVP100187301	9/8/2019	9/8/2020	EACH OCCURRENCE \$ 1,000,000 DAMAGE TO RENTED PREMISES (Ea occurrence) \$ 50,000 MED EXP (Any one person) \$ 10,000 PERSONAL & ADV INJURY \$ 1,000,000 GENERAL AGGREGATE \$ 2,000,000 PRODUCTS - COMP/OP AGG \$ 2,000,000 \$
B	☒ AUTOMOBILE LIABILITY ☒ ANY AUTO OWNED AUTOS ONLY ☐ SCHEDULED AUTOS ☒ HIRED AUTOS ONLY ☒ NON-OWNED AUTOS ONLY	Y	Y	BA5N8767681942G	9/8/2019	9/8/2020	COMBINED SINGLE LIMIT (Ea accident) \$ 1,000,000 BODILY INJURY (Per person) \$ BODILY INJURY (Per accident) \$ PROPERTY DAMAGE (Per accident) \$ \$
A	☐ UMBRELLA LIAB ☒ OCCUR ☒ EXCESS LIAB ☐ CLAIMS-MADE DED ☒ RETENTION \$ 0	Y	Y	EVX100187401	9/8/2019	9/8/2020	EACH OCCURRENCE \$ 5,000,000 AGGREGATE \$ 5,000,000 \$
	WORKERS COMPENSATION AND EMPLOYERS' LIABILITY ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) If yes, describe under DESCRIPTION OF OPERATIONS below	Y/N	N/A				PER STATUTE ☐ OTH-ER ☐ E.L. EACH ACCIDENT \$ E.L. DISEASE - EA EMPLOYEE \$ E.L. DISEASE - POLICY LIMIT \$
A	Professional Liability Contractors Pollution Liability	Y	Y	EVP100187301	9/8/2019	9/8/2020	Each Claim \$1,000,000 Each Occurrence \$1,000,000 Aggregate \$2,000,000

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required)
See Attached...

CERTIFICATE HOLDER**CANCELLATION**

Asbestos & Environmental Consulting Corporation
6308 Fly Road
East Syracuse NY 13057

SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.

AUTHORIZED REPRESENTATIVE

© 1988-2015 ACORD CORPORATION. All rights reserved.



GROUNDWATER SAMPLING REPORT

Former G&G Collision
6985 Collamer Road
East Syracuse, New York

Original: January 7, 2020
Revised January 8, 2020

Prepared by:

Asbestos and Environmental Consulting Corporation
6308 Fly Road
East Syracuse, New York 13057

Prepared for:

CNY Racing
112 Pickard Drive East
Syracuse, New York 13211

TABLE OF CONTENTS

1.0	INTRODUCTION	1
1.1	PROJECT HISTORY.....	1
1.3	LIMITATIONS AND STANDARD OF CARE.....	2
2.0	INVESTIGATION METHODOLOGY	2
2.1	SEPTIC SYSTEM LOCATION.....	2
2.2	GROUNDWATER WELL DEVELOPMENT	2
2.3	GROUNDWATER SAMPLING.....	3
3.0	FIELD OBSERVATIONS.....	3
3.2	SEPTIC SYSTEM LOCATION.....	3
3.2	GROUNDWATER WELL DEVELOPMENT	3
3.3	GROUNDWATER SAMPLING.....	3
4.0	LABORATORY ANALYTICAL RESULTS	3
5.0	SUMMARY AND CONCLUSIONS.....	4

FIGURES

FIGURE 1 SITE PLAN

TABLES

TABLE 1	SUMMARY OF ANALYTICAL DATA – GROUNDWATER (VOCs)
TABLE 2	SUMMARY OF ANALYTICAL DATA – GROUNDWATER (SVOCs)
TABLE 3	SUMMARY OF ANALYTICAL DATA – GROUNDWATER (METALS)

ATTACHMENTS

ATTACHMENT A	SITE PHOTOGRAPHS
ATTACHMENT B	LABORATORY ANALYTICAL REPORT
ATTACHMENT C	NYSDEC “NO FURTHER ACTION” LETTER

GROUNDWATER SAMPLING REPORT
Former G&G Collision, 6985 Collamer Road, East Syracuse, New York

COMMON ACRONYMS / ABBREVIATIONS

bgs – Below Ground Surface
° C – Degrees Celsius
CP-51 – (NYSDEC) Commissioner’s Policy #51 (for Soil Cleanup Guidance)
CREC – Controlled Recognized Environmental Condition
DEC – Department of Environmental Conservation
DO – Dissolved Oxygen
EPA – Environmental Protection Agency
ESA – Environmental Site Assessment
GWS – Groundwater Standard
L – Liter
LSI – Limited Subsurface Investigation
N/A – Not Applicable
NYSDEC – New York State Department of Environmental Conservation
PAH – Polycyclic Aromatic Hydrocarbons
pH – Unit-less measure of Acidity (Scale of 0 to 14, a pH of 7 is ‘neutral’)
PID – Photoionization Detector
ppb – Parts Per Billion
ppm – Parts Per Million
REC – Recognized Environmental Condition
RSCO – Restricted Soil Cleanup Objective
SCO – Soil Cleanup Objective
SVOC – Semi-Volatile Organic Compound
TOGS – Technical & Operational Guidance Series 1.1.1 (NYSDEC)
USEPA – United States Environmental Protection Agency
UST – Underground Storage Tank
VOC – Volatile Organic Compound

GROUNDWATER SAMPLING REPORT

Former G&G Collision, 6985 Collamer Road, East Syracuse, New York

1.0 INTRODUCTION

The Asbestos & Environmental Consulting Corporation (AECC) performed environmental consulting services and a groundwater sampling event at the former G&G Collision site located at 6985 Collamer Road in East Syracuse, New York. AECC performed this work under contract to the prospective purchaser, CNY Racing. The property is currently a vacant automobile collision repair facility.

1.1 PROJECT HISTORY

Review of Previous Environmental Documentation

AECC reviewed the following environmental documents provided by the Client:

- A December 6, 2019 Phase I Environmental Site Assessment (ESA) report, prepared by Labella Associates. The report concluded that former use of the Site as an automobile repair facility with a septic system was a Recognized Environmental Condition. The report also made reference to a prior Phase II ESA report, but Labella did not review the Phase II ESA report before submission of their Phase I ESA report.
- The Client obtained a copy of the referenced Phase II ESA report (Limited and Focused Subsurface Soil & Groundwater Investigation Report, prepared by LCS in September 2015). The review of the report revealed the following information:
 - The subject property had been utilized as an automotive repair facility and collision shop since at least the 1960s. Evidence of one active in-ground hydraulic lift and two former in-ground hydraulic lifts was noted within the automotive repair area of the subject structure. The subject property is serviced by a private septic system.
 - Twelve soil borings were advanced at the Site, including in areas adjacent to the hydraulic lifts, around the perimeter of the building, in the vicinity of the septic system, and in a filled area in the rear portion of the Site. Fill material was observed in all 12 borings.
 - PID readings above background were observed in a majority of the borings. Elevated PID readings were observed in one boring near the rear wall of the building. Laboratory analysis did not detect concentrations of volatile organic compounds (VOCs) above applicable State standards. Laboratory analysis detected a limited number of semi-volatile organic compounds (SVOCs) at concentrations above applicable State standards in some soil borings advanced in the fill material in the rear of the Site.
 - One groundwater monitoring well was installed downgradient of the septic leach field. No groundwater impacts were observed.

In response to the elevated concentrations of SVOCs, LCS called the NYSDEC spill hotline, and a spill file (15-06353) was opened for the Site. The NYSDEC closed the spill file two weeks later. AECC recently interviewed Mr. Daniel LaSalle, the NYSDEC spill file manager. According to Mr. LaSalle, the spill file was closed since the contamination appeared to be associated with fill material (instead of a spill of petroleum) and there was no apparent risk to human health or the environment.

After the Client discussed the LCS report with M&T Bank, the bank stated in an e-mail that “the bank would also need to know where the septic tank is and make sure there is no groundwater contamination”.

GROUNDWATER SAMPLING REPORT

Former G&G Collision, 6985 Collamer Road, East Syracuse, New York

1.3 LIMITATIONS AND STANDARD OF CARE

This report has been prepared on behalf of, and for the exclusive use of CNY Racing, for the stated purposes and locations identified in this report. This report may be relied upon by the following third-party entities:

- M&T Bank
- United States Small Business Administration
- Greater Syracuse Business Development Corporation

This report is not intended to be used or relied upon in connection with other projects or by other unidentified third parties. The use of this report by any undesignated third party or parties will be at such party's sole risk, and AECC and CNY Racing disclaim liability for any such third party use or reliance.

Our findings and conclusions are based on information obtained from on-site field investigation and analytical services performed under the contract, in the location and depths the samples were obtained. This Limited Subsurface Investigation was performed in accordance with the Scope of Services, as reflected in our proposal dated December 27, 2019.

Our services were performed in a manner consistent with generally accepted practices of environmental consulting services undertaken for a groundwater sampling event for the property location and based on readily available information about the property. Our services were performed using the degree of skill and care ordinarily exercised by qualified professionals performing the same type of services, at the same time, under similar conditions, at the same or a similar property. No warranty, expressed or implied, is made.

Specifically, we do not and cannot represent that the site contains no hazardous material, petroleum, or other latent condition beyond what was encountered and evaluated by our investigation.

2.0 INVESTIGATION METHODOLOGY

The following activities were conducted from December 23 -27, 2019.

2.1 SEPTIC SYSTEM LOCATION

The Client hired a septic service contractor to locate the septic tank and access port, and to determine the general location of the associated leach field. AECC observed the Client's contractor and obtained measurements of the location of the tank access port and other associated system components (in relation to Site landmarks). These measurements are provided on the attached Figure 1, and photographs of the septic system components are presented in Attachment A.

2.2 GROUNDWATER WELL DEVELOPMENT

The existing well was located and developed to determine if it was in a workable condition and remained viable. AECC utilized purge-and-surge methods with a bailer to disturb and suspend sediment within the water column. AECC then removed the silty water with the bailer for approximately 15 minutes. The location of the well is depicted on the attached Figure 1, and a photograph of the well in relation to Site features is presented in Attachment A.

GROUNDWATER SAMPLING REPORT
Former G&G Collision, 6985 Collamer Road, East Syracuse, New York

2.3 GROUNDWATER SAMPLING

The well was allowed to “rest” for approximately 48 hours. In order to purge the well, approximately 3 well volumes were removed from the well with a bailer.

Samples were collected from the well, dispensed into laboratory-prepared containers, and sent to the laboratory for analysis. The samples were analyzed for Target Compound List (TCL) VOCs via EPA Method 8260, Base/Neutral SVOCs via EPA Method 8270, and RCRA 8 heavy metals by EPA Methods 6010/7470.

The well installation was left in-place after sampling.

3.0 FIELD OBSERVATIONS

3.2 SEPTIC SYSTEM LOCATION

AECC determined that the existing groundwater well is ideally-located downgradient and in the vicinity of the septic leach field.

3.2 GROUNDWATER WELL DEVELOPMENT

The temporary monitoring well appeared to be constructed of a 12-foot section of one-inch diameter PVC with a plastic cap on top. The screened interval of the well is not known. The well was loosely set in the borehole, which is indicative of a well that was not constructed with grout or sandpack.

The groundwater level was approximately 3.5 feet below ground surface (bgs). AECC observed that the silty water within the well was reddish-brown in color, and that the well recovery rate was satisfactory. After approximately 5 minutes of bailing, the majority of silt had been removed from the well. No odors or sheens were observed.

3.3 GROUNDWATER SAMPLING

The groundwater level was approximately 3.5 feet bgs. It was observed that the water was slightly turbid with a yellow/orange color. No odors or sheens were observed. No drawdown during purging was observed.

4.0 LABORATORY ANALYTICAL RESULTS

Groundwater analytical results were compared with the NYSDEC groundwater standards and guidance values published in the NYSDEC Division of Water Technical and Operations Guidance Series (TOGS) Memorandum 1.1.1. Summary tables comparing the detected contaminant concentrations to the NYSDEC standards / guidance values are presented in the Tables section of this report. The complete laboratory analysis report is presented as Attachment B.

VOCs

Only one VOC, acetone, was detected by the laboratory. The concentration of acetone (1.7 micrograms per liter [µg/L]) was well below the applicable TOGS standard of 50 µg/L.

GROUNDWATER SAMPLING REPORT
Former G&G Collision, 6985 Collamer Road, East Syracuse, New York

SVOCs

A total of six SVOCs were detected by the laboratory.

Caprolactam was detected at a concentration of 24 µg/L. There is no groundwater standard for caprolactam.

The five remaining detected compounds (fluoranthene, benzo(b)fluoranthene, chrysene, phenanthrene, and pyrene) are compounds commonly known as polycyclic aromatic hydrocarbons (PAH). Two of the five PAH compounds were detected above their applicable TOGS standard (0.002 µg/L for each):

- Benzo(b)fluoranthene was detected at a concentration of 0.02 µg/L
- Chrysene was detected at a concentration of 0.01 µg/L

Metals

Of the eight metals analyzed for, five were detected by the laboratory. Arsenic was detected at a concentration of 49.9 µg/L, which exceeds its applicable TOGS ambient groundwater standard of 25 µg/L. The remaining four metals (barium, cadmium, chromium, and lead) were detected at concentrations that were less than their applicable TOGS ambient groundwater standards.

5.0 SUMMARY AND CONCLUSIONS

Based on the information derived from this LSI, the following conclusions have been drawn:

- The septic system and leach field were located. To assist with future access, the Client's contractor constructed a concrete riser over the tank access port, and topped with a metal cover at the surface.
- AECC determined that the existing groundwater well is ideally-located downgradient and in the vicinity of the septic leach field.
- Although PAH compounds were not detected during the 2015 sampling event, the laboratory reporting limits for that event were 20 times higher than the reporting limits for this (2019) event. The concentrations of PAH detected during this (2019) event would not have been detected by the laboratory performing the analysis for the 2015 sampling event.
- It is likely that the concentrations of PAH compounds and arsenic detected in groundwater are potentially biased high and are associated with the urban fill at the Site, rather than a petroleum spill/release, for the following reasons:
 - The collected sample was turbid. The contaminant concentrations may have been biased high due if the contaminants were adhered to the suspended solids.
 - No petroleum odors or sheens were observed during well development, purging, or sampling.
 - The PAH compounds were detected at relatively low concentrations (less than or within one order of magnitude of the applicable TOGS standards).
- Since the primary use of caprolactum is as a monomer for Nylon 6, it is likely that the detection is due to cross-contamination rather than an actual presence in groundwater.

GROUNDWATER SAMPLING REPORT

Former G&G Collision, 6985 Collamer Road, East Syracuse, New York

- It has been our experience that the concentrations of detected compounds are typical of sites with urban fill. Since potable water is provided by a municipal system, there are no apparent sensitive receptors in the area, and there will be no exposure to site groundwater associated with the planned operations at the Site (screen printing and embroidery), it is our professional opinion that no further investigation or remediation is warranted.
- On January 7, 2020, the NYSDEC issued a letter stating "Based on the Groundwater Sampling Report submitted by AECC, Inc., the Department has determined that no remedial actions are necessary at this time." A copy of the letter is presented as Attachment C.
- A copy of this report should be provided to the NYSDEC Region 7 Office, located at 615 Erie Boulevard West, Syracuse, New York 13204, so that the spill file can be updated.

If you should have any questions regarding the information presented in this report, please feel free to contact our corporate office (315) 432-9400 at your convenience. AECC appreciates the opportunity to work with you on this important project.

Sincerely,
Asbestos & Environmental Consulting Corporation



Richard D. McKenna
Senior Project Manager

November 15, 2019

Joe Woodworth
WJC Works LLC
6985 Collamer Road
East Syracuse, NY

**RE: \$242,688 Permanent Mortgage
\$194,150 Bridge Term Loan – SBA 504 Loan Program**

Dear Mr. Woodworth:

M&T Bank ("Bank") is pleased to advise you of its commitment to make available to **WJC Works LLC** ("Borrower") credit facilities in the aggregate maximum principal amount of **\$436,838** (collectively, the "Credit Facility") for the purpose, upon the terms, and subject to the conditions set forth in this letter and in each Summary of Terms and Conditions attached hereto and made part hereof (together, the "Commitment").

This Commitment includes only a brief description of the principal terms of the Credit Facility. The closing and extension of the Credit Facility is contingent upon the satisfactory completion, in the Bank's sole discretion, of all due diligence on the Borrower, any required guarantor(s) and any other relevant third parties, and the delivery to Bank of loan documentation evidencing and securing the proposed Credit Facility in form and substance satisfactory to Bank and its counsel, containing such terms, conditions, representations, warranties, covenants, default provisions and remedies as are appropriate for facilities of this type, size and purpose (collectively, the "Loan Documents").

Upon acceptance and execution of this Commitment by Borrower, Borrower shall pay to Bank non-refundable commitment fees totaling **\$250** (the "Commitment Fee"), duly earned by Bank upon such execution.

It is understood and agreed that this Commitment is further contingent upon there being no material adverse change in (i) the condition (financial or otherwise) of Borrower, any guarantor(s) or the collateral proposed to secure the Credit Facility, (ii) the constituent parties comprising Borrower and guarantor(s), (iii) any information or representations made in any of the materials submitted to Bank since the date any such information was submitted to Bank, or (iv) any change in law or regulation having a material effect on the Bank's ability to fund or service any portion of the Credit Facility in the manner contemplated as of the date hereof. This Commitment is made in reliance on the information received by Bank from Borrower and guarantor(s), and in supporting and related representations, discussions and material. Any misrepresentation or inaccuracy, or failure to supply Bank with any material information shall entitle Bank, in its sole discretion, to withdraw and/or cancel this Commitment. The Borrower will promptly advise the Bank, in writing, of any changes that could materially or adversely affect the Borrower's or any guarantor's financial condition.

Further, Borrower shall have delivered to Bank sufficiently in advance of closing, all information and documentation required by Bank to evidence or facilitate both the Borrower's and Bank's compliance with all applicable laws and regulations, including, without limitation, all "know your customer" rules in effect from time to time pursuant to the Bank Secrecy Act, the USA PATRIOT Act and other applicable laws. Any failure by Borrower or any necessary third party to deliver to Bank, in a timely manner, any material information or documentation requested, or any misrepresentation or inaccuracy with respect to any such information or documentation received, or if Bank reasonably determines that opening any account contemplated herein would potentially violate Bank's regulatory compliance policies or applicable law, shall permit Bank to withdraw or cancel this Commitment without liability.

The Commitment evidenced by this letter is for the benefit of the Borrower only and no other person may obtain any rights under this Commitment or be entitled to rely or claim reliance on this Commitment's terms and conditions. This Commitment may not be assigned by the Borrower without the Bank's prior written consent.

As part of the Credit Facility described in this Commitment and for the sole purpose of providing a lock on the fixed rate applying to the Credit Facility, Borrower may elect to enter into a Future Rate Lock Agreement ("Rate Lock") with M&T Bank. Please note that the Rate Lock is an agreement between the Borrower and M&T Bank and is not a security or other instrument that is tradable on an organized or over-the-counter market.

The Commitment evidenced by this letter is provided with the understanding that it shall not be disclosed to any person or entity other than the Borrower's accountants, attorneys and other professional advisors retained by Borrower in connection with the Credit Facility, except as such disclosure may be required by law. Any violations of the provisions of this paragraph shall, at the Bank's option, render the Commitment evidenced by this letter void.

The closing of the Credit Facility contemplated herein shall occur on or before **March 15, 2020** (the "Closing Date"), at such place as the Bank may designate, on or before which date definitive Loan Documents must be executed and delivered, and all terms and conditions for the initial funding under the Loan Documents must be met.

The Borrower shall pay all costs and expenses incurred by the Bank in connection with this Commitment and the Credit Facility, including without limitation, all due diligence costs and any counsel fees incurred in connection with the preparation, negotiation and delivery of this Commitment and the Loan Documents, and such payment shall be made upon demand, but no later than the earlier to occur of the Closing Date or the Commitment Termination Date (as defined below). The Borrower will reimburse the Bank for these expenses whether or not a closing occurs with respect to the proposed Credit Facility. The Borrower shall also pay the fees included on the attached Terms and Conditions.

Except as otherwise provided under federal law, this Commitment shall be governed by and be construed and enforced in accordance with the internal laws of the State/Commonwealth of **New York** without reference to conflicts or choice of law principles thereof.

No modification or waiver of any of the terms of this Commitment will be valid and binding unless agreed to in writing by the Bank. When accepted, this Commitment will constitute the entire agreement between the Bank and the Borrower concerning the Credit Facility, and shall replace all prior understandings, statements, negotiations and written materials relating to the Credit Facility. The terms and conditions of this Commitment shall not survive the closing of the Credit Facility, at which time the terms and conditions of the Loan Documents shall control and be determinative.

If the foregoing is satisfactory, kindly indicate your acceptance by signing the enclosed copy of this Commitment and returning to the Bank at the address noted below, one fully executed Commitment plus the Commitment Fee.

When accepted, this Commitment will evidence the intent of the parties to proceed in good faith with appropriate pre-closing due diligence and to finalize the terms, conditions and Loan Documents required in order to effectuate the Credit Facility referred to herein.

This Commitment shall automatically expire, and shall be null and void upon the earliest to occur of the following: (i) the Bank has not received a copy of this letter executed by you, within ten (10) days of the date hereof; and (ii) the Credit Facility has not closed on or before the Closing Date, which shall be deemed the "Commitment Termination Date". We may extend the Closing Date, in our sole discretion, provided such extension is in writing and, if so extended, the interest rates offered in connection with the Credit Facility have been adjusted to current market conditions. You acknowledge and agree that the Commitment Fee is non-refundable regardless of whether the Credit Facility closes.

We thank you for opportunity to work with you and to assist you in achieving your financial goals. If you have any questions please do not hesitate to contact the undersigned at (315)424-4038.

Sincerely,

M&T Bank

By: _____
Patrick Griffin, Banking Officer

THE FOREGOING COMMITMENT IS
ACCEPTED AND AGREED TO THIS
_____, 2018.

WJC Works LLC

By: _____
Name Title

Borrower's attorney: _____
Address: _____
Phone: _____

Exhibit to Commitment Letter dated November 15, 2019 to Borrower
SUMMARY OF TERMS AND CONDITIONS – Permanent Financing (Non-Construction)

BORROWER	WJC Works LLC
LENDER	M&T Bank (“Bank”)
FACILITY TYPE	Real Estate Loan (Non-Construction) (“Loan”)
PRINCIPAL AMOUNT	\$242,688
USE OF PROCEEDS	The proceeds of the Loan will be used for bridge financing as a part of an SBA 504 financing structure for the purchase of owner occupied real estate.
INTEREST RATE	The Interest Rate will be a fixed rate to be fixed two (2) days prior to closing based on M&T Bank’s ten (10) year Cost of Funds plus a margin. As of today, the rate would be 4.24%. Additional default interest rates and late fees will apply, as applicable.
TERM	Ten (10) years.
PAYMENTS / AMORTIZATION	Twenty (20) years with a balloon payment due on the maturity date. As an example, payments would be approximately \$1,502 per month, principal including interest.
PREPAYMENT PREMIUM	5% of any principal amount prepaid in the first year, declining 1% each year thereafter with a minimum premium allowance of 2%. Borrower will be permitted to prepay up to 10% of the outstanding principal balance annually without penalty.
GUARANTOR(S)	Unlimited personal guarantee of Joe Woodworth. Unlimited corporate guarantee of CNY Racing, LLC.
COLLATERAL	Recorded, first priority perfected: • mortgage or deed of trust lien on the real property commonly known as 6985 Collamer Road, East Syracuse, NY; (the “Land”), and all buildings, structures, additions and improvements, now existing or hereafter erected upon or made to the Property (“Improvements”), together with any and all easements, rights-of-way, privileges and appurtenances belonging or in any way appertaining thereto (collectively, the “Property”); • assignment of all of Borrower’s interest in all existing and future leases, rents, profits, subleases and agreements of sale of the Property, or any portion thereof, and all cash and other proceeds thereof, free and clear of all encumbrances not approved by Bank (the “Leases”).
REPRESENTATIONS AND WARRANTIES	Appropriate for facilities of this type, size and purpose.
DEPOSIT RELATIONSHIP	The Borrower shall maintain with the Bank its primary operating and deposit accounts.
CONDITIONS TO LENDING	Appropriate for facilities of this type, size and purpose including, but not limited to: Any and all information the Bank deems necessary to evaluate and perform its due diligence in compliance with the terms and requirements of the Loan Agreement. Payments to be automatically deducted from an M&T Bank account. Subject to the approval of the SBA 504 Loan Program and satisfaction of all terms and conditions of that approval. M&T Bank attorney required to close this loan at the Borrower’s expense. UCC search is required. Final approval is conditioned upon the approval of the GSBDC financing as part of the SBA 504 program.
FINANCIAL REPORTING; AUDITS; FINANCIAL CONTROLS OR OTHER COVENANTS	Annual submission of year – end financial statements from WJC Works LLC and CNY Racing, LLC. Annual submission of personal tax returns and personal financial statements from Joe Woodworth.
EVENTS OF DEFAULT AND REMEDIES AFTER DEFAULT	Appropriate for facilities of this type, size and purpose, including, but not limited to, confession of judgment (to the extent applicable under the Governing Law).
EXPENSES	The Borrower or the Guarantor, as the case may be, shall pay all reasonable out-of-pocket expenses of the Bank related to this proposed transaction, including, but not limited to counsel fees.
GOVERNING LAW	New York
FEES	Commitment Fee - \$250

REAL ESTATE LOAN: ADDITIONAL CONDITIONS	
Appraisal	At Borrower's expense, Bank will engage an appraisal firm to conduct an appraisal of the Property. The appraisal must be acceptable to Bank in all respects; including but not limited to a resulting loan to value ratio not to exceed 50%.
Title Insurance	Prior to Closing, a title commitment or title binder issued by a title insurance company acceptable to Bank (the "Title Company") pursuant to which the Title Company will issue to Bank, on the Closing Date, a mortgagee's policy of title insurance acceptable to Bank, insuring the appropriate mortgage or deed of trust, in the maximum principal amount of the Loan, as a valid first lien upon the Property in form and substance acceptable to the Bank.
Flood Insurance	If Bank determines, at Borrower's expense, at any time that any part of the Improvements is located in an area located in a special flood hazard area, Borrower will obtain and maintain a flood insurance policy, with a generally acceptable insurance carrier, in an amount satisfactory to Bank.
Hazard Insurance	Borrower will also need to procure hazard insurance with extended coverage insuring the Property in at least the amount of the mortgage loan with a standard New York mortgagee clause, naming M&T Bank as Mortgagee. Evidence of insurance coverage satisfactory to us needs to be furnished prior to closing.
Environmental Testing and Indemnification	At Borrower's expense, Bank will engage an environmental consulting firm to perform and submit to Bank all required environmental assessments of the Property, as may be required by the Bank in its reasonable discretion, the results of which must be acceptable to Bank. Borrower will authorize the property inspection by signing Bank's standard Authorization, Waiver and Indemnification Agreement. In addition, Borrower and Guarantor(s), if any, shall sign Bank's standard environmental indemnification agreement ("Indemnity Agreement"), indemnifying Bank for any environmental costs and liabilities relating to the Property.
Asbestos	Borrower will certify that buildings located on the Property do not include any materials containing asbestos, or if unable to do so, Bank may require suitable testing of the Property, at Borrower's expense, as a condition to the making the loan, or Bank may terminate the Commitment.
Opinion	If required by the Bank, Borrower will cause to be delivered to Bank an Opinion of Borrower's counsel acceptable to Bank in Bank's sole discretion.
Compliance with Governmental and Other Requirements	Borrower will certify and/or furnish evidence establishing that the Property, the Improvements and its use comply with all applicable zoning, subdivision, environmental, fire safety, building and other governmental laws, ordinances, codes, regulations and orders.
Tax Monitoring	Tax monitoring is required; fee to be paid by Borrower.
Escrow	Required.

Exhibit to Commitment Letter dated November 15, 2019 to Borrower
SUMMARY OF TERMS AND CONDITIONS

BORROWER	WJC Works LLC
LENDER	M&T Bank ("Bank")
FACILITY TYPE	Term Loan ("Loan")
PRINCIPAL AMOUNT	\$194,150
USE OF PROCEEDS	Proceeds to provide bridge financing as a part of an SBA 504 financing structure for the purchase of owner occupied real estate.
INTEREST RATE	The Interest Rate will be a floating rate based on M&T Bank's Prime Rate (provided that WSJ Prime will apply for certain facilities as required by law). Additional default interest rates and late fees will apply, as applicable.
TERM	Twelve (12) months.
AMORTIZATION/PAYMENTS	Interest only monthly with the balance to be taken out by the GSBDC SBA 504 loan program.
PREPAYMENT PREMIUM	No prepayment premium.
GUARANTOR(S)	Unlimited personal guarantee of Joe Woodworth. Unlimited corporate guarantee of CNY Racing, LLC.
COLLATERAL	Recorded, second priority perfected: •mortgage or deed of trust lien on the real property commonly known as 6985 Collamer Road, East Syracuse, NY; (the "Land"), and all buildings, structures, additions and improvements, now existing or hereafter erected upon or made to the Property ("Improvements"), together with any and all easements, rights-of-way, privileges and appurtenances belonging or in any way appertaining thereto (collectively, the "Property"); •assignment of all of Borrower's interest in all existing and future leases, rents, profits, subleases and agreements of sale of the Property, or any portion thereof, and all cash and other proceeds thereof, free and clear of all encumbrances not approved by Bank (the "Leases").
REPRESENTATIONS AND WARRANTIES	Appropriate for facilities of this type, size and purpose.
DEPOSIT RELATIONSHIP	The Borrower shall maintain with the Bank its primary operating and deposit accounts.
CONDITIONS TO LENDING	Appropriate for facilities of this type, size and purpose including, but not limited to: Payments to be automatically deducted from an M&T Bank account. Any and all information the Bank deems necessary to evaluate and perform its due diligence in compliance with the terms and requirements of the Loan Agreement. Subject to the approval of the SBA 504 Loan Program and satisfaction of all terms and conditions of that approval. Loan to close concurrently with the \$242,688 commercial mortgage. All other terms and conditions approved concurrent with the permanent financing will apply to this term loan. M&T Bank attorney required to close this loan at the Borrower's expense.
FINANCIAL REPORTING; AUDITS; FINANCIAL COVENANTS	Appropriate for facilities of this type, size and purpose.
EVENTS OF DEFAULT AND REMEDIES AFTER DEFAULT	Appropriate for facilities of this type, size and purpose, including, but not limited to, confession of judgment (to the extent applicable under the Governing Law).
EXPENSES	The Borrower or the Guarantor, as the case may be, shall pay all reasonable out-of-pocket expenses of the Bank related to this proposed transaction, including, but not limited to counsel fees.
GOVERNING LAW	New York
OPINION	If required by the Bank, Borrower will cause to be delivered to Bank an Opinion of Borrower's counsel acceptable to Bank in Bank's sole discretion.
FEES	Waived
ESCROW	Required.

These Summaries of Terms and Conditions are for Borrower's confidential use only. The terms and conditions contained herein may not be disclosed by Borrower or any other person or entity, without Lender's prior written consent, to any person or entity (including any financial institution) other than the accountants, attorneys and other advisors to Borrower, and then only on a confidential basis in connection with the proposed transactions contemplated by the Summary of Terms and Conditions or the Commitment Letter of which it is a part.

TOWN OF MANLIUS

DISCLOSURE AFFIDAVIT

This affidavit is a part of and must be completed and attached to every application, petition, request submitted for a *site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit.*

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

I. Matt Van Ryn, being duly sworn, deposes and says that (s) he is:
attorneys of record for buyer/petitioner
(applicant, petitioner, corporation officer, property owner, etc.)

II. That deponent has read and is familiar with the provisions of the General
Municipal Law, Section 809 which states:

- A. Every application, petition or request submitted for a site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit, pursuant to the provisions or any ordinance, local law, rule or regulation constituting the zoning and planning regulations of a municipality shall state the name, residence and the nature and extent of the interest of any state officer or any officer or employee of such municipality is a part, in the person, partnership or association making such application, petition or request (hereinafter called the applicant) to the extent known to such applicant.
- B. For the purpose of this action an officer or employee shall be deemed to have an interest in the applicant when (s)he, his/her spouse, or their brothers, sisters, parents, children, grandchildren, or the spouse of any of them:
- 1) is the applicant, or
 - 2) is an officer, director, partner or employee of the applicant, or
 - 3) legally or beneficially owns or controls stock of a corporate applicant or is a member of a partnership or association applicant, or
 - 4) is a party to an agreement with such an applicant, express or implied, whereby (s) he may receive any payment or other benefit, whether or not for services rendered, or contingent upon the favorable approval of such application, petition or request.
- C. Ownership of less than five percent (5%) of the stock of a corporation whose stock is listed on the New York or American Stock Exchanges shall not constitute an interest for the purposes of this section.
- D. A person who knowingly and intentionally violates this section shall be guilty of a misdemeanor.

III. That no Town of Manlius officer, employee or a relative of either, as defined in Section 809 General Municipal Law has any interest in this application.

-OR-

If a Town of Manlius officer, employee or relative of either as defined in Section 809 General Municipal law has any interest in this application, the full particulars are provided on an attached sheet.

Date: Jan 16, 20 20.

Date: _____, 20_____.

Matthew Van Ryn
(Print Name)

(Print Name)

Matt Van Ryn
(Signature)

(Signature)

Melvin & Melvin
(Entity Name)

(Entity Name)

Attorneys for Buyer/Petitioner
By (Officer) (Title)

By (Officer) (Title)

217 S Sahina St, 7th floor
(Mailing Address of Applicant) Syr 13202

(Mailing Address of Applicant)

315-422-1311
(Telephone Number)

(Telephone Number)

ACKNOWLEDGEMENTS

STATE OF NEW YORK)

) SS:

COUNTY OF ONONDAGA)

On this 16th day of January in the year 20 20, before me, the undersigned, a notary public in and for said state, personally appeared Matthew Van Ryn, and _____ personally known to

me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within Petition and acknowledged to me the he/she/they executed the same in his/her/their capacity, and that by his/her/their signature(s) on the Petition, the individual or the persons upon behalf of which the individual acted executed the instrument.

Barbara Nackle
Notary Public

BARBARA NACKLEY
NOTARY PUBLIC, STATE OF NEW YORK
Registration No. 01NA4873856
Qualified In Onondaga County
Commission Expires 10/20/ 2022

Expected
Fee: \$300

TOWN OF MANLIUS
PLANNING DEPARTMENT
INITIAL APPEARANCE APPLICATION

DATE: 1/31/20

Name of Project: _____

Applicant must submit 12 copies of all site plans, surveys, and supporting data with the final application before a planning board meeting can be scheduled.

Location of Project: _____

Type of Project:

☐ Division of Land ☐ Subdivision ☐ Accessory Use ☐ Zone Change ☐ Site Review ☒ Other Sign Allowance

Developer: Signarama Syracuse Phone: 315 446 9420

Address: 102 Headson Dr Syracuse Zip: 13214

Tax Map Number(#)/s: _____

Present Zoning: _____ Desired Zoning: _____

Total Acreage: _____ Total Number of Lots: _____

Property Owner/s: Manlius Acad LLC Phone: 732-369-0062

Address: 4719 Lane Manlius NY Zip: 13104

Tax Map#(s): 114.-04-82.0 Owner's Signature: Michael Silberberg

Printed Name: Michael Silberberg

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

Use next page for additional known property owners' information

Planning Board Meeting Date Assignment: _____

Fee: _____ Paid: _____ Per: ☐ Credit/Debit Card ☐ Check ☐ Cash

Planning Board - Initial

617.20
Appendix B
Short Environmental Assessment Form

Instructions for Completing

Part 1 - Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 - Project and Sponsor Information			
Name of Action or Project: <i>Sign Allowance - Menhies Academy Apartments</i>			
Project Location (describe, and attach a location map):			
Brief Description of Proposed Action: <i>Remove existing sign faces - 959 ft</i> <i>Replace w/ larger sign faces - 20.459 ft</i>			
Name of Applicant or Sponsor: <i>Todd LaFlamme Signarama Syracuse</i>		Telephone: <i>315 446 9420</i>	
Address: <i>102 Heddon Dr</i>		E-Mail: <i>tlaflammesarsyracuse@gmail.com</i>	
City/PO: <i>Syracuse</i>		State: <i>NY</i>	Zip Code: <i>13084</i>
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation?		NO	YES
If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.		☒	☐
2. Does the proposed action require a permit, approval or funding from any other governmental Agency?		NO	YES
If Yes, list agency(s) name and permit or approval:		☒	☐
3.a. Total acreage of the site of the proposed action?		<i>21/0</i> acres	
b. Total acreage to be physically disturbed?		<i>21/0</i> acres	
c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor?		_____ acres	
4. Check all land uses that occur on, adjoining and near the proposed action.			
☐ Urban ☐ Rural (non-agriculture) ☐ Industrial ☐ Commercial ☒ Residential (suburban) ☐ Forest ☐ Agriculture ☐ Aquatic ☐ Other (specify): _____ ☐ Parkland			

5. Is the proposed action, a. A permitted use under the zoning regulations?	NO	YES	N/A
	☐	☐	☐
b. Consistent with the adopted comprehensive plan?		☐	☐
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?	NO	YES	
	☒	☐	
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area? If Yes, identify: _____	NO	YES	
	☒	☐	
8. a. Will the proposed action result in a substantial increase in traffic above present levels?	NO	YES	
	☐	☐	
b. Are public transportation service(s) available at or near the site of the proposed action?		☒	☐
c. Are any pedestrian accommodations or bicycle routes available on or near site of the proposed action?		☒	☐
9. Does the proposed action meet or exceed the state energy code requirements? If the proposed action will exceed requirements, describe design features and technologies: _____	NO	YES	
	☒	☐	
10. Will the proposed action connect to an existing public/private water supply? If No, describe method for providing potable water: _____	NO	YES	
	☒	☐	
11. Will the proposed action connect to existing wastewater utilities? If No, describe method for providing wastewater treatment: _____	NO	YES	
	☒	☐	
12. a. Does the site contain a structure that is listed on either the State or National Register of Historic Places?	NO	YES	
	☒	☐	
b. Is the proposed action located in an archeological sensitive area?		☐	
	☒	☐	
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?	NO	YES	
	☒	☐	
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody? If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres: _____		☐	
	☒	☐	
14. Identify the typical habitat types that occur on, or are likely to be found on the project site. Check all that apply: ☐ Shoreline ☐ Forest ☐ Agricultural/grasslands ☐ Early mid-successional ☐ Wetland ☐ Urban ☐ Suburban			
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or Federal government as threatened or endangered?	NO	YES	
	☒	☐	
16. Is the project site located in the 100 year flood plain?	NO	YES	
	☒	☐	
17. Will the proposed action create storm water discharge, either from point or non-point sources? If Yes, a. Will storm water discharges flow to adjacent properties? ☐ NO ☐ YES b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)? If Yes, briefly describe: _____ _____	NO	YES	
	☒	☐	

18. Does the proposed action include construction or other activities that result in the impoundment of water or other liquids (e.g. retention pond, waste lagoon, dam)? If Yes, explain purpose and size: _____	NO ☒	YES ☐
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility? If Yes, describe: _____	NO ☒	YES ☐
20. Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or completed) for hazardous waste? If Yes, describe: _____	NO ☒	YES ☐
I AFFIRM THAT THE INFORMATION PROVIDED ABOVE IS TRUE AND ACCURATE TO THE BEST OF MY KNOWLEDGE Applicant/sponsor name: <u>Todd LaFlamme Signarsma Spence</u> Date: <u>1-31-20</u> Signature: <u>Todd LaFlamme</u>		

STOP

Part 2 - Impact Assessment. The Lead Agency is responsible for the completion of Part 2. Answer all of the following questions in Part 2 using the information contained in Part 1 and other materials submitted by the project sponsor or otherwise available to the reviewer. When answering the questions the reviewer should be guided by the concept "Have my responses been reasonable considering the scale and context of the proposed action?"


	No, or small impact may occur	Moderate to large impact may occur
1. Will the proposed action create a material conflict with an adopted land use plan or zoning regulations?	☐	☐
2. Will the proposed action result in a change in the use or intensity of use of land?	☐	☐
3. Will the proposed action impair the character or quality of the existing community?	☐	☐
4. Will the proposed action have an impact on the environmental characteristics that caused the establishment of a Critical Environmental Area (CEA)?	☐	☐
5. Will the proposed action result in an adverse change in the existing level of traffic or affect existing infrastructure for mass transit, biking or walkway?	☐	☐
6. Will the proposed action cause an increase in the use of energy and it fails to incorporate reasonably available energy conservation or renewable energy opportunities?	☐	☐
7. Will the proposed action impact existing: a. public / private water supplies? b. public / private wastewater treatment utilities?	☐ ☐	☐ ☐
8. Will the proposed action impair the character or quality of important historic, archaeological, architectural or aesthetic resources?	☐	☐
9. Will the proposed action result in an adverse change to natural resources (e.g., wetlands, waterbodies, groundwater, air quality, flora and fauna)?	☐	☐

	No, or small impact may occur	Moderate to large impact may occur
10. Will the proposed action result in an increase in the potential for erosion, flooding or drainage problems?	☐	☐
11. Will the proposed action create a hazard to environmental resources or human health?	☐	☐

Part 3 - Determination of significance. The Lead Agency is responsible for the completion of Part 3. For every question in Part 2 that was answered "moderate to large impact may occur", or if there is a need to explain why a particular element of the proposed action may or will not result in a significant adverse environmental impact, please complete Part 3. Part 3 should, in sufficient detail, identify the impact, including any measures or design elements that have been included by the project sponsor to avoid or reduce impacts. Part 3 should also explain how the lead agency determined that the impact may or will not be significant. Each potential impact should be assessed considering its setting, probability of occurring, duration, irreversibility, geographic scope and magnitude. Also consider the potential for short-term, long-term and cumulative impacts.


☐	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action may result in one or more potentially large or significant adverse impacts and an environmental impact statement is required.
☐	Check this box if you have determined, based on the information and analysis above, and any supporting documentation, that the proposed action will not result in any significant adverse environmental impacts.
Name of Lead Agency Date	
Print or Type Name of Responsible Officer in Lead Agency Title of Responsible Officer	
Signature of Responsible Officer in Lead Agency Signature of Preparer (if different from Responsible Officer)	

PRINT



Existing sign: 36"t x 36" w


Existing structure to remain




Area View



Property vs Sign location








Banner to be constructed from 1" PVC with digital print

Sign faces to be constructed from 6mm Aluminum Dibond with digital print

- Add on wooden structure painted white
- Existing 4x4 structure with pvc sleeves
- Existing concrete footers remain



- Banner to extend height perimeter of main sign and wrap around the other side



December 18, 2019

Randy Capriotti, Director of Code Enforcement
Town of Manlius, Planning and Development
301 Brooklea Drive
Fayetteville, NY 13066

Re: 3Gi – Central New York Inland Port Project

Dear Mr. Capriotti,

Enclosed for your review is a complete set of plans and documents for a zone change request and site plan review for the 3Gi property north of the CSX rail yard. We look forward to presenting to the Town of Manlius Planning Board meeting on January 6th, 2020. Below are responses to the submission comment letter from Miller Engineers dated September 11th, 2019.

- 1) *The site is currently zoned Restricted Agricultural (RA) and the proposed warehousing and storage container parking is not an allowable use.*

This submission contains the necessary application and materials to apply for a zone change.

- 2) *Submission of site plan and supporting data is required should a zone change be requested... and shall include at a minimum the following information...*

- a) *A properly certified survey of the property...*

A certified survey of the subject parcels is included in this submittal and includes site features and existing topography. Additionally, zone change maps of the properties are also included.

- b) *The site plan showing proposed building locations and land use areas.*

A site plan of the proposed container pooling operation is included in this submittal.

- c) *Traffic circulation, parking and loading spaces, and pedestrian walks.*

The proposed access driveway off of Fremont Road is included on the site plan. There are no associated parking spaces or pedestrian facilities required for the current proposal.

- d) *Landscaping plans, including site grading and landscape design.*

A landscaping and grading plan is included in this submittal.

- e) *Preliminary architectural drawings for buildings...*

For the current proposal, only a small prefabricated modular office building is proposed. Colors and materials have yet to be determined. Some examples of what this office building could look like are shown on the following page. Warehouse buildings are included in the master development plan for the property and are shown only as an example of potential future proposals.



Figures 1&2: Examples of prefabricated modular office buildings.

- f) *Preliminary engineering plans, including street improvements, drainage systems, and public utility extensions.*

All proposed improvements have been included in the site plan. The only utilities proposed at this time are several pole-mounted site lights. Placeholders for stormwater management are shown on the site plan to mitigate future impervious area on the site.

- 3) *For more specific detailed information, the applicant should be directed to reference the Town Zoning Code, procedures for zone change and site plan submission requirements.*

We have reviewed section §155-28 ‘Site Plan Review’ in the Town of Manlius zoning code, and believe that we have addressed all of the applicable requirements.

Any and all future comments will be addressed accordingly. If you have any questions or if you need any other additional information, please contact us.

Respectfully submitted,

NAPIERALA CONSULTING
Professional Engineer, P.C.

Matthew R. Napierala

Matthew R. Napierala, P.E.
Managing Engineer / President

Zone Change Application

For:

**CENTRAL NEW YORK INLAND PORT
TOWN OF MANLIUS, NY**

Prepared for:

3Gi
360 ERIE BOULEVARD EAST
SYRACUSE, NY 13202

Prepared by:



December 2019



EXECUTIVE SUMMARY

A. INTRODUCTION

3Gi CNYIP Inc. (3Gi) is the leading private entity responsible for the development of the Central New York Inland Port (CNYIP), which will offer increased opportunities for importing and exporting by providing infrastructure for dedicated international intermodal service to and from the Port Authority of New York and New Jersey (PANYNJ). By increasing the amount of materials that are transported via rail relative to the amount transported by truck, the project will contribute to more efficient use of energy and reduction in greenhouse gas emissions while enhancing the import/export markets in NYS. 3Gi's CNYIP will be integrated into the existing Dewitt Rail Yard located south of Kirkville Road between Girden Road and Fremont Road in the Town of Manlius. The Dewitt Rail Yard has been operated by CSX since 1857 and is located along a route that extends from Boston to Cleveland. The rail yard and subject site is on a Class 1 railroad, is a part of the NYS Transportation Master Plan, and is also within the Federal Intermodal Corridor, making the project eligible for federal funding. In 2018, New York State funded \$19 million to CSX to make improvements to the DeWitt Rail Yard in order to allow for international container service, which will commence in September of 2019. By developing a functional CNYIP, 3Gi plans to take advantage of the economic opportunity presented by international container service and therefore provide numerous socioeconomic and environmental benefits to the Central New York region.

B. ECONOMIC INCENTIVES

3Gi, in business with Intransit Container, Inc., (ICI), will provide logistic services that match international import containers with exporters who need empty containers. Coordinating importers and exporters to take full advantage of round trip empty international containers is the primary business opportunity filled by 3Gi CNYIP and ICI Port of Worcester. Together, 3Gi and ICI fill a need for regional importers and exporters to send and receive a greater volume of goods from international markets in a more cost-effective and fuel-efficient manner. This business relationship will provide a streamlined alternative to shipping via truck, which is far more time and cost intensive.

C. FACILITY OPERATIONS

The CNYIP will be set up to provide management of incoming and outgoing cargo for the Dewitt Rail Yard, where there is none today. CSX is in the business of transporting cargo; they do not manage cargo once it reaches its destination. The inland port will store, organize, coordinate, distribute, and manage the cargo from the transporter to and from the manufacturer and the buyer. The establishment of an effective inland port will start with the development of an international container yard for CSX containers. The container yard will take in off-loaded international containers, store them in a yard, and mitigate the truck transport of the containers to their final destination. The container yard will also take in empty containers and coordinate their distribution to Central New York exporters for filling. Once they are loaded with product, the containers will be returned to the CNYIP for export via rail back to the PANYNJ for international distribution on container ships.

Future expansion of CNYIP is unknown at this time but could potentially include the development of on-site warehousing for the short-term aggregation of products and the infrastructure required to coordinate the exporting of those products. It could also include the laying of track inside the CNYIP owned property, enabling CSX to switch the rail cars into the 3Gi operated container yard and thereby allow for the control of export loading and the ability to aggregate large numbers of containers to be shipped on the same train.

D. ENVIRONMENTAL IMPACT

The implementation of a Central New York Inland Port will have a positive impact on the environment. Currently, CNY exporters have to transport their goods via truck (tractor trailer) down and through New York City to the PANYNJ. Not only is truck transport more expensive (greater than 5 times the cost of rail transport), but it is harmful to the environment due to excessive carbon emission from the trucks. Rail transport has significantly lower carbon emissions and therefore a smaller environmental impact.

Adjacent to the proposed site there are several NYSDEC freshwater wetlands and a FEMA 100-year floodplain area. The proposed project will avoid much of the jurisdictional wetland areas and only require a small impact for the



road extension from the container yard to Kirkville Road. The project will include properly sized stormwater mitigation basins to mitigate any effects to storm water runoff conditions resulting from the proposed development. A wetland delineation and determination report has been compiled and is included in Appendix C of this report.

E. TRAFFIC IMPACT

As it exists today, the main route for international truck traffic that is entering or exiting the CSX operated DeWitt Rail Yard is via North Central Avenue and Fremont Road. Beginning in September of 2019, CSX will use this existing route for all international cargo transportation by truck. The long-term plan for the CNYIP is to reroute this truck traffic through the 3Gi site onto Girden Road before accessing Kirkville Road. This will alleviate the potential traffic burden from the prospective increase in international container service, thus avoiding the two schools and residential neighborhood located along Fremont Road. The traffic improvement proposed by 3Gi is a great enhancement to the existing condition. The temporary access road (Temp Road 1) proposed in Phase 1 will access the international container yard from Fremont Road. The first permanent option for site access from Girden Road (Perm Road 1) will be via an existing easement directly west of the site. The second permanent option for site access from Girden Road (Perm Road 2) will be to the northwest across the northern part of the wetland area. Perm Road 2 will require coordination with NYS in order to obtain funding, but will have a much smaller impact on the adjacent wetlands.

The intersection of Girden Road and Kirkville Road is only a three quarter-mile drive to Interstate 481. The connection to the NYS Thruway (Interstate 90) is only two miles north of this point and is only another 6 miles from Interstate 81. Therefore, from the future road improvement on Girden Road, international cargo will have a direct connection from the CSX railroad to the entirety of New York State, the northeastern United States, and eastern Canada. To assess the potential impact that the trip generation from the full build-out of the project will have on Girden Road and Kirkville Road, a traffic impact study has been prepared for this project and is included in Appendix D of this report.

F. PROJECT BENEFITS

The CNYIP has many potential socio-economic and environmental benefits to the Central New York Region. The greatest positive outcome is the prospective economic growth that would accompany a reduction in shipping costs associated with a shift from importing and exporting by truck to rail. Many businesses within the CNY region have indicated that transportation costs are a significant cost of sales and consideration in their growth potential as well as retaining their business in NYS. Additionally, the long-term shift to importing and exporting by rail will result in a reduction in emissions of greenhouse gases through a decrease in tractor trailers on NYS roadways.

Expected
Fee: _____

TOWN OF MANLIUS
PLANNING DEPARTMENT
INITIAL APPEARANCE APPLICATION

DATE: August 27, 2019

Name of Project: 3Gi - Central New York Inland Port (CNYIP)

Applicant must submit 12 copies of all site plans, surveys, and supporting data with the final application before a planning board meeting can be scheduled.

Location of Project: Vacant rural property to the south of Kirkville Road between Girden Rd and Fremont Rd

Type of Project:

☐ Division of Land ☐ Subdivision ☐ Accessory Use ☐ Zone Change ☒ Site Review ☐ Other _____

Developer: 3Gi (Contact: Chris Beck) Phone: 315-849-0898

Address: 360 Erie Boulevard East, Syracuse, NY Zip: 13202


Tax Map Number(#)/s: 054.-01-28.1, 054.-01-06.1, 054.-01-04.1, & 054.-01-2.1

Present Zoning: Residential Agricultural Desired Zoning: Industrial

Total Acreage: 75.7 Acres Total Number of Lots: Four (4)

Property Owner/s: 3Gi CNYIP Inc. Phone: 315-475-3700

Address: 360 Erie Boulevard East, Syracuse, NY Zip: 13202

Tax Map#(s): 054.-01-28.1, 054.-01-06.1, 054.-01-04.1, & 054.-01-2.1 Owner's Signature: 
Printed Name: Eckardt C. Beck, CEO

Property Owner/s: _____ Phone: _____

Address: _____ Zip: _____

Tax Map#(s): _____ Owner's Signature: _____

Printed Name: _____

Use next page for additional known property owners' information

Planning Board Meeting Date Assignment: _____

Fee: _____ Paid: _____ Per: ☐ Credit/Debit Card ☐ Check ☐ Cash

TOWN OF MANLIUS

DISCLOSURE AFFIDAVIT

This affidavit is a part of and must be completed and attached to every application, petition, request submitted for a *site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit.*

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

I. Eckardt C. Beck, being duly sworn, deposes and says that (s) he is:

CEO of 3G: CNYIP, Inc. (Property Owner)
(applicant, petitioner, corporation officer, property owner, etc.)

II. That deponent has read and is familiar with the provisions of the General Municipal Law, Section 809 which states:

- A. Every application, petition or request submitted for a site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit, pursuant to the provisions or any ordinance, local law, rule or regulation constituting the zoning and planning regulations of a municipality shall state the name, residence and the nature and extent of the interest of any state officer or any officer or employee of such municipality is a part, in the person, partnership or association making such application, petition or request (hereinafter called the applicant) to the extent known to such applicant.
- B. For the purpose of this action an officer or employee shall be deemed to have an interest in the applicant when (s)he, his/her spouse, or their brothers, sisters, parents, children, grandchildren, or the spouse of any of them:
 - 1) is the applicant, or
 - 2) is an officer, director, partner or employee of the applicant, or
 - 3) legally or beneficially owns or controls stock of a corporate applicant or is a member of a partnership or association applicant, or
 - 4) is a party to an agreement with such an applicant, express or implied, whereby (s) he may receive any payment or other benefit, whether or not for services rendered, or contingent upon the favorable approval of such application, petition or request.
- C. Ownership of less than five percent (5%) of the stock of a corporation whose stock is listed on the New York or American Stock Exchanges shall not constitute an interest for the purposes of this section.
- D. A person who knowingly and intentionally violates this section shall be guilty of a misdemeanor.

III. That no Town of Manlius officer, employee or a relative of either, as defined in Section 809 General Municipal Law has any interest in this application.

-OR-

If a Town of Manlius officer, employee or relative of either as defined in Section 809 General Municipal law has any interest in this application, the full particulars are provided on an attached sheet.

Date: August 27th, 20 19.

Date: _____, 20 _____.

Eckardt C. Beck
(Print Name)

(Print Name)

[Signature]
(Signature)

(Signature)

3G: CNYIP, Inc.
(Entity Name)

(Entity Name)

CEO
By (Officer) (Title)

By (Officer) (Title)

360 Erie Blvd. E, Syracuse, NY 13202
(Mailing Address of Applicant)

(Mailing Address of Applicant)

(315) 269-7767
(Telephone Number)

(Telephone Number)

ACKNOWLEDGEMENTS

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

On this 27th day of August in the year 20 19, before me, the undersigned, a notary public in and for said state, personally appeared Eckardt C. Beck, and _____ personally known to me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within Petition and acknowledged to me the he/she/they executed the same in his/her/their capacity, and that by his/her/their signature(s) on the Petition, the individual or the persons upon behalf of which the individual acted executed the instrument.

[Signature]
Notary Public

BRENDAN V. COTTER
Notary Public, State of New York
No. 02CO6152108
Qualified in Oneida County
My Commission Expires August 28, 2021


CORPORATE ACKNOWLEDGEMENT

STATE OF NEW YORK)

) SS:

COUNTY OF ONONDAGA)

Eckardt C. Beck, being duly sworn, deposes and says the
s(he) is the Chief Executive Officer of 36i CNYIP, Inc.
corporation named in the within Application/Petition, that s(he) has read the foregoing affidavit and
knows the contents thereof; that the same is true of s(he) own knowledge, except as to those matters
therein stated to be alleged upon information and belief, and as to those matters s(he) believes it to be
true.


Applicant Signature

Subscribed to me before this day ^{27th}
Of August, 20 19


Notary Public

BRENDAN V. COTTER
Notary Public, State of New York
No. 02CO6152108
Qualified in Oneida County
My Commission Expires August 28, 2022

**TOWN OF MANLIUS
ZONE CHANGE APPLICATION**

1. Name of Person applying for Zone Change 3Gi (Contact: Chris Beck)
Address of person applying 360 Erie Boulevard East, Syracuse, NY 13202
Cell Number (315) 269-7767 Phone Number (315) 849-0898

2. Name: (owner of record) of land where Zone Change would occur 3Gi CNYIP Inc.
Address (owner of record) 360 Erie Boulevard East, Syracuse, NY 13202
Cell Number (owner of record) _____ Phone Number (315) 849-0898

054-01-28.1, 054-01-06.1

3. Tax Map Number of property where Zone Change would occur 54-01-4.1, & 054-01-02.1

4. Is this property located in a flood hazard area? Yes

If so, what flood area is the property in it in?
100-Year Floodplain

5. Present zoning classification of property Residential Agricultural & Industrial

6. Desired zoning classification Industrial

Reason for Change of Zone (use additional sheets if necessary) Lots to the east, south, and west under common ownership are industrial zoned. A zone change would provide consistent zoning for the parcels in common ownership and would allow for the proposed future use of a container pooling yard and inland port as a natural extension of the CSX rail yard

7. What is lot size? Four (4) parcels totaling 75.7 total acres

8. If the Zone Change is granted, will the use of the property conform to the District regulations as stated in Chapter 155 Article III of the Town of Manlius Municipal Code? Yes

9. Is the property within the protectively zoned area of a housing project authorized under the public housing law? No

10. Is the property within five hundred (500) feet of the boundaries of any city, village, town, county, state park or parkway? Yes

If yes, please specify The center line of Girden Road is the Town of DeWitt boundary.

11. Is the property within five hundred (500) feet from the boundary of any existing or proposed County or State park or other recreation area, or from the right-of-way of any existing or proposed county or state parkway, thruway, expressway, road or highway, or from the existing or proposed right-of-way of any stream or drainage channel owned by the county or for which the county has established channel lines, or from the existing or proposed boundary of any county or state owned land on which a public building or institution is situated? Yes

If yes, please specify Pine Grove Middle School

12. List the uses of all abutting property Residential properties, the CSX rail yard,
a self-storage unit facility, and vacant forested/wetland area.


13. The following must be included with your 12 application packets unless otherwise specified
and/or specifically waived by the Town Board:

- An environmental assessment form which can be obtained from the Town Clerk, or an environmental impact statement.
- Copy of a survey of the premises certified by a New York State licensed surveyor.
- Legal description of the premises.
- This application must be signed by both the owner of record of the property and the applicant.

The failure to answer any question on this application, the failure to submit any item as specified or the failure to execute this application will result in a delay in the processing of the application.

36i CNYIP, Inc.

Date 12/17/19

By: 
Applicant 1
CED

Date _____

Applicant 2

Date _____

Applicant

TOWN OF MANLIUS

DISCLOSURE AFFIDAVIT

This affidavit is a part of and must be completed and attached to every application, petition, request submitted for a *site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit.*

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

I. Eckardt C. Beck being duly sworn, deposes and says that (s) he is:

CEO of 3G: CNYIP, Inc. (Applicant)
(applicant, petitioner, corporation officer, property owner, etc.)

II. That deponent has read and is familiar with the provisions of the General Municipal Law, Section 809 which states:

- A. Every application, petition or request submitted for a site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit, pursuant to the provisions or any ordinance, local law, rule or regulation constituting the zoning and planning regulations of a municipality shall state the name, residence and the nature and extent of the interest of any state officer or any officer or employee of such municipality is a part, in the person, partnership or association making such application, petition or request (hereinafter called the applicant) to the extent known to such applicant.
- B. For the purpose of this action an officer or employee shall be deemed to have an interest in the applicant when (s)he, his/her spouse, or their brothers, sisters, parents, children, grandchildren, or the spouse of any of them:
- 1) is the applicant, or
 - 2) is an officer, director, partner or employee of the applicant, or
 - 3) legally or beneficially owns or controls stock of a corporate applicant or is a member of a partnership or association applicant, or
 - 4) is a party to an agreement with such an applicant, express or implied, whereby (s) he may receive any payment or other benefit, whether or not for services rendered, or contingent upon the favorable approval of such application, petition or request.
- C. Ownership of less than five percent (5%) of the stock of a corporation whose stock is listed on the New York or American Stock Exchanges shall not constitute an interest for the purposes of this section.
- D. A person who knowingly and intentionally violates this section shall be guilty of a misdemeanor.

III. That no Town of Manlius officer, employee or a relative of either, as defined in Section 809 General Municipal Law has any interest in this application.

-OR-

If a Town of Manlius officer, employee or relative of either as defined in Section 809 General Municipal law has any interest in this application, the full particulars are provided on an attached sheet.

Date: December 17th, 20 19.

Date: _____, 20 ____.

Eckardt C. Beck
(Print Name)

(Print Name)

Eckardt C. Beck
(Signature)

(Signature)

3G: CNY IP, Inc.
(Entity Name)

(Entity Name)

Eckardt C. Beck, Chief Executive
By (Officer) (Title) Officer

By (Officer) (Title)

360 Erie Boulevard East, Syracuse, NY
(Mailing Address of Applicant) 13202

(Mailing Address of Applicant)

(315) 269-7767
(Telephone Number)

(Telephone Number)

ACKNOWLEDGEMENTS

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

On this 17th day of December in the year 20 19, before me, the undersigned, a notary public in and for said state, personally appeared Eckardt C. Beck,
_____, and _____ personally known to

me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within Petition and acknowledged to me the he/she/they executed the same in his/her/their capacity, and that by his/her/their signature(s) on the Petition, the individual or the persons upon behalf of which the individual acted executed the instrument.

Brendan V. Cotter
Notary Public

BRENDAN V. COTTER
Notary Public, State of New York
No. 02CO6152108
Qualified in Oneida County
My Commission Expires August 28, 2022


CORPORATE ACKNOWLEDGEMENT

STATE OF NEW YORK)

) SS:

COUNTY OF ONONDAGA)

Eckardt C. Beck, being duly sworn, deposes and says the
s(he) is the Chief Executive Officer of 3G: CNYIP, Inc.
corporation named in the within Application/Petition, that s(he) has read the foregoing affidavit and
knows the contents thereof; that the same is true of s(he) own knowledge, except as to those matters
therein stated to be alleged upon information and belief, and as to those matters s(he) believes it to be
true.



Applicant Signature

Subscribed to me before this day 17th
Of December, 20 19


Notary Public

BRENDAN V. COTTER
Notary Public, State of New York
No. 02CO6152108
Qualified in Oneida County
My Commission Expires August 28, 20 22



Lehr Land Surveyors D.P.C.
Land Surveying & Planning

Suite 6
116 Salina Street
Liverpool, New York 13088
315-451-3333
FAX: 315-451-3392
EMAIL: info@lehrlandsurveyors.com

Surveyor's Description

Tax Id: 54-1-2.1
Town of Manlius

December 09, 2019
Page 1 of 2

RE: Minoa-Kirkville Road

ALL THAT TRACT OR PARCEL OF LAND situate in the Town of Manlius, County of Onondaga and State of New York and being Lot No.33 in said Town, and being more particularly described as follows:

BEGINNING at a point in the southerly road boundary of Minoa – Kirkville Road, said point being easterly a distance of 200.32' from the easterly road boundary of Girden Road, said point also being the northeasterly corner of land now or formerly owned by Niagara Mohawk Power Corporation as recorded in the Onondaga County Clerk's Office in Book 2225 of Deeds, Page 384;

thence S 88°44'02" E., along the southerly road boundary of said Minoa – Kirkville Road, a distance of **112.84 feet** to an angle point in said road boundary;

thence S 79°30'00" E., continuing along the southerly road boundary of said Minoa – Kirkville Road, a distance of **223.73 feet** to a point;

thence S 0°47'08" W., a distance of **2263.50 feet** to the northerly line of lands now or formerly owned by CSX Transportation Inc.;

thence N 89°11'49" W., along the northerly line of said CSX Transportation Inc., a distance of **333.36 feet** to the easterly line of said Niagara Mohawk Power Corporation;

thence N 0°47'08" E., along the easterly line of said Niagara Mohawk Power Corporation, a distance of **2302.10 feet** to the point of beginning;

Containing 17.517 acres or 763,021 square feet of land more or less.

The hereinbefore described parcel of land is subject to any and all easements and/or rights-of-ways of record.



Lehr Land Surveyors D.P.C.
Land Surveying & Planning

Suite 6
116 Salina Street
Liverpool, New York 13088
315-451-3333
FAX: 315-451-3392
EMAIL: info@lehrlandsurveyors.com

Surveyor's Description

Tax Id: 54-1-4.1
Town of Manlius

December 09, 2019
Page 1 of 2

RE: Minoa-Kirkville Road

ALL THAT TRACT OR PARCEL OF LAND situate in the Town of Manlius, County of Onondaga and State of New York and being Lot No.33 in said Town, and being more particularly described as follows:

BEGINNING at a point in the southerly road boundary of Minoa – Kirkville Road, said point being easterly a distance of 536.89' from the easterly road boundary of Girden Road;

thence S 79°30'00" E., along the southerly road boundary of said Minoa – Kirkville Road, a distance of **405.21 feet** to an angle point in said road boundary;

thence S 63°47'03" E., continuing along the southerly road boundary of said Minoa – Kirkville Road, a distance of **22.75 feet** to its intersection with the westerly line of lands now or formerly owned by Michael F. Deecher and Carolyn J. Mulligan as recorded in the Onondaga County Clerk's Office in Book 3298 of Deeds, Page 6;

thence S 1°32'20" W., along the westerly line of said Deecher and Mulligan, a distance of **704.80 feet** to a point;

thence N 88°27'40" W., a distance of **23.16 feet** to a point;

thence S 0°14'19" W., a distance of **1481.12 feet** to its intersection with the northerly line of lands now or formerly owned by CSX Transportation Inc.;

thence N 89°11'49" W., along the northerly line of said CSX Transportation Inc., a distance of **401.67 feet** to a point;

thence N 0°47'08" E., a distance of **2263.50 feet** to the point of beginning.

Containing 20.538 acres or 894,629 square feet of land more or less.

The hereinbefore described parcel of land is subject to any and all easements and/or rights-of-ways of record.



Lehr Land Surveyors D.P.C.
Land Surveying & Planning

Suite 6
116 Salina Street
Liverpool, New York 13088
315-451-3333
FAX: 315-451-3392
EMAIL: info@lehrlandsurveyors.com

Surveyor's Description

Tax Id: 54-1-6.1
Town of Manlius

December 09, 2019
Page 1 of 2

RE: Minoa-Kirkville Road

ALL THAT TRACT OR PARCEL OF LAND situate in the Town of Manlius, County of Onondaga and State of New York and being Lot No.33 in said Town, and being more particularly described as follows:

BEGINNING at a point in the southerly road boundary of Minoa – Kirkville Road, said point being the northeasterly corner of property now or formerly owned by Calvin O. Goodrich, Trustee of the Goodrich Living Trust as recorded in the Onondaga County Clerk's Office in Book 5407 of Deeds, Page 928;

thence S 78°46'12" E., along the southerly road boundary of said Minoa – Kirkville Road, a distance of **353.26 feet** to an angle point in said road boundary;

thence S 80°38'21" E., continuing along the southerly road boundary of said Minoa – Kirkville Road, a distance of **226.01 feet** to its intersection with the westerly line of lands now or formerly owned by Anita G. Santaro as recorded in the Onondaga County Clerk's Office in Book 3959 of Deeds, Page 323;

thence S 0°14'19" W., along the westerly line of said Santaro and the westerly line of lands now or formerly owned by Drive-In Self Storage Manlius, LLC as recorded in the Onondaga County Clerk's Office in Book 4759 of Deeds, Page 310 a distance of **2042.62 feet** to a its intersection with the northerly line of lands now or formerly owned by the CSX Transportation Inc.;

thence N 89°11'49" W., along the northerly line of said CSX Transportation Inc., a distance of **879.74 feet** to a point;

thence N 0°14'19" E., a distance of **1481.12 feet** to a point;

thence S 88°27'40" E., partially along the lands now or formerly owned by Michael F. Deecher and Carolyn J. Mulligan as recorded in the Onondaga County Clerk's Office in Book 3298 of Deeds, Page 6, a distance of **196.02 feet** to a point;

thence N 1°32'20" E., along the easterly line of said Deecher and Mulligan, a distance of **508.83 feet** to its intersection with the southerly line of said Goodrich;

thence S 79°30'00" E., along the southerly line of said Goodrich, a distance of **100.00 feet** to a point;


thence N 1°32'20" E., along the easterly line of said Goodrich, a distance of **169.63 feet** to the point of beginning.

Containing 39.103 acres or 1,703,313 square feet of land more or less.

The hereinbefore described parcel of land is subject to any and all easements and/or rights-of-ways of record.



- LEGEND:
- UTILITY POLE
 - GUY WIRE
 - OVERHEAD WIRES
 - MANHOLE
 - FIRE HYDRANT
 - CHAIN LINK FENCE



ZONE CHANGE MAP
LANDS OF
3GI CNYIP, INC.

SHEET 1 OF 2

Only survey maps with the Land Surveyor's embossed seal are genuine true and correct copies of the surveyor's original work and opinion.

Unauthorized alteration or addition to a survey map bearing a licensed land surveyor's seal is a violation of section 7209, sub-division 2, of the New York State Education Law.

Certifications indicated hereon shall apply only to the persons for whom this survey was performed and on their behalf to the title insurance company governing agency and lending institution and to the assignees of the lending institution and/or subsequent owners.

This map may not be used in connection with a "Survey Affidavit" or similar document, statement or mechanism to obtain insurance for any subsequent or future grantees.

Survey prepared without the benefit of an abstract.

Location surveys do not include the staking of the property corners except as shown.

No.	DATE	DESCRIPTION	BY

LEHR
LAND SURVEYORS D.P.C.



116 SALINA STREET - SUITE 6
LIVERPOOL, NEW YORK 13088
315-451-3333
info@lehrlandsurveyors.com

I HEREBY CERTIFY THAT THIS IS AN
ACCURATE MAP MADE FROM AN ACTUAL SURVEY.

LICENSED LAND SURVEYOR
DOUGLAS R. LEHR


NYSL 49223

LOCATION SURVEY ON PART OF LOT No.33.
TOWN OF MANLIUS

KNOWN AS MINOA-KIRKVILLE ROAD, TOWN OF MANLIUS,
COUNTY OF ONONDAGA, NEW YORK

FIELD DATE: 26 NOV 2019 MAP DATE: 3 DEC 2019 SCALE: DRAWN BY: 1"=100' M.H.

REVISIONS: DRAWING No. 19-J-27 10" x 11"



ZONE CHANGE MAP
LANDS OF
3GI CNYIP, INC.

SHEET 2 OF 2

Only survey maps with the Land Surveyor's embossed seal are genuine true and correct copies of the surveyor's original work and opinion.
Unauthorized alteration or addition to a survey map bearing a licensed land surveyor's seal is a violation of section 7209, sub-division 2, of the New York State Education Law.
Certifications indicated hereon shall apply only to the persons for whom this survey was performed and on their behalf to the title insurance company governing agency and lending institution and to the assignees of the lending institution and/or subsequent owners.
This map may not be used in connection with a "Survey Affidavit" or similar document, statement or mechanism to obtain insurance for any subsequent or future grantees.
Survey prepared without the benefit of an abstract.
Location surveys do not include the staking of the property corners except as shown.

CSX TRANSPORTATION INC.
FORMERLY
CONSOLIDATED RAIL CORP.

No.	DATE	DESCRIPTION	BY



I HEREBY CERTIFY THAT THIS IS AN
ACCURATE MAP MADE FROM AN ACTUAL SURVEY.

DOUGLAS R. LEHR
LICENSED LAND SURVEYOR
NYSLS 49223

LOCATION SURVEY ON PART OF LOT No.33.
TOWN OF MANLIUS


KNOWN AS MINOA-KIRKVILLE ROAD, TOWN OF MANLIUS,
COUNTY OF ONONDAGA, NEW YORK

FIELD DATE: 26 NOV 2019
MAP DATE: 3 DEC 2019
SCALE: DRAWN BY: 1"=100' M.H.

REVISIONS: DRAWING No. 19-J-57 10" x 11"



- LEGEND:
- UTILITY POLE
 - GUY WIRE
 - OVERHEAD WIRES
 - MANHOLE
 - FIRE HYDRANT
 - CHAIN LINK FENCE



TOPOGRAPHICAL MAP
LANDS OF
3GI CNYIP, INC.

SHEET 1 OF 2

Only survey maps with the Land Surveyor's embossed seal are genuine true and correct copies of the surveyor's original work and opinion.

Unauthorized alteration or addition to a survey map bearing a licensed land surveyor's seal is a violation of section 7209, sub-division 2, of the New York State Education Law.

Certifications indicated hereon shall apply only to the persons for whom this survey was performed and on their behalf to the title insurance company governing agency and lending institution and to the assignees of the lending institution and/or subsequent owners.

This map may not be used in connection with a "Survey Affidavit" or similar document, statement or mechanism to obtain insurance for any subsequent or future grantees.

Survey prepared without the benefit of an abstract.

Location surveys do not include the staking of the property corners except as shown.

Elevation and Contours based on North American Datum of 1988 (NAVD88).

No.	DATE	DESCRIPTION	BY



116 SALINA STREET - SUITE 6
LIVERPOOL, NEW YORK 13088
315-451-3333
info@lehrlandsurveyors.com

I HEREBY CERTIFY THAT THIS IS AN
ACCURATE MAP MADE FROM AN ACTUAL SURVEY.

LICENSED LAND SURVEYOR
DOUGLAS R. LEHR


NYSL 49223

LOCATION SURVEY ON PART OF LOT No.33.
TOWN OF MANLIUS

KNOWN AS MINOA-KIRKVILLE ROAD, TOWN OF MANLIUS,
COUNTY OF ONONDAGA, NEW YORK

FIELD DATE: 26 NOV 2019 MAP DATE: 3 DEC 2019 SCALE: DRAWN BY:
1"=100' M.H.

REVISIONS: DRAWING No. 19-J-27
10" x 10"



TOPOGRAPHICAL MAP
LANDS OF
3GI CNYIP, INC.

SHEET 2 OF 2

Only survey maps with the Land Surveyor's embossed seal are genuine true and correct copies of the surveyor's original work and opinion.
Unauthorized alteration or addition to a survey map bearing a licensed land surveyor's seal is a violation of section 7209, sub-division 2, of the New York State Education Law.
Certifications indicated hereon shall apply only to the persons for whom this survey was performed and on their behalf to the title insurance company governing agency and lending institution and to the assignees of the lending institution and/or subsequent owners.
This map may not be used in connection with a "Survey Affidavit" or similar document, statement or mechanism to obtain insurance for any subsequent or future grantees.
Survey prepared without the benefit of an abstract.
Location surveys do not include the staking of the property corners except as shown.
Elevation and Contours based on North American Datum of 1988 (NAVD88).

CSX TRANSPORTATION INC.
FORMERLY
CONSOLIDATED RAIL CORP.

No.	DATE	DESCRIPTION	BY

LEHR
LAND SURVEYORS D.P.C.

116 SALINA STREET - SUITE 6
LIVERPOOL, NEW YORK 13088
315-451-3333
info@lehrlandsurveyors.com

I HEREBY CERTIFY THAT THIS IS AN
ACCURATE MAP MADE FROM AN ACTUAL SURVEY.

LICENSED LAND SURVEYOR
DOUGLAS R. LEHR
NYSLS 49223

LOCATION SURVEY ON PART OF LOT No.33. TOWN OF MANLIUS			
KNOWN AS MINOA-KIRKVILLE ROAD, TOWN OF MANLIUS, COUNTY OF ONONDAGA, NEW YORK			
FIELD DATE: 26 NOV 2019	MAP DATE: 3 DEC 2019	SCALE: DRAWN BY: 1"=100'	W.H.
REVISIONS:		DRAWING No. 19-J-87 42" x 11"	

Short Environmental Assessment Form

Part 1 - Project Information

Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 – Project and Sponsor Information			
Name of Action or Project: 3Gi - Central New York Inland Port			
Project Location (describe, and attach a location map): Town of Manlius - Industrial corridor adjacent to the CSX Dewitt train yard			
Brief Description of Proposed Action: The project will involve the zone change of three properties adjacent to the CSX rail yard. The construction includes a 2-acre gravel container pooling yard and a 'short term' access road off of Fremont Road to the containment yard. This will also include the construction of a +/- 700 SF modular office building and a truck scale for cargo monitoring.			
Name of Applicant or Sponsor: 3Gi-CNYIP (Contact: Chris Beck)		Telephone: 315-269-7767 E-Mail: ebeck@synapsellc.com	
Address: 360 Erie Blvd East			
City/PO: Syracuse		State: NY	Zip Code: 13202
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.		NO ☒	YES ☐
2. Does the proposed action require a permit, approval or funding from any other government Agency? If Yes, list agency(s) name and permit or approval: Zone Change - Town Board of Manlius, Site Plan Approval - Manlius Planning Board, Wetland Crossing Permit - DEC, SOCPA Approval		NO ☐	YES ☒
3. a. Total acreage of the site of the proposed action? b. Total acreage to be physically disturbed? c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor?		92 acres 3.5 acres 92 acres	
4. Check all land uses that occur on, are adjoining or near the proposed action: 5. ☐ Urban ☒ Rural (non-agriculture) ☒ Industrial ☐ Commercial ☒ Residential (suburban) ☐ Forest ☐ Agriculture ☐ Aquatic ☐ Other(Specify): ☐ Parkland			

5. Is the proposed action, *	NO	YES	N/A
a. A permitted use under the zoning regulations? (w/ proposed zone change to industrial)	☐	☒	☐
b. Consistent with the adopted comprehensive plan?	☐	☐	☒
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?	NO	YES	
	☐	☒	
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area?	NO	YES	
If Yes, identify: _____	☒	☐	
8. a. Will the proposed action result in a substantial increase in traffic above present levels?	NO	YES	
	☒	☐	
b. Are public transportation services available at or near the site of the proposed action?	☒	☐	
c. Are any pedestrian accommodations or bicycle routes available on or near the site of the proposed action?	☒	☐	
9. Does the proposed action meet or exceed the state energy code requirements?	NO	YES	
If the proposed action will exceed requirements, describe design features and technologies: _____ _____	☐	☒	
10. Will the proposed action connect to an existing public/private water supply?	NO	YES	
If No, describe method for providing potable water: _____ _____	☐	☒	
11. Will the proposed action connect to existing wastewater utilities?	NO	YES	
If No, describe method for providing wastewater treatment: _____ _____	☒	☐	
12. a. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district which is listed on the National or State Register of Historic Places, or that has been determined by the Commissioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the State Register of Historic Places?	NO	YES	
	☒	☐	
b. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?	☒	☐	
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?	NO	YES	
	☐	☒	
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody?	☐	☒	
If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres: _____ 0.3 acre impact to jurisdictional wetland to create access to Fremont Road. _____ _____			

PRINT FORM

ENVIRONMENTAL IMPACT STATEMENT REPORT

For:

**CENTRAL NEW YORK INLAND PORT
TOWN OF MANLIUS, NY**

Prepared for:

3Gi
360 ERIE BOULEVARD EAST
SYRACUSE, NY 13202

Prepared by:

 **NAPIERALA
CONSULTING**
PROFESSIONAL ENGINEER, P.C.
SITE • DESIGN • ENGINEERING
110 FAYETTE STREET
MANLIUS, NEW YORK 13104
Telephone: (315) 682-5580
Fax: (315) 682-5544

August, 2019



TABLE OF CONTENTS

1.0	PROJECT SUMMARY	1
1.1	BACKGROUND	1
1.2	PROJECT LOCATION	1
1.3	BUSINESS RELATIONSHIPS	2
1.3.a	INTRANSIT CONTAINER INC. (ICI)	2
1.3.b	NYS ENERGY RESEARCH AND DEVELOPMENT AUTHORITY (NYSERDA)	2
1.4	ECONOMIC DRIVERS & ADVANTAGES	2
1.5	FACILITY OPERATIONS AND PHASING	3
1.6	PROJECT PERMITTING	4
1.7	POTENTIAL BENEFITS	5
2.0	ENVIRONMENTAL CONSIDERATIONS	6
2.1	IMPACT ON LAND	6
2.1.a	VEGETATION	6
2.1.b	SOILS	6
2.1.c	GROUNDWATER	6
2.2	IMPACT ON GEOLOGIC FEATURES	6
2.3	IMPACT ON SURFACE WATER	6
2.3.a	FRESHWATER WETLANDS	6
2.3.b	SOIL EROSION	6
2.4	IMPACT ON FLOODING	7
2.5	IMPACT ON AIR	7
2.6	IMPACT ON PLANTS & ANIMALS	7
2.7	IMPACT ON AGRICULTURAL RESOURCES	7
2.8	IMPACT ON AESTHETIC RESOURCES	7
2.9	IMPACT ON HISTORIC AND ARCHEOLOGICAL RESOURCES	7
2.10	IMPACT ON OPEN SPACE & RECREATION	7
2.11	IMPACT ON CRITICAL ENVIRONMENTAL AREAS	7
2.12	IMPACT ON TRANSPORTATION	7
2.13	IMPACT ON ENERGY	8
2.14	IMPACT ON NOISE, ODOR & LIGHT	8
2.15	IMPACT ON HUMAN HEALTH	8
2.16	CONSISTENCY WITH COMMUNITY PLANS	8
2.17	CONSISTENCY WITH COMMUNITY CHARACTER	8

TABLE OF APPENDICES

APPENDIX A	SITE PLANS
APPENDIX B	SHORT ENVIRONMENTAL ASSESSMENT FORM
APPENDIX C	WETLAND DELINEATION/DETERMINATION REPORT
APPENDIX D	TRAFFIC IMPACT STUDY
APPENDIX E	NRCS SOIL MAPS
APPENDIX F	FEMA FLOODPLAIN MAP



1.0 PROJECT SUMMARY

1.1 BACKGROUND

3Gi CNYIP Inc. (3Gi) is an intermodal infrastructure company committed to advancing global opportunities for importing and exporting goods. The goal of 3Gi is to embrace Third Generation Intermodal (3Gi) concepts and apply them to infrastructure projects that advance the foundation for the United States to compete in the global economy. 3Gi is the leading private entity responsible for the development of the Central New York Inland Port (CNYIP), which will offer increased opportunities for importing and exporting by rail in the Central New York region. The CNYIP will accomplish this by providing infrastructure for dedicated international intermodal service to and from the Port Authority of New York and New Jersey (PANYNJ). By increasing the amount of materials that are transported via rail relative to the amount transported by truck, the project will contribute to more efficient use of energy and reduction in greenhouse gas emissions. The 3Gi CNYIP business model will minimize costs and shipping times, maximize profits, and enhance the import/export markets in NYS.

1.2 PROJECT LOCATION

3Gi's Central New York Inland Port will be integrated into the existing Dewitt Rail Yard located in the Town of Manlius, Onondaga County, New York. The Dewitt Rail Yard is operated by CSX, a Class 1 Freight Railroad. 3Gi owns/controls approximately 200 acres of property that is adjacent to the existing rail yard. The subject property is located to the south of Kirkville Road between Girden Road and Fremont Road. This property will be utilized to expand into and facilitate the operations of an international inland port. The property is not only a part of the NYS Transportation Master Plan, but is also within the federally designated National Highway System Intermodal Corridor, and is therefore eligible for federal funding.

The Class 1 Rail that the CNYIP will be located on runs from the PANYNJ and Boston west to Cleveland. This is known as the Water Level Route because it runs parallel with the Hudson River and Erie Canal and thus provides minimal elevation changes. On the Water Level Route, also known as the Main Line, average travel speeds can be increased and international cargo containers can be stacked two-high, optimizing route efficiency.




Figure 1. Location Map of Project Site



1.3 BUSINESS RELATIONSHIPS

1.3.a INTRANSIT CONTAINER INC. (ICI)

3Gi has a strategic business relationship with Intransit Container, Inc., (ICI), a major northeast inland port owner/operator located in Worcester, Massachusetts, who will be the approved private operating entity for 3Gi. Presently, ICI's Port of Worcester receives more international containers as imports from the PANYNJ than it returns as exports. At the CNYIP, 3Gi plans to address the aggregation and coordination of the regional export market, with a focus on NYS agriculture, one of the region's most valuable resources. 3Gi, in business with ICI, will provide logistic services that match international import containers with exporters who need empty containers.

Coordinating importers and exporters to take full advantage of round trip empty international containers is the primary business opportunity filled by 3Gi CNYIP and ICI Port of Worcester. Currently, empty international containers are carried on the trains but are not serviced at the Dewitt Rail Yard. Thus, regional importers and exporters are not serviced, resulting in lost revenue. Importer's empty containers are available for exporters at a reduced cost to both. For exporters, availability of empty containers is a significant factor for cost effective transportation by train to the PANYNJ. For importers, the cost saving benefit is realized by eliminating one-way empty container returns to the PANYNJ.

Together, 3Gi and ICI fill a need for regional importers and exporters to bring their goods to and receive goods from international markets in the more cost-effective and fuel-efficient manner. This business relationship will allow for significant increases in volume of both imports and exports, particularly those of NYS agriculture and manufactured goods. Given that ICI currently receives more imports than exports and 3Gi's Dewitt CNYIP will expand exports, increased profitability stands to reason.

1.3.b NYS ENERGY RESEARCH AND DEVELOPMENT AUTHORITY (NYSERDA)

The New York State Energy Research and Development Authority (NYSERDA) is a NYS program that promotes energy efficiency and the use of renewable energy resources. The overall goal of the program is to reduce greenhouse gas emissions and to accelerate economic growth. NYSERDA partners with businesses such as 3Gi in order to cooperatively develop and foster conditions that will attract private sector capital investment while enabling New York communities to benefit from improved energy efficiency. Transportation by rail is a much more efficient form of transportation when compared to trucking and therefore presents a great opportunity to reduce statewide greenhouse gas emissions, making the project an ideal candidate for partnership with NYSERDA.

1.4 ECONOMIC DRIVERS & ADVANTAGES

The cost of transporting goods by truck has grown significantly, as well as increased limitations of the trucking industry in its practices and overall capacity. Reliance on trucking for transportation of goods over past decades has proven to be less efficient, costlier, and has negative impacts on highway and transportation maintenance and safety. This issue is further compounded by a shortage of skilled drivers. The effective use of rail in US shipping will increase profitability and improve US economics.

There are major challenges associated with the recent opening of the Panama Canal Third Lock and arrival of large capacity Panamax ships at the PANYNJ. First and foremost is the ever-increasing congestion of trucks in queue for unloading and loading. The CNYIP addresses this challenge by moving international containers that are currently transported by truck to the more efficient mode of transportation: trains. International containers can be directly loaded off the ships onto CSX rail for inland distribution, thus eliminating the need for CNY importers and exporters to truck to the PANYNJ.

The second challenge that is addressed by the CNYIP is the diminishing availability of real estate within reasonable proximity to the PANYNJ. A widespread increase in lease rates on the limited warehousing space in the greater NYC area has created a demand for land within reasonable travel distance to the PANYNJ. The Dewitt Rail Yard is the first stop for CSX on the Main Line and therefore only a few hours from the PANYNJ. The availability of property within reasonable travel time of the rail yard provides businesses with the opportunity to locate around the CNYIP, making it a magnet for both major importers and exporters.

In 2018, New York State funded \$19 million to CSX to make improvements to the DeWitt Rail Yard in order to allow for international container service, which will commence in September of 2019. The commencement of



international container service at the DeWitt Rail Yard equates to an opening of international markets to importers in the CNY region. Additionally, the connection with the Port of Montreal will open up the northern trade market. The ability to reduce transportation costs by switching from trucking to rail will result in major cost savings to both importers and exporters in the area. Agricultural exporters will have access to a larger market at a lower cost, resulting in growth within the industry. By expanding the annual potential to handle upwards of 40,000 to 50,000 international shipping containers by rail directly to and from the PANYNJ, the project will result in improved capacity, profitability, regional growth, public safety, and environmental benefits from reduced CO₂.

1.5 FACILITY OPERATIONS AND PHASING

The development of the on-site operations of the facility will happen in three major phases which will happen semi-concurrently. The first step is the establishment of a container yard for all CSX international containers. CSX would load and unload the double-stack rail cars which 3Gi would immediately dray from CSX to the CNYIP where container processing, customs clearance (if applicable) and coordination between 3Gi and the steamship lines would occur. Truck access to the container yard during this phase will be via Temp Road 1 off of Fremont Road.

The second phase includes the development of on-site warehousing for the short term aggregation of products. This phase will also include the construction of Perm Road 1 or Perm Road 2, thus directing traffic off of Fremont Road and re-routing it through the 3Gi subject site onto Girden Road. An easement currently exists across the property to the west of the subject site adjacent to Girden Road which would serve as the location for Perm Road 1. The location of Perm Road 2 would be across the northern part of the wetland areas to the west of the subject site.

The third phase would involve the laying of track inside the CNYIP owned property to allow for CSX to switch the rail cars into the 3Gi operated container yard. This method provides the ultimate control for 3Gi's customers, allowing control of free time, Free Trade Zones, demurrage, customs clearance, chassis pool, reefer plugs-ins, trans-load opportunities and warehouse facilities. These are generally services CSX does NOT provide. 3Gi would have control of the export loading allowing the ability to aggregate large number of containers to be shipped on the same train, a benefit for volume exporters.




Figure 2. Conceptual Layout of the CNYIP Full Build-Out



A state of the art tracking system will be implemented in order to maximize the movement of containers within the marketplace. This will enable point-to-point control of the containers and the chassis through a GPS locating system. The technology will enable 3Gi to manage delays and other problems along the supply chain where historically chasing information has been time-consuming and expensive. It will also allow for real-time tracking of important information such as temperature control within the container. Effectively matching up importers and exporters in the New England area will help coordinate empty cargo containers from numerous shipping lines moved between the CNYIP, Worcester, and the ships. By utilizing a tracking system to more effectively coordinate cargo movement between CNY and the global marketplace, 3Gi can substantially help importers and exporters who currently pay for a one-way empty container.

By providing short term warehouse storage, primarily supporting agriculture with climate control facilities, 3Gi will maximize the ability to load a train which will also allow it to create a chain of custody from the shipper to the ultimate customer. A comprehensive survey of importers and trade associations within the regional market was performed which concluded that all were supportive of warehousing facilities that would serve as temporary aggregation of product due to the potential of major cost of sale savings.

Terminal overhead, personnel, security, paving, lighting, yard equipment, reefer plugs, a terminal operating computer system, etc., will all be required to provide the services that CNY importers and exporters will expect, as well as the shipping companies, which strictly monitor all container movement to and from the PANYNJ. These operational elements will be provided at the 3Gi CNYIP by ICI, which has proven systems and capacity.

Other responsibilities of 3Gi that will develop concurrently with the CNYIP include, but are not limited to:

- Coordination of all aspects of container logistics, rail/trucking/warehouse container handling;
- Management of gate, ocean manifests, freight releases, customs release, bookings, trucking delivery orders and reconciliation;
- Provide a customs bonded facility and free trade zone;
- Secure gate operation;
- Chassis pool operations;
- Manage notifications from steamship lines, importers, trucker notifications of cargo status;
- Security and storage;
- Direct sales and marketing; and
- Data collection from gate operations to drive market response and growth.

1.6 PROJECT PERMITTING

The Container Pooling Operations (CPO) is the first phase of the CNYIP, facilitating its ability to service the increasing regional export opportunities and aggregate exports in order to maximize cargo trains with a minimum of 50 to 100 international export containers. The project will consist of up to a 2-acre pad to provide storage of empty containers that will become available for regional international export opportunities. 3Gi expects that the CPO pad will continue to expand in 2-acre increments over time.

Phase II will be the development of on-site warehousing for the short term aggregation of products. This phase will also include the construction of an access road onto Girden Road, thus directing traffic off of Fremont Road and re-routing it through the 3Gi subject site.

The project will be phased and permitted on a local and state level through the Town of Manlius for Site Plan approval and through New York State for stormwater, floodplain, and wetland mitigation.



1.7 POTENTIAL BENEFITS

The following is a summary of the public benefits that will result by reducing the number of tractor trailers from New York State highways and conversely shipping by rail over an assumed 30-year service life of the project:

1. Highway and Bridge Avoidance Costs: The reduction of the number of tractor trailers on the highways will result in savings of tax dollars used to maintain public roads and bridges over the service life of the project.
2. Highway Congestion Avoidance: A reduction in the number of tractor trailers on New York State Highways will also result in more lane availability and space for motorists and a reduction of congestion.
3. Improved Highway Safety: By reducing the number of tractor trailer traveling on New York State Highways, it is anticipated that there will be a corresponding reduction in the number of accidents with motorists.
4. Noise Pollution Reduction: By reducing the number of tractor trailers on New York Highways, the CNYIP Project will result in a saving to taxpayers through the avoidance of construction noise mitigation structures.
5. Emission Reduction: By reducing the number of tractor trailers on New York State Highways, an avoided emission amount of 1,291 tons of Carbon Dioxide (CO₂) will be realized in the first year with a total of 28,368 tons of avoided CO₂ over the service life of the project.
6. Fuel Efficiency: Data suggests that rail transportation is approximately four (4) times more efficient than tractor trailers. The conversion to rail achieved by the CNYIP Project will result in a savings of 92,625 gallons of diesel fuel in the first year of the project.

Another major benefit is the potential to reduce pricing through the formation of buying groups. Once a large amount of product is being aggregated for export, a buying group can be formed to work with the major freight companies and syndicates to lower pricing for the exporters in the CNY region. The more product that is aggregated, the more cooperative buying power and influence the buying group will have.

3Gi CNYIP, Inc. commissioned an independent market analysis in July 2012 of CNY importers and exporters to determine the economic benefits for businesses. The data collected includes the following:

- 80% indicated the CNYIP would have a moderate to significant positive impact on their business.
- 53% indicated the increased availability of empty containers and more cost-effective shipping options would have a moderate to significant impact on their export potential.
- 73% indicated that the CNYIP would have moderate to significant job growth and/or retention potential on New York State businesses that import or export.
- 93% indicated they thought the CNYIP would have a moderate to significant positive impact on businesses overall in New York State.

In 2014 and 2015, an additional analysis was conducted by 3Gi CNYIP, Inc. at the request of CSX, to identify importers and exporters in a 50-mile radius. This was done to identify where importers and exporters would match up (by zip code) for container maximization. A total of 176 importers and exporters as well as 35 trade associations were directly visited for input on their actual container volume currently being transported by truck. This sampling alone, tallied up over 20,000 containers being trucked that could convert to rail transportation, saving costs, vehicle miles traveled, and CO₂ reduction. Many of these businesses indicated that transportation costs were a significant cost of sales and consideration in their growth potential as well as retaining their business in NYS.



2.0 ENVIRONMENTAL CONSIDERATIONS

2.1 IMPACT ON LAND

The proposed project will involve the addition of several acres of impervious area over multiple phases. The impervious area will consist of asphalt pavement, warehouse building area, and crushed stone container pads. The land being developed is at a fairly consistent slope and grass/shrub land cover. The involved construction for the proposed action will not be on slopes of 15% or greater and will not be on land where bedrock is exposed. Through all three of the phases, there will not be more than a 1,000 tons of natural material excavated and removed. This proposed action will not cause increases in erosion around the disturbed area and is not located within a Coastal Erosion hazard area.

2.1.a VEGETATION

A majority of the land being developed was previously cleared of all trees as fallow agricultural land and now has a consistent grass cover throughout. A majority of the development will not disturb large amounts of vegetation; however, the access roads into the site from Fremont Road and from Girden Road will involve the clearing of some forested area. These two access roads will also require permitting for the disturbance of land within the 100-year floodplain and DEC freshwater wetlands.

2.1.b SOILS

A majority of the soils found on the project site are classified in the NRCS Soil Map as Niagara silt loam, which is in hydrologic soil group C/D. This indicates that the soils present on site are poorly drained if undeveloped. The NRCS Soil map can be viewed in Appendix E.

2.1.c GROUNDWATER

The impact on groundwater for this project will be negligible. All improvements are on the surface with no planned sub-surface infrastructure for the development. Boring tests have not been performed to determine the average depth to groundwater across the site. This project will not result in new or additional use of ground water, or have the potential to introduce contaminants to the groundwater.

2.2 IMPACT ON GEOLOGIC FEATURES

The proposed action will not result in any modifications or destruction of, or inhibit access to, any unique or unusual land forms. No geologic features are located on the project site.

2.3 IMPACT ON SURFACE WATER

There are no open surface waters located on the project site. The closest water body in proximity to the property is Butternut Creek, which is located on the west side of Girden Road. There are currently no plans to develop on the west side of Girden Road; therefore the project will not impact any surface waters.

2.3.a FRESHWATER WETLANDS

Freshwater wetlands are located on the western portion of the project site to the immediate east of Girden Road. A Wetland Delineation/Determination Report was prepared in November of 2015 to analyze the types of wetlands present and the extents of their boundaries within the subject site. It was concluded that a wetland/upland woodland complex exists on-site which was confirmed via field work after having been initially identified in the NYSDEC and National Wetlands Inventory Maps. The exact boundaries of the wetland can be viewed in Appendix C. The impact to the on-site wetlands will be minimal. Perm Road 1 and Perm Road 2 will both require several smaller wetland crossings. The permitting and location of these crossings will be coordinated with the NYSDEC.

2.3.b SOIL EROSION

The soils identified on site, Niagara silt loam, has an erosion factor (k) of 0.49, giving it an above average susceptibility of sheet and rill erosion if left exposed. However, the development of this site is on a relatively flat



area with no steep slopes and no large lawn areas that would be left disturbed for long periods of time. An effective erosion and sediment control plan would minimize any potential for above average erosion on site.

2.4 IMPACT ON FLOODING

The northwestern portion of the site is located within the 100-year floodplain according to the National Flood Hazard mapping by FEMA. The only portion of the development which is located in the 100-year floodplain is the access road which connects to Girden Road. A large portion of the site is located within the 500-year floodplain, giving a 0.2% chance of flooding, which does not warrant mitigation through compensatory volume. The floodplain map can be viewed in Appendix F.

2.5 IMPACT ON AIR

The development will have a negligible effect on air quality surrounding the site. The only source of emissions on-site will be from the truck traffic through the project site. On a large scale, the increase in shipments by rail will decrease the number of tractor-trailers utilized for cargo transport, and will have a positive effect on overall air quality via a reduction in greenhouse gas emissions.

2.6 IMPACT ON PLANTS & ANIMALS

In the area of the proposed action, the Northern Long-Eared Bat is known to inhabit forested ecosystems. Coordination will need to be done with the NYSDEC to ensure that any tree clearing that will be performed for the construction of the access roads will be done at the correct time of the year so as to not disturb any potential hibernacula.

2.7 IMPACT ON AGRICULTURAL RESOURCES

There is no impact on any agricultural resources in the proposed area. The proposed site is not an active agricultural field and is not a designated agricultural soil region.

2.8 IMPACT ON AESTHETIC RESOURCES

There are no aesthetic resources located on the project site.

2.9 IMPACT ON HISTORIC AND ARCHEOLOGICAL RESOURCES

The proposed action does not occur in or adjacent to a historic or archaeological resource.

2.10 IMPACT ON OPEN SPACE & RECREATION

The development of this project will not result in the loss of recreational opportunities or a reduction of open space resources as designated in any adopted municipal open space plan.

2.11 IMPACT ON CRITICAL ENVIRONMENTAL AREAS

The proposed action is not located within or adjacent to a critical environmental area.

2.12 IMPACT ON TRANSPORTATION

Initially, the site will be accessed via Temp Road 1 off of Fremont Road. At the commencement of Phase 2, a main access to the site will be developed off of Girden Road on the south side of Kirkville Road (either Perm Road 1 or Perm Road 2). A traffic impact study has been compiled for the potential traffic volume accessing the site to and from Girden Road off of Kirkville Road. It was concluded that the proposed development will be a minor traffic generator with less than 20 total vehicles entering or exiting during each peak hour. A detailed analysis of the trip generation estimate and distribution can be viewed in Appendix D.



2.13 IMPACT ON ENERGY

The proposed action will have a small increase in the use of energy. The main source of energy usage will be from the proposed refrigerated storage warehousing. Additionally, the warehouse buildings and access drives will require necessary pole-mounted and building-mounted site lighting. This will not require a new or upgraded substation and does not require an extension of an energy transmission or supply system. This will not utilize more than 2.5 MWhrs per year of electricity.

2.14 IMPACT ON NOISE, ODOR & LIGHT

The proposed action will not result in an increase in sounds or odors, but there will be an increase in outdoor lighting once the project is completed. The foot-candles of the proposed site lighting will not shed onto adjacent properties and will not create sky-glow brighter than existing area conditions; all proposed lighting will be dark-sky compliant.

2.15 IMPACT ON HUMAN HEALTH

There will be no impact to human health and will not create any exposure to any sources of contamination.

2.16 CONSISTENCY WITH COMMUNITY PLANS

The subject property is currently within an agricultural zoning district. This will need to be changed to an industrial zone to allow for the construction and operation of warehousing. Being that the property is directly adjacent to the CSX rail yard and also that the warehousing being proposed will likely store a large amount of agricultural products, the development of this property into an inland port seems like a very logical step.

2.17 CONSISTENCY WITH COMMUNITY CHARACTER

Given the surrounding land usage and the immediate proximity to the CSX rail yard and train tracks, the development of this property into an inland port makes sense from a community character standpoint.



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



APPENDIX A SITE PLANS



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



APPENDIX B
SHORT ENVIRONMENTAL ASSESSMENT FORM



[THIS PAGE IS LEFT INTENTIONALLY BLANK]

Short Environmental Assessment Form

Part 1 - Project Information

Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 – Project and Sponsor Information			
Name of Action or Project: 3Gi - Central New York Inland Port			
Project Location (describe, and attach a location map): Town of Manlius - Industrial corridor adjacent to the CSX Dewitt train yard			
Brief Description of Proposed Action: The project will involve the zone change of three properties adjacent to the CSX rail yard. The construction includes a 2-acre gravel container pooling yard and a 'short term' access road off of Fremont Road to the containment yard. This will also include the construction of a +/- 700 SF modular office building and a truck scale for cargo monitoring.			
Name of Applicant or Sponsor: 3Gi-CNYIP (Contact: Chris Beck)		Telephone: 315-269-7767 E-Mail: ebeck@synapsellc.com	
Address: 360 Erie Blvd East			
City/PO: Syracuse		State: NY	Zip Code: 13202
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.		NO ☒	YES ☐
2. Does the proposed action require a permit, approval or funding from any other government Agency? If Yes, list agency(s) name and permit or approval: Zone Change - Town Board of Manlius, Site Plan Approval - Manlius Planning Board, Wetland Crossing Permit - DEC, SOCPA Approval		NO ☐	YES ☒
3. a. Total acreage of the site of the proposed action? b. Total acreage to be physically disturbed? c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor?		92 acres 3.5 acres 92 acres	
4. Check all land uses that occur on, are adjoining or near the proposed action: 5. ☐ Urban ☒ Rural (non-agriculture) ☒ Industrial ☐ Commercial ☒ Residential (suburban) ☐ Forest ☐ Agriculture ☐ Aquatic ☐ Other(Specify): ☐ Parkland			

5. Is the proposed action, *	NO	YES	N/A
a. A permitted use under the zoning regulations? (w/ proposed zone change to industrial)	☐	☒	☐
b. Consistent with the adopted comprehensive plan?	☐	☐	☒
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?	NO	YES	
	☐	☒	
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area?	NO	YES	
If Yes, identify: _____	☒	☐	
8. a. Will the proposed action result in a substantial increase in traffic above present levels?	NO	YES	
	☒	☐	
b. Are public transportation services available at or near the site of the proposed action?	☒	☐	
c. Are any pedestrian accommodations or bicycle routes available on or near the site of the proposed action?	☒	☐	
9. Does the proposed action meet or exceed the state energy code requirements?	NO	YES	
If the proposed action will exceed requirements, describe design features and technologies: _____ _____	☐	☒	
10. Will the proposed action connect to an existing public/private water supply?	NO	YES	
If No, describe method for providing potable water: _____ _____	☐	☒	
11. Will the proposed action connect to existing wastewater utilities?	NO	YES	
If No, describe method for providing wastewater treatment: _____ _____	☒	☐	
12. a. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district which is listed on the National or State Register of Historic Places, or that has been determined by the Commissioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the State Register of Historic Places?	NO	YES	
	☒	☐	
b. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?	☒	☐	
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?	NO	YES	
	☐	☒	
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody?	☐	☒	
If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres: _____ 0.3 acre impact to jurisdictional wetland to create access to Fremont Road. _____ _____			

PRINT FORM



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



APPENDIX C

WETLAND DELINEATION/DETERMINATION REPORT



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



The Central
New York
Inland Port

Wetland Delineation/Determination Report for the Central New York Inland Port Dewitt/Manlius

November 30th, 2015

(AES Project #15-0277)

Prepared by:
John L. Larson, Ph. D.
Applied Ecological Services, Inc.
17921 Smith Road
Brodhead, WI 53520
(608) 897 - 8641

Submitted to:
CNYIP, Inc
360 Erie BLVB. E.
Syracuse, NY 13202

TABLE OF CONTENTS

1.0 INTRODUCTION	1
2.0 REGULATORY DEFINITIONS	1
3.0 WETLAND DETERMINATION METHODS	3
4.0 RESULTS and DISCUSSION	4
5.0 SUMMARY AND CONCLUSIONS	5
Figures	
1. CNY Parcel Location Map	7
2. CNY Parcel Soils Map	8
3. CNY Parcel NYSDEC/NWI Wetland Inventory Map	9
4. CNY Parcel Topographic Map	10
5. CNY Parcel Wetland Delineation/Determination Map	111
Exhibits	
1. 2015 Site Photographs	13
2. Routine Wetland Delineation Data Forms	19
3. Antecedent Weather (Precipitation)	58

WETLAND DELINEATION/DETERMINATION REPORT

1.0 INTRODUCTION

Applied Ecological Services, Inc. (AES) staff conducted a wetland delineation/determination on approximately 90 acres of land on September 22 and 23, 2015. The site is located at 43.07586 North latitude and 76.03483 West longitude in Syracuse, New York (Figure 1). This report locates a large forested wetland complex in the western side of the parcel, a smaller forested wetland complex on the east side of the parcel and what has been determined to be interior fallow agricultural field wetlands. The delineation is based on AES' best professional judgment and our understanding and interpretation of the *Corps of Engineers Wetland Delineation Manual* (1987) and the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region (2012). No data points were collected in the fallow fields, but vegetation conditions suggests most of the fallow agricultural field areas will meet the definition of wetland. The lead investigator, Dr. John L. Larson has a Ph.D degree in biology with emphasis on wetlands ecology and has conducted over 300 wetland delineations in the past 25 years. Dr. Larson also has taken 2 day and 5 day wetland delineating/training courses and is a Certified Wetland Specialist (CWS) in Lake County, Illinois. Ben Zimmerman and Mike McGraw as well as other AES staff assisted in the wetland delineation.

2.0 REGULATORY DEFINITIONS

Waters of the United States

"Waters of the United States" (WOTUS) are within the jurisdiction of the U.S. Army Corps of Engineers under the Clean Water Act, 1972. WOTUS is a broad term that includes territorial seas or waters that are used or could be used for interstate commerce. The WOTUS designation includes wetlands, ponds, lakes, rivers, tributary streams (including intermittent streams), mud flats, sloughs, and wet meadows. A "Traditional Navigable Water" (TNW) is a navigable water of the U.S. subject to the ebb and flow of the tide and/or are presently used, or have been used in the past, or may be susceptible for use to transport interstate or foreign commerce (33 CFR 329.4). According to the June 5, 2007, Rapanos guidance document, a "tributary" is a natural, man-altered, or man-made water body that carries flow directly or indirectly into TNW. The Rapanos document further defines a "Relatively Permanent Water" (RPW) as a water body (i.e. tributary) with year round flow or at least seasonally (e.g. typically 3 months) continuous flow. A non-RPW is a water body (i.e. tributary) that does not have seasonally continuous flow. Easily traceable underground connections such as drain tiles and pipes can serve as sufficient hydrologic connections for a body of water to be considered a tributary to a WOTUS. A specific, detailed definition of WOTUS can be found in the Federal Register (33 CFR 328.3).

Wetlands

Wetlands are areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. A wetland type that can sometimes be problematic is Farmed Wetlands (FW), and another wetland type that may or may not be regulated by Federal, State, or local Government Agencies are Isolated Wetlands.

Farmed Wetlands (FW) are a type of jurisdictional wetlands that were drained, dredged, filled, leveled, or otherwise manipulated before December 23, 1985, to make production of an agricultural commodity possible, but are often wet enough to still be valuable wetland habitat subject to Swampbuster and Clean Water Act Section 404, 1985. Farmed wetland determinations use the procedures outlined in the National Food Security Act Manual (NFSAM) and are similar to the 1987 Corps Wetland Delineation Manual methodology for atypical wetlands.

Isolated Wetlands are a type of wetlands that generally have no surface water connections to other aquatic resources and are not regulated by the U.S. Army Corps of Engineers Clean Water Act Section 404. The USACE typically considers isolated wetlands to be those of any size that are not adjacent to or do not have a sufficient hydrologic connection to navigable waters.

The *Corps of Engineers Wetland Delineation Manual* (1987) identifies the mandatory technical criteria for wetland identification. The use of this manual along with the use of USGS Topographic Maps, National Wetlands Inventory Maps, NRCS Soil Survey Maps, aerial photos of the site, and climate data are typically used as part of the offsite analysis. The three essential characteristics of a jurisdictional wetland in both the 1987 Corps Wetland Delineation Manual and the recent supplements are hydrophytic vegetation, wetland hydrology, and hydric soils.

Vegetation

The hydrophytic vegetation criteria for wetland classification are met when greater than 50% of the dominant plant species are hydrophytes (Lichvar et al. 2014). The indicator status of plant species is expressed in terms of the estimated probabilities of that species occurring in wetland conditions within a given region. Hydrophytes include all plants classified as "FAC", "FACW" or "OBL." The indicator categories as defined by the Corps are outlined below.

Obligate Wetland (OBL) – Almost always occurs under natural conditions in wetlands.

Facultative Wetland (FACW) – Usually occurs in wetlands, but occasionally found in non-wetlands.

Facultative (FAC) - Equally occurs in wetland and non-wetland.

Facultative Upland (FACU) – Usually occurs in non-wetlands, but occasionally found in wetlands.

Obligate Upland (UPL) – Almost always occurs in uplands.

Hydrology

In order for an area to have wetland hydrology, it must exhibit one or more "primary indicators" and/or two or more "secondary indicators" for Corps jurisdictional and isolated wetlands. Primary indicators include either the direct presence of water as inundation or saturation within the upper 12 inches of the soil profile, or direct evidence of recent inundation, such as water marks, drift lines, sediment deposits, or drainage patterns. Secondary indicators are conditions reflecting the presence of reducing, or anaerobic conditions produced as a consequence of saturation or inundation. Some other primary and or secondary indicators include such conditions as oxidized root channels in the upper 12 inches of the soil profile, water-stained leaves, and a positive "FAC neutral" test (i.e., the dominant vegetation is, on average, hydrophytic).

Soils

The National Technical Committee for Hydric Soils (NTCHS) defines a hydric soil as a soil that formed under conditions of saturation, flooding, or ponding long enough during the growing season to develop anaerobic conditions in the upper part. Nearly all hydric soils exhibit characteristic morphologies that result from repeated periods of saturation or inundation for more than a few days. Saturation or inundation, when combined with microbial activity in the soil, causes the depletion of oxygen. This anaerobiosis promotes certain biogeochemical processes, such as the accumulation of organic matter and the reduction, translocation, or accumulation of iron and other reducible elements. These processes result in distinctive characteristics that persist in the soil during both wet and dry periods, making them particularly useful for identifying hydric soils in the field.

Some of the field indicators include dark color (low chroma), redox features, gleying and/or the presence of a sulfurous odor. Although USDA soil maps are useful for soil identification, they should be used only as general guides. Soils are evaluated directly with a soil probe or by digging a test-pit.

In this report, soil colors are described using the Munsell notation system. This method of describing soil color consists of separate notations for hue, value, and chroma that are combined in that order to form the color designation. *Hue* is the primary or secondary color of the soil (i.e. 10YR). The *value* is a measure of soil darkness. The *chroma* is a measure of soil grayness.

The symbol for *hue* consists of a number from 1 to 10, followed by the letter abbreviation of the color. Within each letter range, the hue becomes more yellow and less red as the numbers increase. The notation for *value* consists of numbers from 0 (pure black) to 5 (gray) to 10 (pure white). The notation for *chroma* consists of numbers beginning with /0 (very gray) to /8. A soil described as 10YR 3/1 has a hue of 10YR, a value of 3 and a chroma of 1.

3.0 WETLAND DETERMINATION METHODS

Map Review

Several sources of information were reviewed to evaluate the site and identify potential wetland soil units and wetlands on the parcel. The general topography and elevation of the site was reviewed using an online five foot contour map (LiDAR). Soil types were identified using the U.S Department of Agriculture Natural Resource Conservation Service (NRCS) Web Soil Survey map. Potential wetlands were identified using a *National Wetland Inventory* (NWI) NYSDEC wetland maps and previous wetland delineation wetland maps. Maps can only be used to establish the probability and approximate location of wetlands on the site; therefore, the US Army Corps of Engineers (USACE) do not accept the use of these maps to make final wetland determinations. Final wetland determinations were made with on-site observations and fieldwork. Prior to the fieldwork, background information was reviewed to establish the probability and approximate location of wetlands on the site. The following maps or photographs were reviewed offsite or onsite as part of the wetland determination.

- *Soil Survey Map* - The NRCS Web Soil Survey Map (Figure 2) identifies eight soil series within the site boundaries with five being the most abundant; Mta, Lm, Nga, Lk and Ga (A&B).
- *NWI & NYSDES Map* - The Northwest and NYSDEC Wetland Inventory Map of the area (Figure 3) shows the forested wetland along the west end of the parcel and the forested wetland on portions of the east side of the parcel.
- *Topography Map* - The five foot contour map (Figure 4) shows the general flat topography of the site, with lowest elevations on the west side and highest elevation on the east side of the parcel.

Site Investigation and Description

AES inspected the 90 acre site on September 22 and 23, 2015. The delineation of the wetlands within the site is based on the methodology described in the Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Supplement (2012) as required by current Corps policy.

The project area was inspected with the intent of locating wetlands and determining wetland boundaries. Thirteen soil pits were dug in the western forested area. The western area is comprised of a wetland/upland wooded complex with an area of historic fill. Soil pits were dug to a sufficient depth (14-26 inches) to locate and describe the soil conditions. At each of the four soil pits a NC/NE wetland delineation data form was filled out and a determination was made for each test soil pit as to whether it

was located in a wetland or upland. The wetland boundary was flagged and GPS surveyed with a hand held Trimble unit with sub-meter accuracy. In the fallow field areas, no data points were collected as it was evident that these fields have reverted back to wetland conditions. A return visit will likely be required to further delineate and confirm wetlands in these agricultural fields. The eastern portion of the parcel also contains a wooded wetland complex, somewhat more degraded than the western woods. Historic areas of fill also occur in the eastern side of the parcel.

Site Photographs

Photographs of the site taken in 2015 are located in Exhibit 1. These photographs are the visual documentation of site conditions at the time of inspection. The photographs are intended to provide representative visual samples of soil test pits, wetlands, uplands data points, or other special features found on or near the site investigated.

Routine Wetland Delineation Data Forms

Completed Routine Wetland Delineation Data Forms- Northcentral and Northeast Region for this delineation are located in Exhibit 2. These forms are the written documentation of how the 13 Data Points meet or do not meet each of the wetland criteria.

4.0 RESULTS & DISCUSSION

Site Conditions

General

The antecedent precipitation total for the three months prior to the field delineation work (July, August and September) was 7.35 inches (Exhibit 3). The average precipitation for these three months is 11.73 inches with a 30% threshold for a "dry" condition at 8.75 inches. Thus, antecedent precipitation was outside the normal range and represented a "dry" precipitation condition at the time of the wetland field work.

The 90 acre site is comprised of a wetland/upland woodland complex on the west, a wetland woodland and fill on the east with fallow agricultural fields in the center of the parcel. The NWI and NYSDEC map identifies forested wetlands as occurring in the west and east ends of the parcel (Figure 3), which was confirmed in this field work. However, the NYSDEC wetland map did not differentiate the smaller upland knolls delineated in the western woodland complex (Figure 5). The five-foot topographic map of the area investigated shows that the parcel is essentially flat (Figure 4) with a slight gradual rise from west to east. The fallow agricultural fields represent a disturbed and problematic condition. The property's wetlands had previously been delineated by two firms and the wetland boundaries were substantially different from each other. Thus this delineation was completed to update the previous two delineation results.

Wetlands

Data Points:

Data Points 1, 3, 5, 8, 11 and 12 (Figure 5) documented the existing forested wetland condition on the west side of the parcel and had all three required indicators (vegetation, hydrology, soils). The dominant vegetation identified in the forested wetland areas was usually red maple (*Acer rubrum*), American elm (*Ulmus americana*), sensitive fern (*Onoclea sensibilis*) and calico aster (*Symphotrichum lateriflorum*) (Exhibit 2). Examination of the soils and the test pits in the wetland found that the top layer of soil consisted of a dark colored sandy topsoil with a redox concentrations in the matrix below.

Uplands

Data Points

Upland Data Points 2, 4, 6, 7, 9, 10 & 13 (Figure 5) were sampled in upland woods within the larger wet forest community. Red maple, cherry (*Prunus serotina*) and woodbine (*Parthenocissus quinquefolia*) were the typical upland woods dominants (Exhibit 2).

5.0 SUMMARY AND CONCLUSIONS

Based on the review of soils, NWI, NYSDEC wetland maps, topography and previous delineation maps and the on-site field determination conducted on September 22 & 23 2015 it was apparent that wetlands and wetland vegetation dominant the 90 acre parcel (Figure 5). Investigations of the fallow areas in the center of the property found hydric vegetation throughout including sedges, red top grass, purple loosestrife and giant reed grass. The wetland boundary was GPS surveyed by AES. The wetlands in the fallowed farm fields likely meet the USACE definition of wetland, but will likely require confirmation during the 2016 growing season.

Literature Cited

- Lichvar, R.W., M. Butterwick, N.C. Melvin, and W.N. Kirchner. 2014. The National Wetland Plant List: 2014 update of Wetland Ratings. *Phytoneuron* 2014-41:1-42. Northcentral and Northeast Region
- U.S. Army Corps of Engineers. 2011. Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Northcentral and Northeast Region (Version 2.0), ed. J.S. Wakeley, R. Lichvar, C.V. Noble and J.F. Berkowitz. ERDC/EL TR-12-1. Vicksburg, MS: U.S. Army Engineer Research and Development Center.

FIGURES

Figure 1. CNY Parcel Location Map




Figure 2. CNY Parcel Soils Map.




Figure 3. CNY Parcel National Wetlands and NYSDEC Inventory Map




Figure 4. CNY Parcel Topography Map





Figure 5. CNY Parcel Wetland Delineation and Wetland Determination Map



EXHIBITS

EXHIBIT 1. Site Photographs of the CNY parcel taken on September 22 and 23 , 2015.



Photo 1. Wetland soils at Data Point 1.



Photo 2. Wooded wetland near Data Point 1.




Photo 3. Upland soils at Data Point 2.



Photo 4. Upland woods at Data Point 2.



Photo 5. Upland soils at Data Point 3. Vegetation was hydrophytic



Photo 6. Forested wetland near Data Point 3



Photo 7. Wetland soils at Data Point 5




Photo 8. Forested wetland near Data Point 5




Photo 9. Forested wetland.




Photo 10. Forested wetland.




Photo 11. Forested wetland.




Photo 12. West edge of fallow field with reed canary grass and purple loosestrife.




Photo 13. Fallow field reverted to wetland with purple loosestrife.



Photo 14. Upland soil at Data Point 10




Photo 15. Upland forest conditions at Data Point 10




Photo 16. Wetland soils at Data Point 11



Photo 17. Wetland forest conditions near data point 11




Photo 18. Forested wetland in the vicinity of data point 11.




Photo 19. Upland wooded knoll




Photo 20. Young forested wetland at north end near data point 12.



Photo 21. Upland woods at north end of property near data point 13.

EXHIBIT 2. Routine Wetland Delineation Data Forms – Northcentral & Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 1	
Investigator(s): JLL, SV			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none): Concave Slope (%)			
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Lamson very fine sandy loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present? Yes ☒ No ☐	
Wetland Hydrology Present?	Yes ☒ No ☐	Is the Sampled Area within a Wetland? Yes ☒ No ☐ If yes, optional Wetland Site ID:	
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☒ Water-Stained Leaves (B9)	☒ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☒ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☒ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☒ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒	Depth (inches):	Wetland Hydrology Present? Yes ☒ No ☐
Water Table Present? Yes ☐ No ☒	Depth (inches):	
Saturation Present? Yes ☐ No ☒	Depth (inches):	
(includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks:		
Red maple hardwood swamp w/hummocky vegetation drainage patterns.		

VEGETATION – Use scientific names of plants

Sampling Point: 1

Tree Stratum (Plot size): 15m	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer rubrum</i>	25	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>6</u> (A) Total number of dominant species across all strata: <u>6</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>100</u> (A/B)	
2. <i>Ulmus americana</i>	10	Yes	FACW		
3. <i>Fraxinus pennsylvanica</i>	10	Yes	FACW		
4.					
5.					
	45	= Total Cover			
Sapling/Shrub Stratum (Plot size): 5m				Prevalence Index Worksheet:	
1. <i>Lindera benzoin</i>	10	Yes	FACW	Total % Cover of:	Multiply by:
2. <i>Ulmus americana</i>	10	Yes	FACW	OBL Species	X 1 =
3. <i>Rhamnus cathartica</i>	5	No	FAC	FACW Species	X 2 =
4. <i>Fraxinus pennsylvanica</i>	2	No	FAC	FAC Species	X 3 =
5.				FACU Species	X 4 =
	27	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size): 1m ²				Column Totals:	A) (B)
1. <i>Cinna arundinacea</i>	3	No	FACW	Prevalence Index = B/A =	
2. <i>Polygonum virginianum</i>	5	No	FAC		
3. <i>Epilobium coloratum</i>	2	No	OBL	Hydrophytic Vegetation Indicators:	
4. <i>Geum canadense</i>	2	No	FAC	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Rhus radicans</i>	10	Yes	FAC	☒ Dominance Test is >50%	
6. <i>Oxalis stricta</i>	1	No	UPL	☐ Prevalence Index is ≤ 3.0 ¹	
7. <i>Glyceria striata</i>	3	No	FACW	☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8. <i>Ribes americanum</i>	5	No	FACW	☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9. <i>Symphyotrichum lateriflorum</i>	2	No	FACW	¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10. <i>Rhamnus cathartica</i>	2	No	FAC		
11. <i>Onoclea sensibilis</i>	2	No	FACW		
Total	37	= Total Cover			
1.				Hydrophytic Vegetation Present? Yes ☒ No ☐	
2.					
	0	= Total Cover			
Definitions of Vegetation Strata: Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height. Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall. Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall. Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet). Dominated by wetland plants					

SOILS

Sampling Point 1

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-12	10 YR 2/1						sandy silt loam	
12-	10 YR 5/2		10 YR 5/4	10			Sandy silt loam	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☒ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☒ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)
³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.		
Restrictive Layer (if observed):	Hydric Soil Present? Yes ☒ No ☐	
Type:		
Depth (inches):		
Remarks:		
Thick dark surface in swale concave swale within wetland upland complex.		

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 2	
Investigator(s): JLL, SV, MM			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%) Flat	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Minoa fine sandy loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☐ No ☒	Hydric Soil Present? Yes ☐ No ☒	
Wetland Hydrology Present?	Yes ☐ No ☒	Is the Sampled Area within a Wetland? Yes ☐ No ☒	If yes, optional Wetland Site ID:
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):	Wetland Hydrology Present? Yes ☐ No ☒	
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches): (includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks:		

VEGETATION – Use scientific names of plants

Sampling Point: 2

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Prunus serotina</i>	10	Yes	FACU	Number of Dominant Species that are OBL, FACW, or FAC: <u>3</u> (A) Total number of dominant species across all strata: <u>6</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>50</u> (A/B)	
2. <i>Acer rubrum</i>	25	Yes	FAC		
3.					
4.					
5.					
	35	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Nyssa sylvatica</i>	15	Yes	FAC	Total % Cover of:	Multiply by:
2. <i>Prunus virginiana</i>	5	Yes	FACU	OBL Species 0	X 1 = 0
3.				FACW Species 0	X 2 = 0
4.				FAC Species 60	X 3 = 180
5.				FACU Species 40	X 4 = 160
	20	= Total Cover		UPL Species 0	X 5 = 0
Herb Stratum (Plot size):				Column Totals: 100 A)	340 (B)
1. <i>Prunus virginiana</i>	5	No	FACU	Prevalence Index = B/A = 3.4	
2. <i>Fraxinus pennsylvanica</i>	3	No	FACW		
3. <i>Rhus radicans</i>	20	Yes	FAC	Hydrophytic Vegetation Indicators:	
4. <i>Parthenocissus quinquefolia</i>	25	Yes	FACU	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Viburnum dentatum</i>	5	No	UPL	☐ Dominance Test is >50%	
6. <i>Fragaria virginiana</i>	2	No	FAC	☐ Prevalence Index is ≤ 3.0 ¹	
7. <i>Acer rubrum</i>	1	No	FAC	☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8. <i>Prunus serotina</i>	5	No	FACU	☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	66	= Total Cover			
Woody Vine Stratum (Plot size):					
1.				Hydrophytic Vegetation Present? Yes ☐ No ☒	
2.					
		= Total Cover			
Definitions of Vegetation Strata: Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height. Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall. Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall. Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					

SOILS

Sampling Point 2

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-8	10 YR 3/2						Silty sand loam	
8-12	10 YR 5/6						Sand	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒
Type:	
Depth (inches):	

Remarks: bright color representing oxidized condition

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 3	
Investigator(s): John Larson			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%)	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Naumburg loamy fine sand			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present? Yes ☐ No ☒	
Wetland Hydrology Present?	Yes ☒ No ☐	Is the Sampled Area within a Wetland? Yes ☒ No ☐	If yes, optional Wetland Site ID:
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☒ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☒ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):	Wetland Hydrology Present? Yes ☒ No ☐	
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches): (includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks: Occasional swamp white oak- <i>Quercus bicolor</i>		

VEGETATION – Use scientific names of plants

Sampling Point: 3

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer rubrum</i>	50	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>4</u> (A) Total number of dominant species across all strata: <u>4</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>100</u> (A/B)	
2. <i>Nyssa sylvatica</i>	25	Yes	FAC		
3.					
4.					
5.					
	75	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Acer rubrum</i>	10	Yes	FAC	Total % Cover of:	Multiply by:
2.				OBL Species	X 1 =
3.				FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	10	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals:	A) (B)
1. <i>Rhus radicans</i>	20	Yes	FAC	Prevalence Index = B/A =	
2. <i>Onoclea sensibilis</i>	5	No	FACW		
3. <i>Cornus racemosa</i>	2	No	FACW	Hydrophytic Vegetation Indicators:	
4. <i>Viburnum dentatum</i>	2	No	UPL	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Spiraea alba</i>	1	No	FACW	☒ Dominance Test is >50%	
6.				☐ Prevalence Index is $\leq 3.0^1$	
7.				☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	30	= Total Cover			
Woody Vine Stratum (Plot size):					
1.				Hydrophytic Vegetation Present? Yes ☒ No ☐	
2.					
		= Total Cover			
Definitions of Vegetation Strata: Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height. Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall. Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall. Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					

US Army Corps of Engineers

Northcentral and Northeast Region –Version 2.0

SOILS

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)							
Depth (inches)	Matrix		Redox Features			Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹		
0-11	7.5 YR 3/2					sandy loam	
11-16	10 YR 5/6	75				Sandy loam	
	7.5 YR 4/6	25				sandy loam	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)
³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.		
Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒	
Type:		
Depth (inches):		
Remarks: While soils appeared to be non-hydric the other two indicators were present. This could be a problem area, so delineated as wetland		

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 4	
Investigator(s): John Larson			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%) 2	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Lamson very fine sandy loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☐ No ☒	Hydric Soil Present? Yes ☐ No ☒	
Wetland Hydrology Present?	Yes ☐ No ☒	Is the Sampled Area within a Wetland? Yes ☐ No ☒	If yes, optional Wetland Site ID:
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:			
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)	
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)	
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)	
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)	
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)	
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)	
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)	
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)	
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)	
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)	
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)	
		☐ FAC-Neutral Test (D5)	
Field Observations:			
Surface Water Present? Yes ☐ No ☒ Depth (inches):		Wetland Hydrology Present? Yes ☐ No ☒	
Water Table Present? Yes ☐ No ☒ Depth (inches):			
Saturation Present? Yes ☐ No ☒ Depth (inches): (includes capillary fringe)			
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:			
Remarks:			

VEGETATION – Use scientific names of plants

Sampling Point: 4

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer rubrum</i>	15	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>2</u> (A) Total number of dominant species across all strata: <u>6</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>33</u> (A/B)	
2. <i>Populus tremuloides</i>	15	Yes	FACU		
3. <i>Prunus serotina</i>	10	Yes	FACU		
4. <i>Populus deltoides</i>	5	No	FAC		
5.					
	45	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Fraxinus pennsylvanica</i>	5	Yes	FACW	Total % Cover of:	Multiply by:
2. <i>Lonicera tatarica</i>	5	Yes	UPL	OBL Species	X 1 =
3.				FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	10	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals:	A) (B)
1. <i>Parthenocissus quinquefolia</i>	25	Yes	FACU	Prevalence Index = B/A =	
2. <i>Fraxinus sp.</i>	10	Yes	NI		
3. <i>Fragaria virginiana</i>	2	No	FAC	Hydrophytic Vegetation Indicators:	
4. <i>Rhus radicans</i>	5	No	FAC	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Solidago ulmifolia</i>	5	No	UPL	☐ Dominance Test is >50%	
6.				☐ Prevalence Index is ≤ 3.0 ¹	
7.				☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	47	= Total Cover			
Woody Vine Stratum (Plot size):				Hydrophytic Vegetation Present? Yes ☐ No ☒	
1.					
2.					
		= Total Cover			
Definitions of Vegetation Strata:					
Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height.					
Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall.					
Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall.					
Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					

SOILS

Sampling Point 4

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-8	10 YR 3/2						Sandy loam	
8-16	10 YR 4/4	95						
16+	10 YR 6/2	2-3	10 YR 5/8	2				

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)
³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.		
Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒	
Type:		
Depth (inches):		
Remarks:		

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 5	
Investigator(s): John Larson, SV			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%) Flat	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Niagara silt loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present?	Yes ☒ No ☐
Wetland Hydrology Present?	Yes ☒ No ☐	Is the Sampled Area within a Wetland? Yes ☒ No ☐ If yes, optional Wetland Site ID:	
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☒ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☒ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☒ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☒ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☒ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):		Wetland Hydrology Present? Yes ☒ No ☐
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches): (includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks:		

VEGETATION – Use scientific names of plants

Sampling Point: 5

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer saccharinum</i>	50	Yes	FACW	Number of Dominant Species that are OBL, FACW, or FAC: <u>6</u> (A) Total number of dominant species across all strata: <u>6</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>100</u> (A/B)	
2. <i>Ulmus americana</i>	10	No	FACW		
3. <i>Populus tremuloides</i>	2	No	FAC		
4.					
5.					
	62	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Fraxinus pennsylvanica</i>	5	Yes	FACW	Total % Cover of:	Multiply by:
2. <i>Viburnum lentago</i>	5	Yes	FAC	OBL Species	X 1 =
3.				FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	10	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals: A)	(B)
1. <i>Onoclea sensibilis</i>	50	Yes	FACW	Prevalence Index = B/A =	
2. <i>Symphyotrichum umbellatum</i>	5	No	FACW		
3. <i>Chelone glabra</i>	2	No	OBL	Hydrophytic Vegetation Indicators:	
4. <i>Impatiens capensis</i>	2	No	FACW	☐ Rapid Test for Hydrophytic Vegetation ☒ Dominance Test is >50% ☐ Prevalence Index is ≤ 3.0 ¹ ☐ Morphological Adaptations ¹ (Provide supporting data in Remarks) ☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
5.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
6.					
7.					
8.					
9.					
10.					
	59	= Total Cover			
Woody Vine Stratum (Plot size):					
1. <i>Rhus radicans</i>	5	Yes	FAC	Hydrophytic Vegetation Present? Yes ☒ No ☐	
2. <i>Vitis riparia</i>	2	Yes	FACW		
	7	= Total Cover			
Definitions of Vegetation Strata: Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height. Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall. Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall. Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					

SOILS

Sampling Point 5

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-8	10 YR 2/1						Silt loam	
8-16	10 YR 2/1	80	10YR 4/2	80	D	M	silt loam	
Depletion								

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histic Sol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☒ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):	Hydric Soil Present? Yes ☒ No ☐
Type:	
Depth (inches):	

Remarks:

Depleted matrix
Gley mixed in soils

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 6	
Investigator(s): John Larson, MM			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%) 2-3	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Galen very fine sandy loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present?	Yes ☐ No ☒
Wetland Hydrology Present?	Yes ☐ No ☒	Is the Sampled Area within a Wetland? Yes ☐ No ☒ If yes, optional Wetland Site ID:	
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):		Wetland Hydrology Present? Yes ☐ No ☒
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches): (includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks:		

VEGETATION – Use scientific names of plants

Sampling Point: 6

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer rubrum</i>	25	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>4</u> (A) Total number of dominant species across all strata: <u>6</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>66</u> (A/B)	
2. <i>Ulmus americana</i>	10	Yes	FACW		
3. <i>Nyssa sylvatica</i>	10	Yes	FAC		
4.					
5.					
	45	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Prunus serotina</i>	10	Yes	FACU	Total % Cover of:	Multiply by:
2. <i>Acer rubrum</i>	5	Yes	FAC	OBL Species	X 1 =
3. <i>Fraxinus americana</i>	2	No	FACU	FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	17	= Total Cover		UPL Species	X 5 =
				Column Totals: A)	(B)
Herb Stratum (Plot size):				Prevalence Index = B/A =	
1. <i>Parthenocissus quinquefolia</i>	75	Yes	FACU		
2. <i>Solidago ulmifolia</i>	2	No	UPL		
3. <i>Prunus serotina</i>	5	No	FACU	Hydrophytic Vegetation Indicators:	
4. <i>Onoclea sensibilis</i>	2	No	FACW	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Rhus radicans</i>	2	No	FAC	☒ Dominance Test is >50%	
6.				☐ Prevalence Index is ≤ 3.0 ¹	
7.				☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	86	= Total Cover			
Woody Vine Stratum (Plot size):					
1.				Hydrophytic Vegetation Present? Yes ☒ No ☐	
2.					
		= Total Cover			
Definitions of Vegetation Strata:					
Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height.					
Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall.					
Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall.					
Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					

SOILS

Sampling Point 6

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)							
Depth (inches)	Matrix		Redox Features			Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹		
0-10	10 YR 5/2					Sandy silt loam	
10-16	10 YR 5/6					sandy silt loam	
16+	10 YR 5/3	5	10 YR 4/6			Sandy silt loam	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)
³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.		
Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒	
Type:		
Depth (inches):		
Remarks: Bright color (oxidized at depth)		

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 7	
Investigator(s): JLL, MM			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)			Local relief (concave, convex, none): Convex Slope (%)		
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Niagara silt loam			NYSDEC/NWI classification: No		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☐ No ☒	Hydric Soil Present? Yes ☐ No ☒	
Wetland Hydrology Present?	Yes ☐ No ☒	Is the Sampled Area within a Wetland? Yes ☐ No ☒	If yes, optional Wetland Site ID:
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒	Depth (inches):	Wetland Hydrology Present? Yes ☐ No ☒
Water Table Present? Yes ☐ No ☒	Depth (inches):	
Saturation Present? Yes ☐ No ☒	Depth (inches):	
(includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks: Soil dry sandy.		

VEGETATION – Use scientific names of plants

Sampling Point: 7

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Prunus serotina</i>	25	Yes	FACU	Number of Dominant Species that are OBL, FACW, or FAC: <u>2</u> (A) Total number of dominant species across all strata: <u>4</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>50</u> (A/B)	
2. <i>Acer rubrum</i>	25	Yes	FAC		
3. <i>Ulmus americana</i>	5	No	FACW		
4.					
5.					
	55	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Acer rubrum</i>	10	Yes	FAC	Total % Cover of:	Multiply by:
2.				OBL Species	X 1 =
3.				FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	10	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals: A)	(B)
1. <i>Parthenocissus quinquefolia</i>	75	Yes	FACU	Prevalence Index = B/A =	
2. <i>Rhus radicans</i>	5	No	FAC		
3. <i>Quercus rubra</i>	1	No	FACU	Hydrophytic Vegetation Indicators:	
4. <i>Rhamnus cathartica</i>	3	No	FAC	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Prunus virginiana</i>	2	No	FACU	☐ Dominance Test is >50%	
6. <i>Rubus allegheniensis</i>	2	No	FACU	☐ Prevalence Index is ≤ 3.0 ¹	
7.				☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	88	= Total Cover			
Woody Vine Stratum (Plot size):					
1. <i>Vitis riparia</i>	3	No	FACW	Hydrophytic Vegetation Present? Yes ☐ No ☒	
2.					
	3	= Total Cover			
Definitions of Vegetation Strata: Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height. Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall. Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall. Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet). Convex knoll – soils not hydric					

SOILS

Sampling Point 7

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)							
Depth (inches)	Matrix		Redox Features			Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹		
0-8	10 YR 3/2					Sandy silt loam	
8-12	10 YR 3/4		10 YR 4/4			Sandy loam	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒
Type:	
Depth (inches):	

Remarks:

Bright soils at depth (brownish)

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 8	
Investigator(s): JLL, MM			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%) concave swale	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Galen very fine sandy loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present? Yes ☒ No ☐	
Wetland Hydrology Present?	Yes ☒ No ☐	Is the Sampled Area within a Wetland? Yes ☒ No ☐	If yes, optional Wetland Site ID:
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☒ Water-Stained Leaves (B9)	☒ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☒ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☒ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☒ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):		Wetland Hydrology Present? Yes ☒ No ☐
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches):		
(includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks: Swale between data points 6 and 9.		

Sampling Point: 8

Northcentral and Northeast Region -Version 2.0

SOILS

Sampling Point 8

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-8	10 YR 2/1						Sandy loam	
8-16	10 YR 2/1		10YR 5/2	2-3	D	N	sandy loam	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☒ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):	Hydric Soil Present? Yes ☒ No ☐
Type:	
Depth (inches):	
Remarks:	

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 9	
Investigator(s): John Larson			Section, Township, Range:		
Landform (Hillslope, terrace, etc.) Convex		Local relief (concave, convex, none): Convex Slope (%) 1-3			
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Galen very fine sandy loam			NYSEDC/NWI classification: No		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☐ No ☒	Hydric Soil Present? Yes ☐ No ☒	
Wetland Hydrology Present?	Yes ☐ No ☒	Is the Sampled Area within a Wetland? Yes ☐ No ☒	
If yes, optional Wetland Site ID:			
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):	Wetland Hydrology Present? Yes ☐ No ☒	
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches): (includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks:		

VEGETATION – Use scientific names of plants

Sampling Point: 9

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer rubrum</i>	50	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>1</u> (A) Total number of dominant species across all strata: <u>4</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>25</u> (A/B)	
2. <i>Prunus serotina</i>	20	Yes	FACU		
3.					
4.					
5.					
	70	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Prunus serotina</i>	10	Yes	FACU	Total % Cover of:	Multiply by:
2.				OBL Species	X 1 =
3.				FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	10	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals:	A) (B)
1. <i>Parthenocissus quinquefolia</i>	75	Yes	FACU	Prevalence Index = B/A =	
2. <i>Prunus serotina</i>	2	No	FACU		
3. <i>Rhus radicans</i>	5	No	FAC	Hydrophytic Vegetation Indicators:	
4. <i>Carya ovata</i>	3	No	FACU	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Prunus virginiana</i>	3	No	FACU	☐ Dominance Test is >50%	
6.				☐ Prevalence Index is ≤ 3.0 ¹	
7.				☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	88	= Total Cover			
Woody Vine Stratum (Plot size):					
1. <i>Vitis riparia</i>	3	No	FACW	Hydrophytic Vegetation Present? Yes ☐ No ☒	
2.					
	3	= Total Cover			
Definitions of Vegetation Strata:					
Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height.					
Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall.					
Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall.					
Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					

SOILS

Sampling Point 9

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-8	10 YR 3/2						Sandy loam	
8-14	7.5 YR 4/6						Sand	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)
³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.		
Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒	
Type:		
Depth (inches):		
Remarks:		

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 10	
Investigator(s): John Larson			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none): convex Slope (%)			
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Minoa fine sandy loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present?	Yes ☐ No ☒
Wetland Hydrology Present?	Yes ☐ No ☒	Is the Sampled Area within a Wetland?	Yes ☐ No ☒
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):		Wetland Hydrology Present? Yes ☐ No ☒
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches): (includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks: Upland Knoll		

VEGETATION – Use scientific names of plants

Sampling Point: 10

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer rubrum</i>	70	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>3</u> (A) Total number of dominant species across all strata: <u>5</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>60</u> (A/B)	
2. <i>Prunus serotina</i>	10	No	FACU		
3. <i>Ulmus americana</i>	10	No	FACW		
4.					
5.					
	90	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Prunus serotina</i>	25	Yes	FACU	Total % Cover of:	Multiply by:
2. <i>Nyssa sylvatica</i>	10	Yes	FAC	OBL Species	X 1 =
3.				FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	35	= Total Cover		UPL Species	X 5 =
				Column Totals: A)	(B)
Herb Stratum (Plot size):				Prevalence Index = B/A =	
1. <i>Parthenocissus quinquefolia</i>	25	Yes	FACU		
2. <i>Rhus radicans</i>	20	Yes	FAC		
3. <i>Glyceria striata</i>	10	No	FACW	Hydrophytic Vegetation Indicators:	
4. <i>Circaea lutetiana canadensis</i>	2	No	FACU	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Onoclea sensibilis</i>	5	No	FACW	☒ Dominance Test is >50%	
6. <i>Fragaria virginiana</i>	3	No	FAC	☐ Prevalence Index is ≤ 3.0 ¹	
7. <i>Polygonum virginianum</i>	2	No	FAC	☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	67	= Total Cover			
Woody Vine Stratum (Plot size):					
1.				Hydrophytic Vegetation Present? Yes ☒ No ☐	
2.					
		= Total Cover			
Definitions of Vegetation Strata: Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height. Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall. Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall. Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet). 					

SOILS

Sampling Point 10

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-8	10 YR 4/2						Sandy loam	
8-12+	10 YR 5/4						Clay in soils	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒
Type:	
Depth (inches):	
Remarks:	

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 11	
Investigator(s): John Larson			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%) Concave to flat	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Lamson very fine sandy loam			NYSDEC classification: Yes		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present? Yes ☒ No ☐	
Wetland Hydrology Present?	Yes ☒ No ☐	Is the Sampled Area within a Wetland? Yes ☒ No ☐	If yes, optional Wetland Site ID:
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☒ Water-Stained Leaves (B9)	☒ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☒ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☒ Sparsely Vegetated Concave Surface (B8)		☒ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒ Depth (inches):	Wetland Hydrology Present? Yes ☒ No ☐	
Water Table Present? Yes ☐ No ☒ Depth (inches):		
Saturation Present? Yes ☐ No ☒ Depth (inches):		
(includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks: FW in south		

VEGETATION – Use scientific names of plants

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Acer rubrum</i>	60	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>3</u> (A) Total number of dominant species across all strata: <u>3</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>100</u> (A/B)	
2. <i>Fraxinus pennsylvanica</i>	10	No	FACW		
3. <i>Tilia americana</i>	10	No	FACU		
4.					
5.					
	80	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Carpinus caroliniana</i>	20	Yes	FAC	Total % Cover of:	Multiply by:
2. <i>Ulmus americana</i>	5	No	FACW	OBL Species	X 1 =
3. <i>Hamamelis virginiana</i>	5	No	FACU	FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	30	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals: A)	(B)
1. <i>Rubus flagellaris</i>	5	No	FACU	Prevalence Index = B/A =	
2. <i>Rhus radicans</i>	10	Yes	FAC		
3. <i>Polygonum virginianum</i>	5	No	FAC	Hydrophytic Vegetation Indicators:	
4. <i>Ulmus americana</i>	2	No	FACW	☐ Rapid Test for Hydrophytic Vegetation	
5. <i>Carpinus caroliniana</i>	2	No	FAC	☒ Dominance Test is >50%	
6. <i>Solidago flexicaulis</i>	2	No	FACU	☐ Prevalence Index is ≤ 3.0 ¹	
7. <i>Leersia oryzoides</i>	2	No	OBL	☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	38	= Total Cover			
Woody Vine Stratum (Plot size):				Hydrophytic Vegetation Present? Yes ☒ No ☐	
1.					
2.					
		= Total Cover			
Definitions of Vegetation Strata:					
Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height.					
Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall.					
Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall.					
Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					

SOILS

Sampling Point 11

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-14	10 YR 2/1						Sandy silt loam	
14+	10 YR 6/2		10 YR 5/6	5	C	N	Sandy clay loam	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☒ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)
³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.		
Restrictive Layer (if observed):	Hydric Soil Present? Yes ☒ No ☐	
Type:		
Depth (inches):		
Remarks:		

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 12	
Investigator(s): John Larson, Susan Lehnhardt			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)			Local relief (concave, convex, none): Flat Slope (%)		
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Niagara silt loam			NYSEDC/NWI classification: No		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☒ No ☐	Hydric Soil Present? Yes ☒ No ☐	
Wetland Hydrology Present?	Yes ☒ No ☐	Is the Sampled Area within a Wetland? Yes ☒ No ☐	
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:			Secondary Indicators (minimum of 2 required)	
Primary Indicators (minimum of one is required: check all that apply).				
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☒ Surface Soil Cracks (B6)		
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☒ Drainage Patterns (B10)		
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)		
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)		
☐ Sediment Deposits (B2)	☐ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)		
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)		
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)		
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)		
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)		
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)		
		☐ FAC-Neutral Test (D5)		
Field Observations:			Wetland Hydrology Present?	
Surface Water Present? Yes ☐ No ☒ Depth (inches):			Yes ☒ No ☐	
Water Table Present? Yes ☐ No ☒ Depth (inches):				
Saturation Present? Yes ☐ No ☒ Depth (inches):				
(includes capillary fringe)				
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:				
Remarks: This was a marginal wetland area.				

VEGETATION – Use scientific names of plants

Sampling Point: 12

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Fraxinus pennsylvanica</i>	50	Yes	FACW	Number of Dominant Species that are OBL, FACW, or FAC: <u>6</u> (A) Total number of dominant species across all strata: <u>6</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>100</u> (A/B)	
2. <i>Ulmus americana</i>	20	Yes	FACW		
3.					
4.					
5.					
	70	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Rhamnus cathartica</i>	15	Yes	FAC	Total % Cover of:	Multiply by:
2. <i>Cornus stolonifera</i>	20	Yes	FACW	OBL Species	X 1 =
3. <i>Viburnum opulus</i>	5	No	FACU	FACW Species	X 2 =
4. <i>Cornus racemosa</i>	25	Yes	FACW	FAC Species	X 3 =
5.				FACU Species	X 4 =
	65	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals: A)	(B)
1.				Prevalence Index = B/A =	
2.					
3.				Hydrophytic Vegetation Indicators:	
4.				☐ Rapid Test for Hydrophytic Vegetation	
5.				☒ Dominance Test is >50%	
6.				☐ Prevalence Index is ≤ 3.0 ¹	
7.				☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
		= Total Cover			
Woody Vine Stratum (Plot size):					
1. <i>Vitis riparia</i>	5	Yes	FACW	Hydrophytic Vegetation Present? Yes ☒ No ☐	
2.					
	5	= Total Cover			
Definitions of Vegetation Strata:					
Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height.					
Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall.					
Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall.					
Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet).					
Ground cover shade suppressed and absent over large areas					

SOILS

Sampling Point 12

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-12	10 YR 3/1						Sandy silt loam	
12-15	10 YR 3/2		10 YR 4/4				Sandy silt loam	
15+	7.5 YR 5/6		10 YR 5/2	1-2			Clay sand	

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)

³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if observed):	Hydric Soil Present? Yes ☒ No ☐
Type:	
Depth (inches):	
Remarks:	

WETLAND DETERMINATION DATA FORM – Northcentral and Northeast Region

Project Site: CNY		City/County: Syracuse		Sampling Date: 9/22/15	
Applicant/Owner: Working Lands		State: New York		Sampling Point: 13	
Investigator(s): John Larson, Susan Lehnhardt			Section, Township, Range:		
Landform (Hillslope, terrace, etc.)		Local relief (concave, convex, none):		Slope (%)	
Subregion (LRR or MLRA):		Lat:	Long:	Datum: 43.07586 North latitude and 76.03483 West longitude	
Soil Map Unit Name: Niagara silt loam			NYSDEC/NWI classification: No		
Are climatic/hydrologic conditions on the site typical for this time of year? Yes ☐ No ☒ (If no, explain in remarks)					
Is Significantly Disturbed:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	Are "Normal Circumstances" Present? Yes ☒ No ☐	
Is Naturally Problematic:	Vegetation? ☐	Soil? ☐	Hydrology? ☐	If needed, explain in remarks	

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.			
Hydrophytic Vegetation Present?	Yes ☐ No ☒	Hydric Soil Present? Yes ☐ No ☒	
Wetland Hydrology Present?	Yes ☒ No ☐	Is the Sampled Area within a Wetland? Yes ☐ No ☒	
If yes, optional Wetland Site ID:			
Remarks: June was very wet, July, August and September below normal.			

HYDROLOGY

Wetland Hydrology Indicators:		
Primary Indicators (minimum of one is required: check all that apply).		Secondary Indicators (minimum of 2 required)
☐ Surface Water (A1)	☐ Water-Stained Leaves (B9)	☐ Surface Soil Cracks (B6)
☐ High Water Table (A2)	☐ Aquatic Fauna (B13)	☐ Drainage Patterns (B10)
☐ Saturation (A3)	☐ Marl Deposits (B15)	☐ Moss Trim Lines (B16)
☐ Water Marks (B1)	☐ Hydrogen Sulfide Odor (C1)	☐ Dry-Season Water Table (C2)
☐ Sediment Deposits (B2)	☒ Oxidized Rhizospheres on Living Roots (C3)	☐ Crayfish Burrows (C8)
☐ Drift Deposits (B3)	☐ Presence of Reduced Iron (C4)	☐ Saturation Visible on Aerial Imagery (C9)
☐ Algal Mat or Crust (B4)	☐ Recent Iron Reduction in Tilled Soils (C6)	☐ Stunted or Stressed Plants (D1)
☐ Iron Deposits (B5)	☐ Thin Muck Surface (C7)	☐ Geomorphic Position (D2)
☐ Inundation Visible on Aerial Imagery (B7)	☐ Other (Explain in Remarks)	☐ Shallow Aquitard (D3)
☐ Sparsely Vegetated Concave Surface (B8)		☐ Microtopographic Relief (D4)
		☐ FAC-Neutral Test (D5)
Field Observations:		
Surface Water Present? Yes ☐ No ☒	Depth (inches):	Wetland Hydrology Present? Yes ☒ No ☐
Water Table Present? Yes ☐ No ☒	Depth (inches):	
Saturation Present? Yes ☐ No ☒	Depth (inches):	
(includes capillary fringe)		
Described Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:		
Remarks:		

VEGETATION – Use scientific names of plants

Sampling Point: 13

Tree Stratum (Plot size):	Absolute % Cover	Dominant Species?	Indicator Status	Dominance Test Worksheet:	
1. <i>Fraxinus pennsylvanica</i>	10	Yes	FAC	Number of Dominant Species that are OBL, FACW, or FAC: <u>2</u> (A) Total number of dominant species across all strata: <u>4</u> (B) % Dominant Species that are OBL, FACW, or FAC: <u>50</u> (A/B)	
2. <i>Crataegus</i> sp	10	Yes	NI		
3.					
4.					
5.					
	20	= Total Cover			
Sapling/Shrub Stratum (Plot size):				Prevalence Index Worksheet:	
1. <i>Lonicera tatarica</i>	75	Yes	UPL	Total % Cover of:	Multiply by:
2. <i>Rhamnus cathartica</i>	15	No	FAC	OBL Species	X 1 =
3. <i>Ulmus americana</i>	5	No	FACW	FACW Species	X 2 =
4.				FAC Species	X 3 =
5.				FACU Species	X 4 =
	95	= Total Cover		UPL Species	X 5 =
Herb Stratum (Plot size):				Column Totals: A)	(B)
1. <i>Solidago canadensis</i>	5	Yes	FACU	Prevalence Index = B/A =	
2. <i>Polygonum virginianum</i>	2	Yes	FAC		
3.				Hydrophytic Vegetation Indicators:	
4.				☐ Rapid Test for Hydrophytic Vegetation	
5.				☐ Dominance Test is >50%	
6.				☐ Prevalence Index is ≤ 3.0 ¹	
7.				☐ Morphological Adaptations ¹ (Provide supporting data in Remarks)	
8.				☐ Problematic Hydrophytic Vegetation ¹ (Explain)	
9.				¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.	
10.					
	7	= Total Cover			
Woody Vine Stratum (Plot size):					
1.				Hydrophytic Vegetation Present? Yes No ☒	
2.					
		= Total Cover			
Definitions of Vegetation Strata: Trees – Woody plants 3" (7.6 cm) or more in diameter at breast height (DBH), regardless of height. Sapling/shrub – Woody plants less than 3" in DBH and greater than 3.28 ft (1 m) tall. Herb – All herbaceous (non-woody) plants, regardless of size, and woody plants less than 3.28 ft. tall. Woody vines – All woody vines greater than 3.28 ft in height.					
Remarks: (Include photo numbers here or on a separate sheet). Slightly convex, edge of upland/wetland					

US Army Corps of Engineers

Northcentral and Northeast Region –Version 2.0

SOILS

Sampling Point 13

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)								
Depth (inches)	Matrix		Redox Features				Texture	Remarks
	Color (moist)	%	Color (moist)	%	Type ¹	Loc ²		
0-6	10 YR 3/2							Redox
6-7	5 YR 4/4	1-2	10 YR 6/2					
14+	10 YR 4/2		10 YR 5/6	1				

¹ Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

² Location: PL=Pore Lining, M=Matrix

Hydric Soil Indicators:		Indicators for Problematic Hydric Soils ³ :
☐ Histosol (A1)	☐ Stripped Matrix (S6)	☐ 2 cm Muck (A10) (LRR K, L, MLRA 149B)
☐ Histic Epipedon (A2)	☐ Dark Surface (S7) (LRR R, MLRA 149B)	☐ Coast Prairie Redox (A16) (LRR K, L, R)
☐ Black Histic (A3)	☐ Polyvalue Below Surface (S8) (LRR R, MLRA 149B)	☐ 5 cm Mucky Peat or Peat (S3) (LRR K, L, R)
☐ Hydrogen Sulfide (A4)	☐ Thin Dark Surface (S9) (LRR R, MLRA 149B)	☐ Dark Surface (S7) (LRR K, L)
☐ Stratified layers (A5)	☐ Loamy Mucky Mineral (F1) (LRR K, L)	☐ Polyvalue Below Surface (S8) (LRR K, L)
☐ Depleted Below Dark Surface (A11)	☐ Loamy Gleyed Matrix (F2)	☐ Thin Dark Surface (S9) (LRR K, L)
☐ Thick Dark Surface (A12)	☐ Depleted Matrix (F3)	
☐ Sandy Mucky Mineral (S1)	☐ Redox Dark Surface (F6)	
☐ Sandy Gleyed Matrix (S4)	☐ Depleted Dark Surface (F7)	
☐ Sandy Redox (S5)	☐ Redox Depressions (F8)	
		☐ Iron-Manganese Masses (F12) (LRR K, L, R)
		☐ Piedmont Floodplain Soils (F19) (MLRA 149B)
		☐ Mesic Spodic (TA6) (MLRA 144A, 145, 149B)
		☐ Red Parent Material (TF2)
		☐ Very Shallow Dark Surface (TF12)
		☐ Other (Explain in Remarks)
³ Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.		
Restrictive Layer (if observed):	Hydric Soil Present? Yes ☐ No ☒	
Type:		
Depth (inches):		
Remarks:		

Exhibit 3. WETs Table-Showing Antecedent Precipitation Conditions for July -September 2015 in Syracuse, NY. (Page 1 of 4)

11/13/2015 WETS Table

USDA Field Office Climate Data

WETS Station : SYRACUSE HAMCOCK INTL AP, NY771 Creation Date: 11/13/2015
 Latitude: 4307 Longitude: 07606 Elevation: 00413
 State FIPS/County(FIPS): 36067 County Name: Onondaga
 Start yr. - 1971 End yr. - 2000

Month	Temperature (Degrees F.)			Precipitation (Inches)				
	avg daily	avg daily	avg min	avg	less than	more than	30% chance will have	avg # of days total w/.1 or more
January	31.4	14.0	22.7	2.60	1.86	3.07	7	33.2
February	33.5	15.5	24.5	2.12	1.57	2.49	6	24.0
March	43.1	24.2	33.6	3.02	2.37	3.48	8	18.8
April	55.7	34.9	45.3	3.39	2.36	4.02	8	4.8
May	68.5	45.8	57.1	3.39	2.27	4.06	8	0.1
June	77.0	54.6	65.8	3.71	2.41	4.46	8	0.0
July	81.7	60.1	70.9	4.02	2.88	4.75	7	0.0
August	79.6	58.8	69.2	3.56	2.62	4.18	7	0.0
September	71.4	51.1	61.3	4.15	3.25	4.79	7	0.0
October	59.8	40.4	50.1	3.20	2.16	3.83	8	0.4
November	47.4	32.0	39.7	3.77	2.93	4.36	9	11.1
December	36.3	20.9	28.6	3.12	2.42	3.61	9	28.6
Annual					35.82	43.60		
Average	57.1	37.7	47.4					
Average				40.05			92	121.2

GROWING SEASON DATES

Http://agris.rox-ads.org/36067/wetsresults

Exhibit 3. (Continued) (Page 2 of 4)

11/13/2015

WETS Table

	Temperature			Beginning and Ending Dates	
				Growing Season Length	
Probability	24 F or higher	28 F or higher	32 F or higher		
50 percent *	4/ 5 to 11/ 5	4/17 to 10/24	4/27 to 10/12		
	213 days	189 days	168 days		
70 percent *	3/31 to 11/10	4/13 to 10/28	4/23 to 10/16		
	223 days	197 days	176 days		

* Percent chance of the growing season occurring between the Beginning and Ending dates.

total 1950-2015 prep

Station : NY771, SYRACUSE HANCOCK INTL AP

Unit = inches

yr	jan	feb	mar	apr	may	jun	jul	aug	sep	oct	nov	dec	annl
50	2.73	5.38	4.65	3.79	1.97	4.21	2.05	2.52	4.22	3.41	3.91	3.59	19.70
51	2.45	2.00	2.39	2.57	3.88	1.18	5.22	3.33	3.17	1.86	3.76	4.34	44.41
52	2.91	2.71	3.75	2.07	4.35	1.51	1.93	2.39	2.11	1.64	1.74	2.61	29.72
53	2.43	3.74	3.48	4.75	3.17	3.66	1.12	7.19	3.06	1.99	4.84	4.03	43.46
54	1.61	3.32	6.84	1.81	1.90	2.43	2.85	3.80	1.87	8.29	2.69	2.53	39.94
55	2.28	3.90	4.63	3.35	3.03	1.71	3.75	8.41	4.27	1.28	2.38	3.02	42.01
56	2.19	1.76	2.01	2.60	2.88	4.18	6.13	3.45	2.28	0.93	1.86	2.90	33.17
57	4.46	5.28	1.31	3.36	3.70	5.24	3.63	2.06	4.89	3.37	3.76	1.73	42.79
58	4.59	2.22	2.93	2.51	1.97	2.53	2.54	4.48	0.93	7.15	4.34	5.01	41.20
59	3.11	4.90	2.48	2.94	3.96	1.86	1.03	2.69	2.93	2.77	1.68	1.86	32.21
60	2.30	4.14	4.22	3.74	2.40	3.68	5.08	1.78	1.21	3.59	2.99	2.45	37.58
61	2.87	2.96	1.96	3.57	1.05	1.10	2.74	4.63	1.99	3.30	2.22	2.25	30.64
62	1.85	2.05	2.79	2.22	2.84	2.49	1.21	3.59	0.85	0.21	5.65	2.06	27.81
63	2.18	1.13	3.83	3.66	2.31	1.41	2.15	3.09	0.75	1.52	2.20	2.87	27.10
64	2.28	2.82	1.63	3.53	1.61	2.04	1.34	1.95	3.60	2.70	2.97	1.92	28.39
65	3.98	2.96	2.27	3.05	1.79	2.73	2.09	2.64	4.75	0.90	2.05	3.93	33.14

Exhibit 3. (Continued) (Page 3 of 4)

11/13/2015	WETS Table													
	67	68	69	70	71	72	73	74	75	76	77	78	79	80
1.47	1.49	1.34	2.11	3.33	1.56	6.33	5.00	2.73	3.52	4.48	2.66	36.02		
2.08	1.10	3.13	2.40	3.46	6.14	3.77	4.17	3.43	5.81	4.07	4.67	44.23		
3.37	1.49	1.08	3.95	4.34	3.74	0.90	1.77	1.13	2.30	4.56	3.42	32.05		
1.02	1.84	2.45	3.68	2.79	2.93	4.42	4.07	4.33	3.84	3.53	3.33	38.23		
1.90	4.07	2.90	2.19	3.40	3.26	6.49	4.01	2.56	1.62	3.52	3.26	39.19		
1.10	2.87	2.49	4.03	6.19	12.30	3.45	3.76	4.12	4.36	6.79	3.95	55.41		
1.85	1.64	3.45	6.91	5.58	7.07	3.62	2.97	4.57	3.81	6.73	4.38	52.58		
2.08	1.70	4.34	3.09	5.78	4.67	9.52	4.60	4.45	1.58	4.95	3.47	50.23		
2.54	3.05	2.67	2.01	2.74	4.08	9.32	5.35	8.81	3.69	3.54	4.10	51.90		
2.79	2.71	4.62	8.12	7.41	7.42	5.24	6.73	3.27	6.53	1.53	1.80	58.17		
1.84	1.62	3.47	3.04	0.75	3.30	4.76	4.93	6.54	4.75	5.31	4.33	44.64		
5.77	0.80	3.08	1.87	1.90	3.58	2.78	3.31	3.93	2.68	1.25	4.12	35.07		
4.70	2.54	2.73	3.89	3.07	2.33	2.33	3.69	5.25	2.91	3.25	1.84	38.53		
1.47	1.38	4.34	3.33	1.34	4.45	2.57	1.33	3.40	2.56	2.64	3.27	32.08		
1.34	2.72	1.01	2.04	2.61	1.89	2.68	2.63	5.58	6.66	3.09	2.96	35.21		
3.59	1.26	2.63	1.71	2.87	4.64	3.83	2.60	4.22	0.72	4.52	2.55	35.14		
1.92	1.07	2.30	6.34	3.33	1.50	2.31	2.80	2.98	1.98	4.30	5.50	36.33		
1.30	2.88	2.39	3.16	4.97	2.02	3.66	5.17	2.61	1.95	3.48	4.38	37.97		
2.49	1.55	2.61	1.22	3.39	2.80	2.75	1.44	3.88	3.39	5.18	1.80	32.50		
2.41	2.27	2.82	3.42	2.67	4.89	5.23	3.36	5.47	3.32	3.74	3.33	42.93		
3.03	0.63	1.86	3.31	1.41	5.04	2.16	2.12	5.99	3.13	3.02	1.99	33.69		
1.50	2.13	1.79	2.70	3.05	2.46	5.72	3.77	1.88	3.57	3.95	1.92	34.44		
1.06	1.71	3.13	1.52	4.27	5.41	2.20	2.68	5.96	4.08	2.78	2.13	36.93		
2.13	3.95	3.70	4.09	5.62	2.92	3.72	5.33	3.45	6.09	3.23	5.24	49.47		
2.44	1.54	4.07	3.90	3.90	1.67	2.86	4.03	4.20	2.62	2.72	3.10	37.05		
2.62	2.46	3.80	3.54	5.21	1.78	8.00	2.64	4.55	2.69	3.75	2.57	43.61		
3.08	2.45	3.75	6.55	2.25	2.93	4.76	4.71	3.83	2.91	3.20	M2.96	43.38		
3.49	1.92	5.14	3.62	3.03	2.38	2.64	5.19	2.43	M0.77	3.50	2.52	36.63		
1.80	2.19	1.31	1.88	1.70	1.00	1.98	3.50	2.53	6.57	4.83	2.05	31.34		
3.35	1.25	1.74	4.28	3.02	3.05	4.24	1.71	4.38	2.14	5.78	4.45	39.39		
1.46	2.25	3.57	1.77	2.43	1.64	2.78	4.06	2.75	1.50	4.28	4.13	32.62		
4.76	3.14	2.94	2.09	2.37	4.62	3.63	4.77	2.41	2.53	2.06	1.74	37.06		
5.33	1.43	3.53	1.75	0.81	1.78	2.55	1.02	5.35	2.77	3.16	1.40	30.88		
2.80	2.46	2.37	4.24	4.75	4.46	2.73	2.48	3.13	2.25	2.98	2.36	37.01		
1.57	1.77	5.38	1.53	2.24	3.58	2.08	4.84	4.05	2.15	2.92	2.19	34.30		
2.13	1.44	2.75	4.38	5.77	5.35	1.75	2.71	3.55	3.98	3.61	2.84	40.26		
1.44	2.58	2.89	2.61	5.27	2.83	3.30	3.03	3.14	4.27	3.14	3.10	37.60		
1.86	1.12	2.04	3.72	7.82	2.42	6.95	5.09	3.23	2.28	2.81	3.80	43.14		
2.96	1.57	1.39	5.71	0.59	1.95	4.61	5.95	1.75	6.40	4.66	2.56	40.10		
2.96	1.66	1.86	3.93	2.25	5.09	10.12	3.21	4.04	5.70	2.62	3.76	47.20		
4.20	M2.42	4.16	4.42	0.86	3.67	3.61	1.76	3.20	4.02	4.17	5.04	41.53		
1.36	4.71	5.00	2.99	1.78	3.75	4.28	3.62	2.47	4.87	3.19	3.89	41.91		
1.86	M1.27	3.80	2.31	3.53	5.24	2.04	4.57	2.27	4.08	2.16	M2.20	35.33		

Exhibit 3. (Continued) (Page 4 of 4)

11/13/2015	WETS Table													
10M1.21	2.02	2.54	0.84	2.87	6.57	4.28	6.36	5.26	4.11	2.93	M2.42	41.41		
11 2.45	3.11	2.86	8.53	3.90	3.31	3.30	6.66	6.36	3.20	3.36	2.48	49.52		
12 3.88	1.41	1.96	2.24	3.15	2.28	1.84	2.27	3.11	3.99	1.41	7.57	35.11		
13 1.71	2.71	2.02	3.59	3.91	6.80	3.22	2.58	3.20	3.91	3.84	2.89	40.38		
14 2.20	3.35	3.48	4.64	3.71	2.74	5.18	3.74	1.60	4.54	2.30	3.02	40.50		
15 1.60	2.28	1.52	2.79	3.93	9.92	3.37	1.91	5.05	3.77	M0.80		36.94		

Product generated by ACIS - NOAA Regional Climate Centers



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



APPENDIX D TRAFFIC IMPACT STUDY



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



Consulting

1396 White Bridge Road

Chittenango, NY 13037

Tel: (315) 391-5110 Fax: (315) 687-6267

December 6, 2018

Romeo & Romeo, PC
314 East Fayette Street
Syracuse, NY 13202

Attn: Mr. Robert Romeo

**Re: Traffic Impact Assessment – Proposed International Container Transfer Facility
Girden Road – Town of DeWitt, NY**

Dear Mr. Romeo:

I have completed my review of the traffic operations associated with the proposed international container transfer facility on the west side of Girden Road in the Town of DeWitt, NY. This letter summarizes the work completed in this review as well as my findings.

Project Understanding

The proposed development is located on the west side of Girden Road, just north of the CSX railroad tracks in the Town of DeWitt. The proposed international container transfer facility encompasses approximately 9 acres with access proposed via the southern end of Girden Road. The site is expected to generate approximately 3,000 trucks per year at start up traveling exclusively to/from the I-481 interchange to the west via Kirkville Road. The overall truck generation is anticipated to grow to approximately 5,000 trucks per year by end of the first year will full operations of approximately 10,000 trucks per year in 3-5 years. With 24 hour operations, seven days per week, the site is expected to generate approximately 27 trucks per day under full operation with peak movements occurring between 7-9 in the morning and 3:30-5:30 in the evening.

This study evaluates the full build condition assuming that 25% of the daily truck traffic (7 trucks) enters and exits the site during the weekday peak morning and evening commuting hours. The trucks generated will be predominantly heavy duty 80' double-axle class 8 tractors and trailers with 40' containers. The site is expected to employ 5-10 people.

Data Collection

Site visits were conducted on Tuesday – December 4th, 2018 to collect the following:

- Existing Traffic Volume Counts – Traffic turning movement counts were collected at the intersection of Kirkville Road with Girden Road during the weekday morning (7-9am) and evening (4-6pm) peak travel periods to ensure that actual peak hours of the adjacent streets were captured. The traffic counts included car and heavy vehicle counts by movement. There was no pedestrian activity observed during the traffic count periods and all area schools were in session.



Mr. Romeo
December 6, 2018
Page 2 of 7

**Re: Traffic Impact Assessment – Proposed International Container Transfer Facility
Girden Road – Town of DeWitt, NY**

- Kirkville Road Gap Data – Gap data was collected to assess the ability for vehicles to turn in and out of Girden Road on Kirkville Road. In order for a vehicle to turn right out of Girden Road, or left into Girden Road, the vehicle only requires a gap in the eastbound direction on Kirkville Road. A vehicle requires a gap in traffic in both directions at the same time to turn left out of Girden Road. These gaps in traffic were observed and timed on Kirkville Road during the weekday morning and evening traffic count periods. The gaps were then converted to a number of vehicles that could turn left or right out of Girden Road during each gap and then totaled for the peak hour. For example, one vehicle can turn from the side road with a 6-9 second gap in traffic, two can turn with a 10-13 second gap, 3 with a 14-17 second gap, 4 with an 18-19 second gap, etc.
- Spot Speed Measurements – 50 speed measurements were collected in each direction on Kirkville Road passing Girden Road to identify average and 85th percentile operating speeds in the area.
- Sight Distance Measurements – Sight lines looking east/west along Kirkville Road from Girden Road were collected for comparison to design standards in order to confirm that adequate sight lines are available for safe ingress and egress from the site.
- Operational Data - Other data needed to evaluate traffic operations, such as intersection geometry, control, and speeds limits were also collected.

Existing Operations

Based on the traffic counts collected, the peak hours were identified as follows:

Morning Peak Hour – 7:15am to 8:15am
Evening Peak Hour – 4:00pm to 5:00pm

The 2018 existing traffic volumes are shown in the attached Figure 1 for the morning and evening peak hours. Kirkville Road operates as an east/west arterial roadway with approximately 616 vehicles eastbound, 1,044 vehicles westbound during the morning peak hour and 1,027 vehicles eastbound/624 vehicles westbound during the evening peak hour. Girden Road is an extremely low volume dead end roadway carrying less than 10 vehicles to/from Kirkville Road during each of the peak hours. The traffic count data has been attached.

Kirkville Road has one 12 foot wide travel lane and a 9 foot wide shoulder in each direction passing Girden Road with a 45 mph speed limit.

Girden Road varies in width from 24-28 feet wide at the northern end near Kirkville Road, to approximately 20 feet wide in the middle section, to 18-20 feet wide near the southern end. The visual

**Re: Traffic Impact Assessment – Proposed International Container Transfer Facility
Girden Road – Town of DeWitt, NY**

pavement condition on Girden Road is generally fair with some minor longitudinal cracking, some minor potholes and areas where patching has been completed. It is noted that there is some rutting in the pavement, particularly closer to Kirkville Road.

The peak hour traffic volumes were compared to 2014 NYSDOT AADT counts on Kirkville Road and Girden Road from the Traffic Data Viewer website. The traffic counts through the study area are all consistent with the historical traffic volume counts. The historical traffic volume data has been attached.

Based on the gap data collected, there are sufficient gaps in traffic to accommodate 399 vehicles turning right onto Kirkville Road from Girden Road during the morning peak hour and 187 vehicles turning right during the evening peak hour. These gaps would also be available for vehicles turning left onto Girden Road from Kirkville Road. There were sufficient gaps observed to accommodate 102 vehicles turning left out onto Kirkville Road during the morning peak hour and 94 vehicles turning left during the evening peak hour. While it is noted that the available gaps in traffic are limited due to the high through volumes on Kirkville Road, there are sufficient gaps to accommodate both the existing traffic on Girden Road and the projected traffic volumes from the proposed international container transfer facility given the low existing and projected traffic volumes. The gap data is attached.

The posted speed limit in the area on Kirkville Road is 45mph. The speed data collected indicates that the average speeds passing the site on Kirkville Road are 48-50 mph in both directions. The 85th percentile speed based on the data collected is 53 mph in the eastbound direction and 51 mph in the westbound direction on Kirkville Road. The 85th percentile speeds are considered the operating speeds and are typically used for design and analysis. The speed data has been attached.

The following table provides a summary of the recommended sight distances along Kirkville Road from the AASHTO A Policy on Design of Highways and Streets as well as the available sight distances based on field measurements. The speed limit in the area is 45 mph on Kirkville Road, however the 85th percentile speeds were used in the review.

Sight Distance Summary

Location	Operating Speed	Direction	AASHTO	Available Sight Distance
			Recommended Sight Distance	
Kirkville Road @ Girden Road – Turning Left	55 mph	Looking Left	610 feet	1,200 feet
		Looking Right	610 feet	715 feet
Kirkville Road @ Girden Road – Turning Right	55 mph	Looking Left	530 feet	1,200 feet

There is more than adequate sight distance available on Kirkville Road looking both east and west from Girden Road for passenger cars. An additional review was completed for a compound tractor

**Re: Traffic Impact Assessment – Proposed International Container Transfer Facility
Girden Road – Town of DeWitt, NY**

trailer using an 11.5 second critical gap as opposed to the standard 7.5 second critical gap used for passenger cars. Using the longer critical gap, the recommended sight distance for a tractor trailer is 862 feet in each direction using the 51 mph westbound operating speed. While there is still more than sufficient distance looking to the west, the existing sight distance to the right is approximately 150 feet shorter than recommended. This would indicate that approaching westbound motorists on Kirkville Road may have to slow down slightly as tractor trailers are accelerating on Kirkville Road.

Capacity analysis of the existing traffic operations was completed using Synchro10, an industry accepted standard for the analysis of both signalized and unsignalized intersections that is based on methodologies developed in the Highway Capacity Manual. Intersection and individual movement operations are graded in terms of Level of Service ranging from A to F, as described in the HCM. For example, a signalized intersection movement with an average delay of 5 seconds per vehicle is considered a Level of Service A while an average delay per vehicle of 25 seconds is considered a C. A Level of Service D or better is generally considered acceptable for a signalized intersection and a Level of Service E or better is generally considered acceptable for an unsignalized intersection.

The results of the capacity analysis indicate that there are minimal delays on Kirkville Road at Girden Road during both the morning and evening peak hours. Girden Road operates at a Level of Service B during the morning peak hour but has longer existing delays with overall Level of Service F during the evening peak hour.

Although there may be some longer delays turning out onto Kirkville Road, this would be expected for a low volume approach to a high volume commuter roadway. There are sufficient existing gaps in traffic to accommodate the existing and projected traffic volumes. These findings are consistent with observations made during the data collection.

Accident Analysis

An accident analysis was completed for the study area using history reports obtained for a five year period from September 2013 through August 2018. Over the five year period, there were 5 total accidents in the study area. Two accidents occurred at the Girden Road intersection with one being a left turn accident and one being a right angle accident. There was one accident on Kirkville Road at a residential driveway to the west of Girden Road and two accidents on Kirkville Road, one being a rearend accident and one being a fixed object accident.

Assuming the evening peak hour volume in the Girden Road intersection is 9% of the average daily traffic volume, the resulting accident rate is 0.059 accidents per million entering vehicles. This rate is below the statewide average rate of 0.17 accidents per million entering vehicles for similar facilities, indicating that this is not a high accident location.

The accident data and calculations have been attached.



Mr. Romeo
December 6, 2018
Page 5 of 7

**Re: Traffic Impact Assessment – Proposed International Container Transfer Facility
Girden Road – Town of DeWitt, NY**

2023 Background Operations

The proposed international container transfer facility is assumed to be in full operation by 2023. In order to fully understand the impacts of the development on the adjacent roadway system, analysis of the operations immediately before the project opening must first be completed. The existing traffic volumes were adjusted by a growth rate to account for any unknown development that may occur prior to completion of the project.

Historical traffic volumes along Kirkville Road between Roberts Street and Girden Road, and between Girden Road and Freemont Road, were taken from the 2016 NYSDOT Traffic Volume Report and reviewed in order to identify an appropriate background growth rate. Long term growth rates in the area have been –1.4% per year to the east of Girden Road and +1.0% per year to the west of Girden Road between 2008 and 2016. A 1% annual background growth in traffic was assumed from 2018 to 2023 in order to maintain a conservative traffic analysis. The 2023 background traffic volumes with 5% total growth are shown in Figure 1.

The capacity analyses of the 2023 background condition shows no notable increases in delay on Kirkville Road from the existing condition. Girden Road will continue to experience longer delays during the evening peak hour. The detailed Level of Service summary and the Synchro capacity analysis printouts have been attached.

Trip Generation Estimate and Distribution

The site is expected to generate approximately 3,000 trucks per year at start up traveling exclusively to/from the I-481 interchange to the west via Kirkville Road. The overall truck generation is anticipated to grow to approximately 5,000 trucks per year by end of the first year will full operations of approximately 10,000 trucks per year in 3-5 years. With 24 hour operations, seven days per week, the site is expected to generate approximately 27 trucks per day under full operation with peak movements occurring between 7-9 in the morning and 3:30-5:30 in the evening. The site is expected to employ 5-10 people.

It is assumed that 25% of the daily truck traffic (7 trucks) will enter and the site during the weekday peak morning and evening commuting hours. The trucks generated will be predominantly heavy duty 80' double-axle class 8 tractors and trailers with 40' containers. For a worst case analysis, it is also assumed that 10 employees enter and exit the site during each of the peak hours.

The following table summarizes the trip generation estimate for the proposed international container transfer facility.

**Re: Traffic Impact Assessment – Proposed International Container Transfer Facility
Girden Road – Town of DeWitt, NY**

Trip Generation Summary

	Morning Peak Hour		Evening Peak Hour	
	Entering	Exiting	Entering	Exiting
Trucks	7	7	7	7
Cars (Employees)	<u>10</u>	<u>10</u>	<u>10</u>	<u>10</u>
Total Trips Generated	17	17	17	17

The proposed development will be a minor traffic generator with less than 20 total vehicles entering or exiting during each peak hour.

Based on existing traffic patterns and population centers in the area, 63% of the employee trips generated are expected to travel to/from the east on Kirkville Road, and 37% are expected to travel to/from the west on Kirkville Road. All truck traffic will travel to/from the west on Kirkville Road. The anticipated arrival/departure distribution for the facility is shown in Figure 1. The trips generated during each peak hour are and the resultant 2023 full build traffic volumes expected when the development is in full operation are also shown in Figure 1.

Build Operations

Based on the projected turning movements on Kirkville Road at Girden Road, there are sufficient gaps available to accommodate the proposed development.

Capacity analysis of the 2023 build condition continues to show minimal delays on Kirkville Road at Girden Road during both peak hours. The analysis does indicate that there may be longer delays of 1-2 minutes for vehicles to turn off Girden Road onto Kirkville Road during both peak hours. With minimal traffic volumes on Girden Road, even with the proposed transfer facility, there would be no notable queueing expected. Girden Road only has two houses on the roadway other than the operations at the southern end of the road associated with CSX. There is only expected to be 1 vehicle exiting the roadway every 2-3 minutes during the peak hours. Delays will be significantly reduced during off peak hour when volumes on Kirkville Road are lower.

The detailed Level of Service summary and capacity analysis printouts have been attached.

Intersection Turning Radius Review

Truck turning templates were reviewed for a WB-62 interstate tractor trailer turning left off Girden Road and right off Kirkville Road onto Girden Road assuming that the trucks can use the full width of Girden Road for turning movements. The turning templates indicate that some minor pavement



Mr. Romeo
December 6, 2018
Page 7 of 7

**Re: Traffic Impact Assessment – Proposed International Container Transfer Facility
Girden Road – Town of DeWitt, NY**

widening will be needed on the southwest corner of the intersection to accommodate the turning movement onto Girden Road.

The turning templates have been attached.

Conclusions

The additional traffic generated by the proposed International container transfer facility will be minor with less than 1 vehicle entering and exiting the site every 2-3 minutes during the busiest peak commuter hours. This estimate is conservative in that it assumes 10 employees are entering and exiting in addition to the truck traffic.


The minimal traffic increase will have no significant impact on traffic operations on Kirkville Road in the vicinity of the development. It is noted that westbound traffic may have to slow for accelerating trucks on Kirkville Road with slightly reduced sight lines for trucks looking to the east when exiting Girden Road. The sight distances are more than sufficient for passenger car traffic in both directions and there are no concerns with stopping sight distances.

There will be longer delays expected for vehicles turning off Girden Road, particularly during the morning and evening peak commuter hours when volumes are heavier on Kirkville Road. With little to no other traffic on Girden Road, these delays will be observed by the trucks and employee traffic generated by the site, and will have no impact on existing motorists traveling through the area.

The pavement radius on the southwest corner of the Kirkville Road/Girden Road intersection should be widened to accommodate the truck traffic turning right onto Girden Road.

If you have any questions or need additional information, please call.

Sincerely,



Gordon T. Stansbury, P.E., P.T.O.E.
GTS Consulting

Attachments –

Level of Service Summary
Truck Turning Template
Gap Calculations
Growth Calculations
Traffic Count Data

Traffic Volume Figures 1
NYSDOT AADT Data
Spot Speed Data
Accident Analysis
Capacity Analysis Printouts

Proposed International Container Transfer Facility – Girden Road – DeWitt, NY

Intersection Level of Service Summary

Morning Peak Hour


Intersection	2018 Existing	2023 Background	2023 Build
Kirkville Road @ Girden Road			
EB Through/Right	a(0)	a(0)	a(0)
WB Left/Through	a(0)	a(0)	a(1)
NB Left/Right	b(14)	b(15)	f(138)

a(9) – Unsignalized Level of Service (Average Delay per Vehicle in Seconds)


Evening Peak Hour

Intersection	2018 Existing	2023 Background	2023 Build
Kirkville Road @ Girden Road			
EB Through/Right	a(0)	a(0)	a(0)
WB Left/Through	a(0)	a(0)	a(1)
NB Left/Right	f(63)	f(72)	f(106)


a(9) – Unsignalized Level of Service (Average Delay per Vehicle in Seconds)




2018 Existing Traffic Volumes
Morning (Evening) Peak Hour




2023 Background Traffic Volumes
With 1% Growth Per Year (5% Total)
Morning (Evening) Peak Hour



Arrival /Departure Trip Distribution
Cars (Trucks)



Trips Generated
Morning (Evening) Peak Hour



2023 Build Traffic Volumes
Morning (Evening) Peak Hour



New York State Department of Transportation

Roadway Traffic Count Hourly Report

STATION: 336116

ROUTE/ROAD: KIRKVILLE RD	FROM: ROBERTS ST	TO: MANLIUS TN LN	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 3, 7	REF. MARKER:	FUNC. CLASS: 16 - U Minor Arterial	MUNI: De Witt-Town-0233
ST DIR CODE: 7	END MILEPOST: 2.78	FACTOR GROUP: 30	BIN: 3312700
DOT ID: 129988	LANES BY DIR: 1 East 1 West	CC STN:	RR CROSSING:
BEGIN DATE: 5/7/2014	WEEK OF YEAR: 19	ADDL DATA: CLS SPD	HPMS SAMPLE:
NOTES 1: WB TRAVEL LANE	PLACEMENT: 60 FT E OF BENEDICT RD	JURISDICTION: 02-County	1 WAY CODE:
NOTES 2:			COUNT TYPE: Vehicle
TAKEN BY: TTG-AJW	PROCESSED BY: DOT-SJW	BATCH ID: DOT-SJWR3ww19	SPEED LIMIT:

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
5/07, Wed											694	736	802	874	1003	1486	1293	1257	1134	717	580	364	231	152	11323		
5/08, Thu	75	44	44	48	78	277	770	1649	1242	708	671	810	834	849	1008	1604	1711	1744	1036	783	604	357	279	157	17382	1744	17-18
5/09, Fri	86	53	62	62	84	260	750	1528	1218	859	845	839	945	1003	1176	1583	1732	1607	1114	758	652	431	296	243	18186	1732	16-17
5/10, Sat	108	67	45	49	50	107	249	424	680	794	871	887	869	897	930	887	858	708	666	527	490	371	283	225	12042	930	14-15
5/11, Sun	136	88	68	32	49	59	137	249	415	537	743	784	905	946	916	781	775	657	712	565	449	287	191	110	10591	946	13-14
5/12, Mon	43	26	37	46	89	265	824	1657	1349	753	734	790	841	879	1036	1484	1767	1673	1003	690	543	340	221	150	17240	1767	16-17
5/13, Tue	73	32	43	52	89	277	787	1647	1287																4287		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																									AWDT		
	78	43	50	54	84	271	783	1620	1274	773	736	794	826	867	1016	1525	1590	1558	1058	730	576	354	244	153	17055		

AVERAGE WEEKDAY											ESTIMATED AADT		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	East High Hour	% of day	West High Hour	% of day		Roadway	East	West
6	143	3	77	1620	9.5	1032	11.8	1071	12.9		15827	8147	7680
FACTOR													
Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl				
5	1.08	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00				

New York State Department of Transportation

STATION: 336116

EB Traffic Count Hourly Report

ROUTE/ROAD: KIRKVILLE RD	FROM: ROBERTS ST	TO: MANLIUS TN LN	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 3	REF. MARKER:	FUNC. CLASS: 16 - U Minor Arterial	MUNI: De Witt-Town-0233
ST DIR CODE: 7	END MILEPOST: 2.78	FACTOR GROUP: 30	BIN: 3312700
DOT ID: 129988	LANES BY DIR: 1 East	CC STN:	RR CROSSING:
BEGIN DATE: 5/7/2014	WEEK OF YEAR: 19	ADDL DATA: CLS SPD	HPMS SAMPLE:
NOTES 1: WB TRAVEL LANE	PLACEMENT: 60 FT E OF BENEDICT RD	JURISDICTION: 02-County	1 WAY CODE:
NOTES 2:			COUNT TYPE: Vehicle
TAKEN BY: TTG-AJW	PROCESSED BY: DOT-SJW	BATCH ID: DOT-SJWR3ww19	SPEED LIMIT:

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
5/07, Wed											368	379	425	479	537	898	858	790	590	388	301	249	147	82	6491		
5/08, Thu	53	32	19	23	30	74	242	545	511	302	327	406	446	459	529	939	1104	1128	598	396	311	234	171	85	8964	1128	17-18
5/09, Fri	64	38	37	28	31	80	244	516	498	387	412	432	525	544	612	893	1146	995	593	416	360	277	171	158	9457	1146	16-17
5/10, Sat	73	49	33	23	21	32	104	186	297	368	425	456	485	444	568	472	426	384	366	299	273	225	161	135	6305	568	14-15
5/11, Sun	84	54	50	20	23	22	54	118	186	239	369	443	509	532	497	436	433	350	347	281	249	176	114	62	5648	532	13-14
5/12, Mon	36	17	25	17	21	88	276	566	550	354	353	418	424	474	519	814	1135	1126	548	423	267	180	135	83	8849	1135	16-17
5/13, Tue	44	20	26	25	25	83	266	569	508																1566		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																									AWDT		
	54	30	27	25	29	79	257	549	517	348	365	409	432	471	528	884	1032	1015	579	402	293	221	151	83	8779		

AVERAGE WEEKDAY										ESTIMATED AADT		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	East High Hour	% of day	West High Hour	% of day	Roadway	East	West
6	143	3	77	1620	9.5	1032	11.8	1071	12.9	15827	8147	7680

FACTOR

Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl
5	1.08	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

New York State Department of Transportation

STATION: 336116

WB Traffic Count Hourly Report

ROUTE/ROAD: KIRKVILLE RD	FROM: ROBERTS ST	TO: MANLIUS TN LN	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 7	REF. MARKER:	FUNC. CLASS: 16 - U Minor Arterial	MUNI: De Witt-Town-0233
ST DIR CODE: 7	END MILEPOST: 2.78	FACTOR GROUP: 30	BIN: 3312700
DOT ID: 129988	LANES BY DIR: 1 West	CC STN:	RR CROSSING:
BEGIN DATE: 5/7/2014	WEEK OF YEAR: 19	ADDL DATA: CLS SPD	HPMS SAMPLE:
NOTES 1: WB TRAVEL LANE	PLACEMENT: 60 FT E OF BENEDICT RD	JURISDICTION: 02-County	1 WAY CODE:
NOTES 2:			COUNT TYPE: Vehicle
TAKEN BY: TTG-AJW	PROCESSED BY: DOT-SJW	BATCH ID: DOT-SJWR3ww19	SPEED LIMIT:

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
5/07, Wed											326	357	377	395	466	588	435	467	544	329	279	115	84	70	4832		
5/08, Thu	22	12	25	25	48	203	528	1104	731	406	344	404	388	390	479	665	607	616	438	387	293	123	108	72	8418	1104	07-08
5/09, Fri	22	15	25	34	53	180	506	1012	720	472	433	407	420	459	564	690	586	612	521	342	292	154	125	85	8729	1012	07-08
5/10, Sat	35	18	12	26	29	75	145	238	383	426	446	431	384	453	362	415	432	324	300	228	217	146	122	90	5737	453	13-14
5/11, Sun	52	34	18	12	26	37	83	131	229	298	374	341	396	414	419	345	342	307	365	284	200	111	77	48	4943	419	14-15
5/12, Mon	7	9	12	29	68	177	548	1091	799	399	381	372	417	405	517	670	632	547	455	267	276	160	86	67	8391	1091	07-08
5/13, Tue	29	12	17	27	64	194	521	1078	779																2721		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																									AWDT		
	24	13	22	29	55	192	526	1071	757	426	371	385	394	397	487	641	558	543	479	328	283	133	93	70	8276		

AVERAGE WEEKDAY										ESTIMATED AADT		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	East High Hour	% of day	West High Hour	% of day	Roadway	East	West
6	143	3	77	1620	9.5	1032	11.8	1071	12.9	15827	8147	7680

FACTOR

Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl
5	1.08	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00

New York State Department of Transportation

Roadway Traffic Count Hourly Report

STATION: 331145

ROUTE/ROAD: KIRKVILLE RD	FROM: MANLIUS TN LN	TO: FREEMONT RD	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 3, 7	REF. MARKER:	FUNC. CLASS: 16 - U Minor Arterial	MUNI: Manlius-Town-0506
ST DIR CODE: 7	END MILEPOST: 3.36	FACTOR GROUP: 30	BIN:
DOT ID: 129988	LANES BY DIR: 1 East 1 West	CC STN:	RR CROSSING:
BEGIN DATE: 4/21/2014	WEEK OF YEAR: 16	ADDL DATA:	HPMS SAMPLE:
NOTES 1: WB TRAVEL LANE	PLACEMENT: 1200 FT W OF FREEMONT RD	JURISDICTION: 02-County	1 WAY CODE:
NOTES 2:			COUNT TYPE: Axle
TAKEN BY: TST----	PROCESSED BY: R03-JAB	BATCH ID: DOT-R03R3 WW	SPEED LIMIT: 55

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
4/21, Mon														799	917	1098	1384	1321	725	540	403	285	175	148	7795		
4/22, Tue	63	44	51	49	91	226	656	1190	919	629	676	703	773	730	803	1133	1369	1347	713	514	384	271	203	126	13663	1369	16-17
4/23, Wed	62	30	56	54	86	264	627	1139	976	613	667	639	735	740	840	1056	1364	1400	775	518	409	310	234	128	13722	1400	17-18
4/24, Thu	67	41	53	53	97	257	661	1139	909	712	671	796													5456		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																									AWDT		
	63	38	52	51	90	245	636	1135	918	640	659	700	740	743	838	1076	1348	1332	724	515	391	283	200	132	13548		

											AVERAGE WEEKDAY				ESTIMATED		
DAYS		HOURS		WEEKDAYS		WEEKDAY		Roadway		East		West		AADT			
Counted	Counted	Counted	Counted	Hours	Hours	High Hour	% of day	High Hour	% of day	High Hour	% of day	High Hour	% of day	Roadway	East	West	
3	71	3	71			1348	9.9	903	12.9	818	12.5			12884	6648	6237	
FACTOR																	
Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl								
4	1.05		1.00	1.00	1.00	1.00			0.98								

New York State Department of Transportation

STATION: 331145

EB Traffic Count Hourly Report

ROUTE/ROAD: KIRKVILLE RD	FROM: MANLIUS TN LN	TO: FREEMONT RD	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 3	REF. MARKER:	FUNC. CLASS: 16 - U Minor Arterial	MUNI: Manlius-Town-0506
ST DIR CODE: 7	END MILEPOST: 3.36	FACTOR GROUP: 30	BIN:
DOT ID: 129988	LANES BY DIR: 1 East	CC STN:	RR CROSSING:
BEGIN DATE: 4/21/2014	WEEK OF YEAR: 16	ADDL DATA:	HPMS SAMPLE:
NOTES 1: WB TRAVEL LANE	PLACEMENT: 1200 FT W OF FREEMONT RD	JURISDICTION: 02-County	1 WAY CODE:
NOTES 2:			COUNT TYPE: Axle
TAKEN BY: TST----	PROCESSED BY: R03-JAB	BATCH ID: DOT-R03R3 WW	SPEED LIMIT: 55

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
4/21, Mon														402	503	653	885	894	413	312	246	174	111	90	4683		
4/22, Tue	39	30	29	20	25	63	183	328	330	276	328	345	392	381	453	674	868	936	399	310	241	181	129	89	7049	936	17-18
4/23, Wed	43	19	37	20	25	68	190	319	348	265	311	310	387	387	463	669	881	930	443	329	248	192	153	81	7118	930	17-18
4/24, Thu	51	27	27	25	35	61	209	323	320	334	311	393													2116		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																									AWDT		
	44	25	30	21	28	63	191	318	327	286	311	343	382	383	464	653	862	903	411	311	241	179	129	85	6991		

AVERAGE WEEKDAY											ESTIMATED AADT		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	East High Hour	% of day	West High Hour	% of day		Roadway	East	West
3	71	3	71	1348	9.9	903	12.9	818	12.5		12884	6648	6237
FACTOR													
Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl				
4	1.05		1.00	1.00	1.00	1.00			0.98				

New York State Department of Transportation

STATION: 331145

WB Traffic Count Hourly Report

ROUTE/ROAD: KIRKVILLE RD	FROM: MANLIUS TN LN	TO: FREEMONT RD	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 7	REF. MARKER:	FUNC. CLASS: 16 - U Minor Arterial	MUNI: Manlius-Town-0506
ST DIR CODE: 7	END MILEPOST: 3.36	FACTOR GROUP: 30	BIN:
DOT ID: 129988	LANES BY DIR: 1 West	CC STN:	RR CROSSING:
BEGIN DATE: 4/21/2014	WEEK OF YEAR: 16	ADDL DATA:	HPMS SAMPLE:
NOTES 1: WB TRAVEL LANE	PLACEMENT: 1200 FT W OF FREEMONT RD	JURISDICTION: 02-County	1 WAY CODE:
NOTES 2:			COUNT TYPE: Axle
TAKEN BY: TST----	PROCESSED BY: R03-JAB	BATCH ID: DOT-R03R3 WW	SPEED LIMIT: 55

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
4/21, Mon														397	414	445	499	427	312	228	157	111	64	58	3112		
4/22, Tue	24	14	22	29	66	163	473	862	589	353	348	358	381	349	350	459	501	411	314	204	143	90	74	37	6614	862	07-08
4/23, Wed	19	11	19	34	61	196	437	820	628	348	356	329	348	353	377	387	483	470	332	189	161	118	81	47	6604	820	07-08
4/24, Thu	16	14	26	28	62	196	452	816	589	378	360	403													3340		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																									AWDT		
	19	13	22	30	62	182	446	818	591	353	348	357	358	360	373	423	485	428	314	203	151	104	72	46	6558		

AVERAGE WEEKDAY											ESTIMATED		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	East High Hour	% of day	West High Hour	% of day		Roadway AADT	East AADT	West AADT
3	71	3	71	1348	9.9	903	12.9	818	12.5		12884	6648	6237
FACTOR													
Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl				
4	1.05		1.00	1.00	1.00	1.00			0.98				

STATION: 331143

New York State Department of Transportation Roadway Traffic Count Hourly Report

ROUTE/ROAD: GIRDEN RD	FROM: KIRKVILLE RD	TO: DEAD END	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 1, 5	REF. MARKER:	FUNC. CLASS: 19 - U Local System	MUNI: De Witt-Town-0233
ST DIR CODE: 1, 2	END MILEPOST: .61	FACTOR GROUP: 30	BIN:
DOT ID: 131758	LANES BY DIR: 1 North 1 South	CC STN:	RR CROSSING:
BEGIN DATE: 6/24/2013	WEEK OF YEAR: 25	ADDL DATA:	HPMS SAMPLE:
NOTES 1: nb travel lane	PLACEMENT: .35 miles south of kirksvill	JURISDICTION: 03-Town	1 WAY CODE:
NOTES 2: sb travel lane			COUNT TYPE: Vehicle
TAKEN BY: TST-dnm	PROCESSED BY: R03-JAB	BATCH ID: DOT-R03r3ww26	SPEED LIMIT:

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
6/24, Mon													11	11	19	18	11	5	3	6	2	0	4	5	95		
6/25, Tue	1	4	2	0	1	5	13	8	11	5	11	16	12	17	26	15	6	3	2	3	0	1	8	4	174	26	14-15
6/26, Wed	0	0	0	4	4	7	9	10	9	8	7	15	6	12	17	15	5	3	1	4	3	5	11	1	156	17	14-15
6/27, Thu	3	3	0	0	3	8	11	8	12	4	10														62		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																											
	1	2	1	1	3	7	11	9	11	6	9	16	10	13	21	16	7	4	2	4	2	2	8	3	168		

AVERAGE WEEKDAY											ESTIMATED AADT		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	North High Hour	% of day	South High Hour	% of day		Roadway	North	South
3	71	3	71	21	12.5	10	13.2	10	11		159	73	86
FACTOR													
Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl				
6	1.05		1.00	1.00	1.00	1.00			1.00				

STATION: 331143

New York State Department of Transportation

NB Traffic Count Hourly Report

ROUTE/ROAD: GIRDEN RD	FROM: KIRKVILLE RD	TO: DEAD END	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 1	REF. MARKER:	FUNC. CLASS: 19 - U Local System	MUNI: De Witt-Town-0233
ST DIR CODE: 1, 2	END MILEPOST: .61	FACTOR GROUP: 30	BIN:
DOT ID: 131758	LANES BY DIR: 1 North	CC STN:	RR CROSSING:
BEGIN DATE: 6/24/2013	WEEK OF YEAR: 25	ADDL DATA:	HPMS SAMPLE:
NOTES 1: nb travel lane	PLACEMENT: .35 miles south of kirksvill	JURISDICTION: 03-Town	1 WAY CODE:
NOTES 2: sb travel lane			COUNT TYPE: Vehicle
TAKEN BY: TST-dnm	PROCESSED BY: R03-JAB	BATCH ID: DOT-R03r3ww26	SPEED LIMIT:

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
6/24, Mon													2	6	9	10	5	3	3	2	2	0	1	5	48		
6/25, Tue	0	3	1	0	0	1	2	4	5	1	5	7	6	7	14	7	3	2	1	1	0	0	5	4	79	14	14-15
6/26, Wed	0	0	0	3	1	2	1	3	2	6	3	8	3	7	8	7	2	1	1	0	2	4	7	1	72	8	14-15
6/27, Thu	2	3	0	0	0	2	2	2	5	0	7														23		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																											
	1	2	0	1	0	2	2	3	4	2	5	8	4	7	10	8	3	2	2	1	1	1	4	3	76		

AVERAGE WEEKDAY											ESTIMATED AADT		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	North High Hour	% of day	South High Hour	% of day		Roadway	North	South
3	71	3	71	21	12.5	10	13.2	10	11		159	73	86

FACTOR										
Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl	
6	1.05		1.00	1.00	1.00	1.00			1.00	

New York State Department of Transportation

SB Traffic Count Hourly Report

STATION: 331143

ROUTE/ROAD: GIRDEN RD	FROM: KIRKVILLE RD	TO: DEAD END	REGION-COUNTY: 3-ONONDAGA
FED DIR CODE: 5	REF. MARKER:	FUNC. CLASS: 19 - U Local System	MUNI: De Witt-Town-0233
ST DIR CODE: 1, 2	END MILEPOST: .61	FACTOR GROUP: 30	BIN:
DOT ID: 131758	LANES BY DIR: 1 South	CC STN:	RR CROSSING:
BEGIN DATE: 6/24/2013	WEEK OF YEAR: 25	ADDL DATA:	HPMS SAMPLE:
NOTES 1: nb travel lane	PLACEMENT: .35 miles south of kirksvill	JURISDICTION: 03-Town	1 WAY CODE:
NOTES 2: sb travel lane			COUNT TYPE: Vehicle
TAKEN BY: TST-dnm	PROCESSED BY: R03-JAB	BATCH ID: DOT-R03r3ww26	SPEED LIMIT:

DATE	00-01	01-02	02-03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24	DAILY TOTAL	HIGH COUNT	HIGH HOUR
6/24, Mon													9	5	10	8	6	2	0	4	0	0	3	0	47		
6/25, Tue	1	1	1	0	1	4	11	4	6	4	6	9	6	10	12	8	3	1	1	2	0	1	3	0	95	12	14-15
6/26, Wed	0	0	0	1	3	5	8	7	7	2	4	7	3	5	9	8	3	2	0	4	1	1	4	0	84	9	14-15
6/27, Thu	1	0	0	0	3	6	9	6	7	4	3														39		
AVERAGE WEEKDAY HOURS (Axle Factored, Mon 6 AM to Fri Noon)																								AWDT			
	1	0	0	0	2	5	9	6	7	3	4	8	6	7	10	8	4	2	0	3	0	1	3	0	91		

AVERAGE WEEKDAY											ESTIMATED AADT		
DAYS Counted	HOURS Counted	WEEKDAYS Counted	WEEKDAY Hours	Roadway High Hour	% of day	North High Hour	% of day	South High Hour	% of day		Roadway	North	South
3	71	3	71	21	12.5	10	13.2	10	11		159	73	86
FACTOR													
Month	Seasonal	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Axl				
6	1.05		1.00	1.00	1.00	1.00			1.00				

Intersection Gap Study

Project: Proposed International Container Transfer Facility, Town of DeWitt, NY
 Date: 12/4/2018



Intersection: Girden Road @ Kirkville Road
 Movement: Right Turns Exiting / Left Turns Entering

Time Interval		6-9 sec x 1	10-13 sec x 2	14-17 sec x 3	18-19 sec x 4	20-23 sec x 5	24-25 sec x 6	26-29 sec x 7	>29 sec x 8	Interval Total	Hour Total
Morning Peak											
7:15-7:30am	# of Gaps	21	11	7	3	3	1	0	0		
	# of Vehicles	21	22	21	12	15	6	0	0	97	
7:30-7:45am	# of Gaps	23	8	7	1	2	0	1	3		
	# of Vehicles	23	16	21	4	10	0	7	24	105	
7:45-8:00am	# of Gaps	18	6	6	2	2	2	0	0		
	# of Vehicles	18	12	18	8	10	12	0	0	78	
8:00-8:15am	# of Gaps	10	14	5	0	3	2	1	4		
	# of Vehicles	10	28	15	0	15	12	7	32	119	399

Evening Peak											
4:00-4:15pm	# of Gaps	15	5	5	1	1	0	0	0		
	# of Vehicles	15	10	15	4	5	0	0	0	49	
4:15-4:30pm	# of Gaps	22	11	3	1	0	0	0	0		
	# of Vehicles	22	22	9	4	0	0	0	0	57	
4:30-4:45pm	# of Gaps	15	4	5	2	1	0	0	0		
	# of Vehicles	15	8	15	8	5	0	0	0	51	
4:55-5:00pm	# of Gaps	15	6	1	0	0	0	0	0		
	# of Vehicles	15	12	3	0	0	0	0	0	30	187

Intersection Gap Study

Project: Proposed International Container Transfer Facility, Town of DeWitt, NY
 Date: 12/4/2018



Intersection: Girden Road @ Kirkville Road
 Movement: Left Turns Exiting

Time Interval		6-9 sec x 1	10-13 sec x 2	14-17 sec x 3	18-19 sec x 4	20-23 sec x 5	24-25 sec x 6	26-29 sec x 7	>29 sec x 8	Interval Total	Hour Total
Morning Peak											
7:15-7:30am	# of Gaps	10	5	3	0	1	0	0	0		
	# of Vehicles	10	10	9	0	5	0	0	0	34	
7:30-7:45am	# of Gaps	12	2	1	0	0	0	0	0		
	# of Vehicles	12	4	3	0	0	0	0	0	19	
7:45-8:00am	# of Gaps	7	0	1	1	0	0	0	0		
	# of Vehicles	7	0	3	4	0	0	0	0	14	
8:00-8:15am	# of Gaps	18	7	1	0	0	0	0	0		
	# of Vehicles	18	14	3	0	0	0	0	0	35	102

Evening Peak											
4:00-4:15pm	# of Gaps	12	6	2	0	0	0	0	0		
	# of Vehicles	12	12	6	0	0	0	0	0	30	
4:15-4:30pm	# of Gaps	16	4	1	0	0	0	0	0		
	# of Vehicles	16	8	3	0	0	0	0	0	27	
4:30-4:45pm	# of Gaps	11	2	0	0	0	0	0	0		
	# of Vehicles	11	4	0	0	0	0	0	0	15	
4:55-5:00pm	# of Gaps	13	3	1	0	0	0	0	0		
	# of Vehicles	13	6	3	0	0	0	0	0	22	94

Proposed International Container Transfer Facility - Girden Road, Town of DeWitt, NY

Speed Study Measurements - Kirkville Road Passing Girden Road

12/4/2018

Distance Travelled (ft) = 285

50 Speed Measurements per Direction

Speed Limit 45 mph

EB Time Seconds	Calculated Speed	EB Time Seconds	Calculated Speed	WB Time Seconds	Calculated Speed	WB Time Seconds	Calculated Speed
4.47	43	3.88	50	5.09	38	4	49
4.38	44	3.88	50	4.72	41	4	49
4.37	44	3.87	50	4.69	41	4	49
4.34	45	3.87	50	4.53	43	3.97	49
4.31	45	3.85	50	4.47	43	3.97	49
4.25	46	3.85	50	4.46	44	3.95	49
4.21	46	3.82	51	4.38	44	3.94	49
4.19	46	3.82	51	4.35	45	3.91	50
4.18	46	3.82	51	4.32	45	3.87	50
4.15	47	3.78	51	4.31	45	3.84	51
4.13	47	3.78	51	4.25	46	3.84	51
4.1	47	3.76	52	4.21	46	3.83	51
4.1	47	3.76	52	4.19	46	3.82	51
4.06	48	3.72	52	4.19	46	3.81	51
4.06	48	3.71	52	4.16	47	3.79	51
4.06	48	3.69	53	4.15	47	3.78	51
4.03	48	3.69	53	4.15	47	3.78	51
4.01	48	3.69	53	4.13	47	3.78	51
3.97	49	3.68	53	4.13	47	3.71	52
3.97	49	3.62	54	4.09	48	3.69	53
3.97	49	3.6	54	4.07	48	3.69	53
3.94	49	3.59	54	4.05	48	3.69	53
3.94	49	3.59	54	4.05	48	3.69	53
3.93	49	3.56	55	4.02	48	3.67	53
3.92	50	3.41	57	4.02	48	3.67	53

Eastbound

Average Speed = 50 mph

85th Percentile Speed = 53 mph

Westbound

Average Speed = 48 mph

85th Percentile Speed = 51 mph

Background Traffic Growth Calculations

Proposed International Container Transfer Facility, Girden Road, Town of DeWitt, NY

Historical Traffic Counts Taken from the NYSDOT 2016 Traffic Volume Report

Kirkville Road - Between Roberts Street and Manlius Town Line (Girden Road)

2016 (Est)	2014	2011	2008
15,713 veh	15,837 veh	15,732 veh	14,572 veh
-0.4% per year	+0.2% per year	+2.7% per year	
-0.0% per year			
+1.0% per year			

Kirkville Road - Between Manlius Town Line (Girden Road) and Freemont Road

2016 (Est)	2014	2011	2008
12,865 veh	12,966 veh	16,177 veh	14,427 veh
-0.0% per year	-6.7% per year	+4.0% per year	
-4.1% per year			
-1.4% per year			

Use +1.0% annual growth for traffic projections

Proposed International Container Transfer Facility - Girden Road, Town of DeWitt, NY
Accident History Summaries - September 1 2013 Through August 31, 2018

Accident #	Date	Location	Type	# Cars	Severity	Direction	Conditions	Contributing Factors
1	10/8/2013	Kirkville / Girden	Left Turn	2	INJ	WB Left / WB	Dry	Failure to Yield ROW
2	7/3/2014	Kirkville / Girden	Right Angle	2	PDO	NB / WB	Wet	Failure to Yield ROW
3	8/22/2014	Kirkville / Driveway	Right Angle	2	INJ	SB Left / WB	Wet	Driver Inattention
4	2/16/2015	Kirkville Road	Rear End	3	INJ	EB / EB Stopped / WB	Dry	Unsafe Speed
5	2/2/2018	Kirkville Road	Fixed Object	1	PDO	WB / Ditch	Wet	Slippery Pavement

Kirkville Road @ Girden Road - 2 Accidents

1 - Left Turn Accident

1 - Right Angle Accident

Kirkville Road @ Girden Road Intersection - Evening Peak Hour - 1,659 Vehicles. Assumed PM Peak is 9% of AADT, AADT = 18,433 Vehicles

Intersection Accident Rates

$$\frac{\# \text{ Accidents} \times 1,000,000}{\text{AADT} \times \# \text{ Years} \times 365 \text{ Days}}$$

Time Period = 5 years

Kirkville Road @ Girden Road - 2 Accidents

Accident Rate = .059 accidents per million entering vehicles

Statewide average for similar facilities = 0.17 accidents per million entering vehicles (Rural - 3 Legged Intersection - All Lanes)

Intersection Accident History is Below the Statewide Average


File Name : Kirkville Road @ Girden Road
 Site Code : 00000001
 Start Date : 12/4/2018
 Page No : 1

Groups Printed- Cars - Trucks

	Southbound				Kirkville Road Westbound				Girden Road Northbound				Kirkville Road Eastbound				Int. Total
Start Time	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Right	Thru	Left	Peds	Right	Thru	Left	Peds	
07:00 AM	0	0	0	0	0	202	0	0	0	0	2	0	0	102	0	0	306
07:15 AM	0	0	0	0	0	199	0	0	0	0	0	0	2	153	0	0	354
07:30 AM	0	0	0	0	0	286	0	0	0	0	0	0	1	153	0	0	440
07:45 AM	0	0	0	0	0	328	1	0	0	0	0	0	1	198	0	0	528
Total	0	0	0	0	0	1015	1	0	0	0	2	0	4	606	0	0	1628
08:00 AM	0	0	0	0	0	231	1	0	1	0	0	0	1	112	0	0	346
08:15 AM	0	0	0	0	0	147	0	0	0	0	2	0	1	109	0	0	259
08:30 AM	0	0	0	0	0	171	2	0	1	0	0	0	1	153	0	0	328
08:45 AM	0	0	0	0	0	128	0	0	0	0	0	0	1	106	0	0	235
Total	0	0	0	0	0	677	3	0	2	0	2	0	4	480	0	0	1168
04:00 PM	0	0	0	0	0	166	0	0	0	0	1	0	1	242	0	0	410
04:15 PM	0	0	0	0	0	169	0	0	0	0	1	0	0	246	0	0	416
04:30 PM	0	0	0	0	0	156	0	0	0	0	2	0	1	235	0	0	394
04:45 PM	0	0	0	0	0	133	0	0	0	0	1	0	1	304	0	0	439
Total	0	0	0	0	0	624	0	0	0	0	5	0	3	1027	0	0	1659
05:00 PM	0	0	0	0	0	112	0	0	0	0	0	0	0	292	0	0	404
05:15 PM	0	0	0	0	0	96	0	0	0	0	0	0	1	253	0	0	350
05:30 PM	0	0	0	0	0	117	0	0	0	0	0	0	0	209	0	0	326
05:45 PM	0	0	0	0	0	135	0	0	0	0	0	0	0	185	0	0	320
Total	0	0	0	0	0	460	0	0	0	0	0	0	1	939	0	0	1400
Grand Total	0	0	0	0	0	2776	4	0	2	0	9	0	12	3052	0	0	5855
Apprch %	0	0	0	0	0	99.9	0.1	0	18.2	0	81.8	0	0.4	99.6	0	0	
Total %	0	0	0	0	0	47.4	0.1	0	0	0	0.2	0	0.2	52.1	0	0	
Cars	0	0	0	0	0	2701	4	0	2	0	7	0	11	2982	0	0	5707
% Cars	0	0	0	0	0	97.3	100	0	100	0	77.8	0	91.7	97.7	0	0	97.5
Trucks	0	0	0	0	0	75	0	0	0	0	2	0	1	70	0	0	148
% Trucks	0	0	0	0	0	2.7	0	0	0	0	22.2	0	8.3	2.3	0	0	2.5


File Name : Kirkville Road @ Girden Road
 Site Code : 00000001
 Start Date : 12/4/2018
 Page No : 2

	Southbound					Kirkville Road Westbound					Girden Road Northbound					Kirkville Road Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 11:45 AM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:15 AM																					
07:15 AM	0	0	0	0	0	0	199	0	0	199	0	0	0	0	0	2	153	0	0	155	354
07:30 AM	0	0	0	0	0	0	286	0	0	286	0	0	0	0	0	1	153	0	0	154	440
07:45 AM	0	0	0	0	0	0	328	1	0	329	0	0	0	0	0	1	198	0	0	199	528
08:00 AM	0	0	0	0	0	0	231	1	0	232	1	0	0	0	1	1	112	0	0	113	346
Total Volume	0	0	0	0	0	0	1044	2	0	1046	1	0	0	0	1	5	616	0	0	621	1668
% App. Total	0	0	0	0	0	0	99.8	0.2	0		100	0	0	0		0.8	99.2	0	0		
PHF	.000	.000	.000	.000	.000	.000	.796	.500	.000	.795	.250	.000	.000	.000	.250	.625	.778	.000	.000	.780	.790
Cars	0	0	0	0	0	0	1023														
% Cars	0	0	0	0	0	0	98.0	100	0	98.0	100	0	0	0	100	80.0	98.1	0	0	97.9	98.0
Trucks	0	0	0	0	0	0	21	0	0	21	0	0	0	0	0	1	12	0	0	13	34
% Trucks	0	0	0	0	0	0	2.0	0	0	2.0	0	0	0	0	0	20.0	1.9	0	0	2.1	2.0



File Name : Kirkville Road @ Girden Road
 Site Code : 00000001
 Start Date : 12/4/2018
 Page No : 3

	Southbound					Kirkville Road Westbound					Girden Road Northbound					Kirkville Road Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 12:00 PM to 05:45 PM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 04:00 PM																					
04:00 PM	0	0	0	0	0	0	166	0	0	166	0	0	1	0	1	1	242	0	0	243	410
04:15 PM	0	0	0	0	0	0	169	0	0	169	0	0	1	0	1	0	246	0	0	246	416
04:30 PM	0	0	0	0	0	0	156	0	0	156	0	0	2	0	2	1	235	0	0	236	394
04:45 PM	0	0	0	0	0	0	133	0	0	133	0	0	1	0	1	1	304	0	0	305	439
Total Volume	0	0	0	0	0	0	624	0	0	624	0	0	5	0	5	3	1027	0	0	1030	1659
% App. Total	0	0	0	0	0	0	100	0	0	100	0	0	100	0	100	0.3	99.7	0	0	100	100
PHF	.000	.000	.000	.000	.000	.000	.923	.000	.000	.923	.000	.000	.625	.000	.625	.750	.845	.000	.000	.844	.945
Cars	0	0	0	0	0	0	609	0	0	609	0	0	4	0	4	3	1004	0	0	1004	1659
% Cars	0	0	0	0	0	0	97.6	0	0	97.6	0	0	80.0	0	80.0	100	97.8	0	0	97.8	97.6
Trucks	0	0	0	0	0	0	15	0	0	15	0	0	1	0	1	0	23	0	0	23	39
% Trucks	0	0	0	0	0	0	2.4	0	0	2.4	0	0	20.0	0	20.0	0	2.2	0	0	2.2	2.4



HCM 2010 TWSC
3: Girden Road & Kirkville Road

12/05/2018

Intersection

Int Delay, s/veh 0

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	616	5	2	1044	0	1
Future Vol, veh/h	616	5	2	1044	0	1
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	78	78	80	80	90	90
Heavy Vehicles, %	2	20	0	2	0	0
Mvmt Flow	790	6	3	1305	0	1

Major/Minor	Major1	Major2	Minor1
Conflicting Flow All	0	0	796
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	-	4.1
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	-	2.2
Pot Cap-1 Maneuver	-	-	835
Stage 1	-	-	-
Stage 2	-	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	-	835
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	EB	WB	NB
HCM Control Delay, s	0	0	14.2
HCM LOS			B

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	392	-	-	835	-
HCM Lane V/C Ratio	0.003	-	-	0.003	-
HCM Control Delay (s)	14.2	-	-	9.3	0
HCM Lane LOS	B	-	-	A	A
HCM 95th %tile Q(veh)	0	-	-	0	-

HCM 2010 TWSC
3: Girden Road & Kirkville Road

12/05/2018

Intersection

Int Delay, s/veh 0.2

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	1027	3	0	624	5	0
Future Vol, veh/h	1027	3	0	624	5	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	84	84	92	92	90	90
Heavy Vehicles, %	2	0	0	2	20	0
Mvmt Flow	1223	4	0	678	6	0

Major/Minor	Major1	Major2	Minor1
Conflicting Flow All	0	0	1227
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	4.1	-
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	2.2	-
Pot Cap-1 Maneuver	-	575	-
Stage 1	-	-	-
Stage 2	-	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	575	-
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	EB	WB	NB
HCM Control Delay, s	0	0	62.6
HCM LOS			F

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	68	-	-	575	-
HCM Lane V/C Ratio	0.082	-	-	-	-
HCM Control Delay (s)	62.6	-	-	0	-
HCM Lane LOS	F	-	-	A	-
HCM 95th %tile Q(veh)	0.3	-	-	0	-

HCM 2010 TWSC
3: Girden Road & Kirkville Road

12/05/2018

Intersection

Int Delay, s/veh 0

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	647	5	2	1096	0	1
Future Vol, veh/h	647	5	2	1096	0	1
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	78	78	80	80	90	90
Heavy Vehicles, %	2	20	0	2	0	0
Mvmt Flow	829	6	3	1370	0	1

Major/Minor	Major1	Major2	Minor1
Conflicting Flow All	0	0	835
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	-	4.1
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	-	2.2
Pot Cap-1 Maneuver	-	-	807
Stage 1	-	-	-
Stage 2	-	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	-	807
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	EB	WB	NB
HCM Control Delay, s	0	0	14.7
HCM LOS			B

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	372	-	-	807	-
HCM Lane V/C Ratio	0.003	-	-	0.003	-
HCM Control Delay (s)	14.7	-	-	9.5	0
HCM Lane LOS	B	-	-	A	A
HCM 95th %tile Q(veh)	0	-	-	0	-

HCM 2010 TWSC
3: Girden Road & Kirkville Road

12/05/2018

Intersection

Int Delay, s/veh 0.2

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	1078	3	0	655	5	0
Future Vol, veh/h	1078	3	0	655	5	0
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	84	84	92	92	90	90
Heavy Vehicles, %	2	0	0	2	20	0
Mvmt Flow	1283	4	0	712	6	0

Major/Minor	Major1	Major2	Minor1
Conflicting Flow All	0	0	1287
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	4.1	-
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	2.2	-
Pot Cap-1 Maneuver	-	546	-
Stage 1	-	-	-
Stage 2	-	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	546	-
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	EB	WB	NB
HCM Control Delay, s	0	0	72.3
HCM LOS			F

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	59	-	-	546	-
HCM Lane V/C Ratio	0.094	-	-	-	-
HCM Control Delay (s)	72.3	-	-	0	-
HCM Lane LOS	F	-	-	A	-
HCM 95th %tile Q(veh)	0.3	-	-	0	-

HCM 2010 TWSC

3: Girden Road & Kirkville Road

12/05/2018

Intersection

Int Delay, s/veh 1.3

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	647	16	8	1096	11	7
Future Vol, veh/h	647	16	8	1096	11	7
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	78	78	80	80	90	90
Heavy Vehicles, %	2	50	0	2	64	0
Mvmt Flow	829	21	10	1370	12	8

Major/Minor	Major1	Major2	Minor1
Conflicting Flow All	0	0	850
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	-	4.1
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	-	2.2
Pot Cap-1 Maneuver	-	-	797
Stage 1	-	-	-
Stage 2	-	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	-	797
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	EB	WB	NB
HCM Control Delay, s	0	0.1	137.8
HCM LOS			F

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	45	-	-	797	-
HCM Lane V/C Ratio	0.444	-	-	0.013	-
HCM Control Delay (s)	137.8	-	-	9.6	0
HCM Lane LOS	F	-	-	A	A
HCM 95th %tile Q(veh)	1.6	-	-	0	-

HCM 2010 TWSC

3: Girden Road & Kirkville Road

12/05/2018

Intersection

Int Delay, s/veh 1.3

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	1078	14	6	655	16	6
Future Vol, veh/h	1078	14	6	655	16	6
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	84	84	92	92	90	90
Heavy Vehicles, %	2	50	0	2	50	0
Mvmt Flow	1283	17	7	712	18	7

Major/Minor	Major1	Major2	Minor1
Conflicting Flow All	0	0	1300
Stage 1	-	-	-
Stage 2	-	-	-
Critical Hdwy	-	-	4.1
Critical Hdwy Stg 1	-	-	-
Critical Hdwy Stg 2	-	-	-
Follow-up Hdwy	-	-	2.2
Pot Cap-1 Maneuver	-	-	540
Stage 1	-	-	-
Stage 2	-	-	-
Platoon blocked, %	-	-	-
Mov Cap-1 Maneuver	-	-	540
Mov Cap-2 Maneuver	-	-	-
Stage 1	-	-	-
Stage 2	-	-	-

Approach	EB	WB	NB
HCM Control Delay, s	0	0.1	106.4
HCM LOS			F

Minor Lane/Major Mvmt	NBLn1	EBT	EBR	WBL	WBT
Capacity (veh/h)	58	-	-	540	-
HCM Lane V/C Ratio	0.421	-	-	0.012	-
HCM Control Delay (s)	106.4	-	-	11.7	0
HCM Lane LOS	F	-	-	B	A
HCM 95th %tile Q(veh)	1.6	-	-	0	-



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



APPENDIX E NRCS SOIL MAPS



[THIS PAGE IS LEFT INTENTIONALLY BLANK]

Hydrologic Soil Group—Onondaga County, New York (CNYIP Soil Map)



**Natural Resources
Conservation Service**

Web Soil Survey
National Cooperative Soil Survey

8/2/2019
Page 1 of 4

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

Soil Rating Polygons

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points

 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available

Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Onondaga County, New York
 Survey Area Data: Version 13, Sep 3, 2018

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Dec 31, 2009—Sep 23, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
GaA	Galen very fine sandy loam, 0 to 2 percent slopes	A/D	8.0	1.8%
GaB	Galen very fine sandy loam, 2 to 6 percent slopes	A/D	7.0	1.6%
LbC2	Lairdsville silty clay loam, 6 to 12 percent slopes, eroded	D	9.2	2.1%
Lk	Lakemont silty clay loam, 0 to 3 percent slopes	D	21.6	4.9%
Lm	Lamson very fine sandy loam	A/D	15.2	3.5%
LvB	Lockport and Brockport silty clay loams, 0 to 6 percent slopes	C/D	65.9	15.0%
MtA	Minoa fine sandy loam, 0 to 2 percent slopes	B/D	29.8	6.8%
Na	Naumburg loamy fine sand	A/D	5.3	1.2%
NgA	Niagara silt loam, 0 to 4 percent slopes	C/D	99.1	22.6%
OgB	Ontario loam, 3 to 8 percent slopes	B	0.1	0.0%
PpA	Phelps gravelly loam, 0 to 3 percent slopes	B/D	4.9	1.1%
PpB	Phelps gravelly loam, 3 to 8 percent slopes	B/D	15.6	3.6%
Te	Teel silt loam	B/D	4.1	0.9%
Ub	Urban land		98.3	22.4%
Wn	Wayland soils complex, 0 to 3 percent slopes, frequently flooded	B/D	53.5	12.2%
WwB	Williamson silt loam, 2 to 6 percent slopes	D	1.2	0.3%
Totals for Area of Interest			438.9	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified


Tie-break Rule: Higher



APPENDIX F FEMA FLOODPLAIN MAP



[THIS PAGE IS LEFT INTENTIONALLY BLANK]




JOINS PANEL 0234

47°00'00"N

OF0224



MAP SCALE 1" = 500'



NATIONAL FLOOD INSURANCE PROGRAM

PANEL 0233F

FIRM

FLOOD INSURANCE RATE MAP
ONONDAGA COUNTY,
NEW YORK
 (ALL JURISDICTIONS)

PANEL 233 OF 520

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
DEWITT, TOWN OF	360973	0233	F
EAST SYRACUSE, VILLAGE OF	360574	0233	F
MANLIUS, TOWN OF	360584	0233	F

Notice to User: The **Map Number** shown below should be used when placing map orders; the **Community Number** shown above should be used on insurance applications for the subject community.



MAP NUMBER
36067C0233F


EFFECTIVE DATE
NOVEMBER 4, 2016

Federal Emergency Management Agency


This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov



[THIS PAGE IS LEFT INTENTIONALLY BLANK]



1 LAYOUT PLAN - CONTAINER POOLING YARD
SK-2 SCALE: 1"=40'



2 OVERALL LAYOUT PLAN
SK-2 SCALE: 1"=250'

PRELIMINARY
FOR PLANNING
PURPOSES ONLY, NOT
FOR CONSTRUCTION.

COPYRIGHT © 2019
NAPIERALA CONSULTING
THIS DOCUMENT IS THE PROPERTY OF NAPIERALA CONSULTING, P.C. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF NAPIERALA CONSULTING, P.C.

PROJECT NO.
17-1588

DATE
18 DEC 2019

SCALE
AS SHOWN

PREPARED BY:
NAPIERALA CONSULTING
PROFESSIONAL ENGINEER, P.C.
SITE • DESIGN • ENGINEERING
110 FAYETTE STREET
MANLIUS, NEW YORK 13104
email: MNA@NAPCON.COM
PH: (315) 682-5580 FAX: (315) 682-5544

NO.	REVISION/ISSUE	DATE


PROJECT TITLE:
**PROPOSED CPO FACILITY
GIRDEN ROAD**
TOWN OF MANLIUS
ONONDAGA COUNTY, NY
PREPARED FOR:
THIRD GENERATION INTERMODAL (3GI)
360 ERIE BOULEVARD EAST
SYRACUSE, NY 13202

LAYOUT PLAN

SHEET TITLE:

SHEET

SK-2



LANDSCAPE LEGEND						
KEY	QUANTITY	LATIN NAME	COMMON NAME	CALIPER	HEIGHT	ROOT
DECIDUOUS TREES						
	12	PICEA GLAUCA	WHITE SPRUCE	2½"	—	B&B
	11	PINUS STROBUS	WHITE PINE	2½"	—	B&B
	2	ACER RUBRUM	RED MAPLE	2½"	—	B&B

LEGEND:

XX XX

SPECIES KEY

QUANTITY

LANDSCAPING NOTES:

1. ALL TREES AND SHRUBS SHALL BE SURROUNDED BY A BED OF BARK MULCH UNLESS OTHERWISE SPECIFIED.
2. DEAD MATERIAL SHALL BE REPLACED AND PLANT MATERIAL SHALL BE REGULARLY PRUNED AND NOURISHED TO MAINTAIN HEALTH.
3. TREES AND SHRUBS IDENTIFIED MAY BE SUBSTITUTED AT THE OWNER AND/OR LANDSCAPER'S REQUEST WITH SIMILAR/ALTERNATE SPECIES BASED ON PREFERENCE AND LOCAL AVAILABILITY.

GRAPHIC SCALE

(IN FEET)
1 inch = 40 ft

PRELIMINARY
FOR PLANNING PURPOSES ONLY,
NOT FOR CONSTRUCTION.

PLAN SEAL BY:
MATTHEW R. NAPIERALA, P.E.
NYS REGISTRATION # 068733

17-1588

48 DEC 2010

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

PREPARED BY:

**NAPIERALA
CONSULTING**
PROFESSIONAL ENGINEER, P.C.
SITE • DESIGN • ENGINEERING
110 FANETTE STREET
MANLUS, NEW YORK 13104

email: MNAP@NAPCON.COM
PH: (315) 682-5580 FAX: (315) 682-5544



GRADING AND LANDSCAPING PLAN


PROJECT TITLE: **PROPOSED CPO FACILITY
GIRDEN ROAD**

TOWN OF MANLIUS ONONDAGA COUNTY, NY


PREPARED FOR: **THIRD GENERATION INTERMODAL (3GI)**

**360 ERIE BOULEVARD EAST
SYRACUSE, NY 13202**

SK-3



BRIDLE PATH
GENESEE TURNPIKE TOWN OF MANLIUS
CONCEPT PLAN



DECEMBER 13, 2019



KEPLINGER
FREEMAN
ASSOCIATES



LANDSCAPE ARCHITECTURE & LAND PLANNING

6320 FLY ROAD EAST SYRACUSE, NEW YORK 13057
PHONE (315) 445-7980 FAX (315) 445-7981

TOWN OF MANLIUS ZONING CHART		X-MANLIUS-ZONING
1. CURRENT ZONING		
- TAX MAP #0822-01-02.0 & 0822-01-03.0 ARE CURRENTLY ZONED RESTRICTED AGRICULTURE (RA) DISTRICTS. TAX MAP PARCEL 0822-01-02.0 IS SPLIT ZONED RA/CB. - THE FOLLOWING USES ARE PERMITTED IN RA DISTRICTS: - ANY USE PERMITTED IN RESIDENTIAL DISTRICT R-1, ACCORDING TO THE SAME RESTRICTIONS. - ANY USE PERMITTED IN RESIDENTIAL DISTRICT R-3, ACCORDING TO THE SAME RESTRICTIONS. - THE PROPOSED DEVELOPMENT WILL REQUIRE A ZONE CHANGE TO MEET TOWN OF MANLIUS CODE. EXISTING LOT TO BE SUBDIVIDED INTO (2) NEW LOTS ZONED R-5.		
2. RA BULK REGULATIONS (EXISTING)		
MIN. FRONTAGE	N/A	
MIN. LOT AREA	N/A	
FRONT YARD SETBACK	40'-0"	
SIDE YARD SETBACK	20'-0"	
REAR YARD SETBACK	40'-0"	
3. R-5 BULK REGULATIONS (PROPOSED) - 2 NEW LOTS		
MIN. FRONTAGE	N/A	
MIN. LOT AREA	NO LESS THAN FIVE ACRES, BUT NO MORE THAN 10 ACRES.	
SETBACK FROM HIGHWAY	50'-0"	
REAR AND SIDE YARD SETBACK	THE DISTANCE EQUAL TO THE HEIGHTS OF THE BUILDING, BUT IN NO CASE LESS THAN 30 FEET.	
BUILDING SPACING	(a) BLANK WALL TO BLANK WALL: 30 FEET. (b) WINDOW TO FACING BLANK WALL: 30 FEET. (c) WINDOW TO VISIBLE WINDOW: 40 FEET.	
BUILDING LENGTH	THE MAXIMUM LENGTH OF EACH BUILDING SHALL BE 60 FEET UNLESS A MINIMUM OFFSET OF FOUR FEET IS ESTABLISHED FOR EACH SIXTY-FOOT SECTION.	
BUILDING HEIGHT	NOT MORE THAN 40 FEET OR THREE STORIES, INCLUDING BASEMENT OR CELLAR, WHICHEVER IS LESS.	
USEABLE DISTRICT SPACE	5000 SF PER 2 BEDROOM DWELLING NEEDED: LOT 3.1- 60 X 5000 = 300,000 SF LOT 3.2- 12 X 5000 = 360,000 SF	
4. PARKING		
MIN. PARKING REQUIREMENT	2 SPOTS PER BEDROOM	
PROPOSED BEDROOMS		
	LOT 03.1	60 X 2 = 120 PARKING SPACES
	LOT 03.2	12 X 2 = 144 PARKING SPACES
	TOTAL	264 PARKING SPACES
PROPOSED PARKING COUNT		
	LOT 03.1	117 PARKING SPACES
	LOT 03.2	136 PARKING SPACES
	TOTAL	253 PARKING SPACES (-11)
5. PROPOSED DEVELOPMENT		
PARCEL TO BE SUBDIVIDED INTO (2) LOTS OF VARYING SIZES AS NOTED ON PLANS. LOT 3.1 AND 3.2 WILL CONFORM TO R-5 ZONING UNDER 10 ACRES IN SIZE. APPROXIMATELY 132 UNITS TO BE CONSTRUCTED WITHIN (5) BUILDINGS.		

ALL THAT TRCT OR PARCEL OF LAND situated in the Town of Manlius, County of Onondaga, State of New York, being part of Lot 58 and 59 in said Town and being more specifically described as follows:

Beginning at a point in the northerly line of N.Y. Route #5, (a/k/a E. Genesee Street), at the intersection of said northerly line with the easterly line of Lot 59 Town of Manlius, (being also the easterly line of Onondaga County and the westerly line of Madison County),.

Running thence N81°50'02"W a distance of 60.13 feet to the point and place of beginning,

Thence S04°25'29"W a distance of 700 feet along the westerly side of Strawmount Trail,

Thence N81°49'11"W a distance of 1040.03 feet,

Thence S04°45'25"W a distance of 700 feet to a point on the north side of N.Y.Route #5,

Thence S81°50'02"E along the northerly line of N.Y. Route #5 a distance of 704.20 feet,

Thence N04°25'29"E a distance of 150 feet,

Thence S81°50'02"E a distance of 200 feet,

Thence S04°25'29"W a distance of 150 feet,

Thence S81°50'02"E a distance of 139.87 feet along the northerly line of N.Y. Route #5, to the point and place of beginning, containing 16.025+/- acres of land

Subject to easements and restrictions of record.

Short Environmental Assessment Form


Part 1 - Project Information

Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 – Project and Sponsor Information				
Name of Action or Project: Bridle Path				
Project Location (describe, and attach a location map): Genesee Tpke and Strawmount Trail				
Brief Description of Proposed Action: Parcels to be subdivided into (2) lots of varying sizes as noted on plan. Project includes the construction of 132 residential units.				
Name of Applicant or Sponsor: Scott Freeman - Keplinger Freeman Associates		Telephone: 315-445-7980 E-Mail: sf@keplingerfreeman.com		
Address: 6320 Fly Road				
City/PO: East Syracuse		State: NY	Zip Code: 13057	
1. Does the proposed action only involve the legislative adoption of a plan, local law, ordinance, administrative rule, or regulation? If Yes, attach a narrative description of the intent of the proposed action and the environmental resources that may be affected in the municipality and proceed to Part 2. If no, continue to question 2.			NO ☒	YES ☐
2. Does the proposed action require a permit, approval or funding from any other government Agency? If Yes, list agency(s) name and permit or approval: Town of Manlius Town Board & Planning Board approval NYSDEC permit			NO ☐	YES ☒
3. a. Total acreage of the site of the proposed action? b. Total acreage to be physically disturbed? c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor?			16.02 acres 7.7 acres 16.02 acres	
4. Check all land uses that occur on, are adjoining or near the proposed action:				
5. ☐ Urban ☐ Rural (non-agriculture) ☐ Industrial ☐ Commercial ☒ Residential (suburban) ☐ Forest ☐ Agriculture ☐ Aquatic ☐ Other(Specify): ☐ Parkland				


14. Identify the typical habitat types that occur on, or are likely to be found on the project site. Check all that apply: ☐ Shoreline ☐ Forest ☐ Agricultural/grasslands ☐ Early mid-successional ☒ Wetland ☐ Urban ☒ Suburban		
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or Federal government as threatened or endangered?	NO	YES
	☒	☐
16. Is the project site located in the 100-year flood plan?	NO	YES
	☒	☐
17. Will the proposed action create storm water discharge, either from point or non-point sources? If Yes,	NO	YES
	☐	☒
a. Will storm water discharges flow to adjacent properties?	☒	☐
b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)? If Yes, briefly describe:	☐	☒
Storm water will be directed to storm inlets and conveyed to storm water basin(s).		
18. Does the proposed action include construction or other activities that would result in the impoundment of water or other liquids (e.g., retention pond, waste lagoon, dam)? If Yes, explain the purpose and size of the impoundment:	NO	YES
	☒	☐
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility? If Yes, describe:	NO	YES
	☒	☐
20. Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or completed) for hazardous waste? If Yes, describe:	NO	YES
	☒	☐
I CERTIFY THAT THE INFORMATION PROVIDED ABOVE IS TRUE AND ACCURATE TO THE BEST OF MY KNOWLEDGE Applicant/sponsor/name: <u>SCOTT FREEMAN (KEPUNGAN FREEMAN)</u> Date: <u>12-13-19</u> Signature: <u></u> Title: <u>PARTNER</u>		

L.D:
FILE:
B/P: 381/054

"NO CHANGE" AFFIDAVITS ISSUED ON THIS MAP VOID THE CERTIFICATION,
INFRINGE ON COPYRIGHT AND REPRESENT UNLICENSED SURVEY PRACTICE!
COPYRIGHT © 2005-
BY COTTRELL LAND SURVEYORS, P.C.
ALL RIGHTS RESERVED
COPIES WITHOUT THE EMBOSSED SEAL ARE UNAUTHORIZED
AND HAVE BEEN ALTERED.

SURVEYORS: REFERENCE TO, USE OF OR RELIANCE ON THIS MAP
WITHOUT THE WRITTEN CONSENT FOR WHATEVER PURPOSE VIOLATES MY
COPYRIGHT AND ABSOLVES ME OF ANY LIABILITY FOR LATENT OMISSIONS
AND ERRORS AND OF ANY RESPONSIBILITY FOR RESULTANT DAMAGES.

USERS: THIS MAP IS NOT USABLE NOR CERTIFICATIONS EXTENDABLE
FOR UNSPECIFIED PURPOSES OR FOR SUBSEQUENT TRANSACTIONS
EXCEPT BY THE WRITTEN CONSENT OF OR BY SURVEY UPDATE BY THE
UNDERSIGNED ONLY.



N. Y. S. ROUTE 5
(GENESEE TURNPIKE)
PART OF LOT 59 - TOWN OF MANLIUS
ONONDAGA CO., N. Y.

SCALE: 1" = 100'
NOV. 1, 2005
COTTRELL LAND SURVEYORS, P.C.
MANLIUS, NY - (315) 682-8121


Rev. 5/07/07

S04°45'25"W
700.00'

1040.03'
N81°49'11"W

AREA 16.025± AC.
(excl hwy.)

VACANT



700.00'
N04°25'29"E

ONONDAGA COUNTY
MADISON COUNTY


FOR CONVEYANCE AND/OR MORTGAGE PURPOSES OCCURRING
WITHIN ONE YEAR OF THE LATEST CERTIFICATION DATE ONLY.

THE UNDERSIGNED HEREBY CERTIFIES THAT THIS MAP
WAS MADE FROM AN ACTUAL SURVEY ON 03.16.05
VOID WITHOUT EMBOSSED SEAL

Gary E. Cottrell

POOLS_MEGNIN_2005_11_01.DWG

POOLSBRK.CRD



BRIDLE PATH - TAX MAP

DECEMBER 13, 2019

TOWN OF MANLIUS ZONE CHANGE APPLICATION

1. Name of Person applying for Zone Change Brandon Jacobson, managing member of Brolex Properties, LLC
Address of person applying 5912 North Burdick Street, Manlius, NY 13057
Cell Number _____ Phone Number (315) 559-0556
2. Name: (owner of record) of land where Zone Change would occur Donald Megnin Trust & Megnin Farms
Address (owner of record) 1301 Nottingham Road, Unit C211, Jamesville NY 13078
Cell Number (owner of record) _____ Phone Number _____
3. Tax Map Number of property where Zone Change would occur 082.2-01-02.0 & 082.2-01-03.0
4. Is this property located in a flood hazard area? No
If so, what flood area is the property in it in?

5. Present zoning classification of property RA - Restricted Agriculture / CB - Commercial B
6. Desired zoning classification R5 - Residential 5
Reason for Change of Zone (use additional sheets if necessary) Apartments are not a permitted use in Restricted Agricultural and Commercial Business Districts.

7. What is lot size? 16.02 acres
8. If the Zone Change is granted, will the use of the property conform to the District regulations as stated in Chapter 155 Article III of the Town of Manlius Municipal Code? Yes
9. Is the property within the protectively zoned area of a housing project authorized under the public housing law? No
10. Is the property within five hundred (500) feet of the boundaries of any city, village, town, county, state park or parkway? Yes
If yes, please specify Property is adjacent to the Madison County boundary line.
11. Is the property within five hundred (500) feet from the boundary of any existing or proposed County or State park or other recreation area, or from the right-of-way of any existing or proposed county or state parkway, thruway, expressway, road or highway, or from the existing or proposed right-of-way of any stream or drainage channel owned by the county or for which the county has established channel lines, or from the existing or proposed boundary of any county or state owned land on which a public building or institution is situated? Yes

If yes, please specify Property is adjacent to NY-5.

12. List the uses of all abutting property residential housing, commercial nursery, vacant land

13. The following must be included with your 12 application packets unless otherwise specified and/or specifically waived by the Town Board:

- An environmental assessment form which can be obtained from the Town Clerk, or an environmental impact statement.
- Copy of a survey of the premises certified by a New York State licensed surveyor.
- Legal description of the premises.
- This application must be signed by both the owner of record of the property and the applicant.

The failure to answer any question on this application, the failure to submit any item as specified or the failure to execute this application will result in a delay in the processing of the application.

Date 12-17-19

Donald Megnin

Donald H. Megnin
Applicant 1

Date 12-17-19

Brandon Jacobson, managing member of Brolex Properties, LLC

Applicant 2

Date _____

Applicant

TOWN OF MANLIUS

DISCLOSURE AFFIDAVIT

This affidavit is a part of and must be completed and attached to every application, petition, request submitted for a *site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit.*

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

I. Donald Megnin, being duly sworn, deposes and says that (s) he is:

property owner
(applicant, petitioner, corporation officer, property owner, *etc.*)

II. That deponent has read and is familiar with the provisions of the General Municipal Law, Section 809 which states:

- A. Every application, petition or request submitted for a site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit, pursuant to the provisions or any ordinance, local law, rule or regulation constituting the zoning and planning regulations of a municipality shall state the name, residence and the nature and extent of the interest of any state officer or any officer or employee of such municipality is a part, in the person, partnership or association making such application, petition or request (hereinafter called the applicant) to the extent known to such applicant.
- B. For the purpose of this action an officer or employee shall be deemed to have an interest in the applicant when (s)he, his/her spouse, or their brothers, sisters, parents, children, grandchildren, or the spouse of any of them:
 - 1) is the applicant, or
 - 2) is an officer, director, partner or employee of the applicant, or
 - 3) legally or beneficially owns or controls stock of a corporate applicant or is a member of a partnership or association applicant, or
 - 4) is a party to an agreement with such an applicant, express or implied, whereby (s) he may receive any payment or other benefit, whether or not for services rendered, or contingent upon the favorable approval of such application, petition or request.
- C. Ownership of less than five percent (5%) of the stock of a corporation whose stock is listed on the New York or American Stock Exchanges shall not constitute an interest for the purposes of this section.
- D. A person who knowingly and intentionally violates this section shall be guilty of a misdemeanor.

III. That no Town of Manlius officer, employee or a relative of either, as defined in Section 809 General Municipal Law has any interest in this application.

-OR-

If a Town of Manlius officer, employee or relative of either as defined in Section 809 General Municipal law has any interest in this application, the full particulars are provided on an attached sheet.

Date: _____, 20____.

(Print Name)

(Signature)

(Entity Name)

By (Officer) _____ (Title) _____

(Mailing Address of Applicant)

(Telephone Number)

Date: 1/2/2020, 20____.

DONALD F. MEGNIN
(Print Name) Trustee

Donald F. Megnin
(Signature)

(Entity Name)

By (Officer) _____ (Title) _____

1301 NOTTINGHAM RD APT C211, JAMESVILLE NY
(Mailing Address of Applicant) 13078

315 396 0080
(Telephone Number)

ACKNOWLEDGEMENTS

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

On this 2nd day of January in the year 2020, before me, the undersigned, a notary public in and for said state, personally appeared Donald F. Megnin, and _____ personally known to me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within Petition and acknowledged to me the he/she/they executed the same in his/her/their capacity, and that by his/her/their signature(s) on the Petition, the individual or the persons upon behalf of which the individual acted executed the instrument.

Brenda R. Green
Notary Public



TOWN OF MANLIUS

DISCLOSURE AFFIDAVIT

This affidavit is a part of and must be completed and attached to every application, petition, request submitted for a *site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit.*

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

I. Brandon Jacobson, being duly sworn, deposes and says that (s) he is:

managing member of Brolex Properties, LLC
(applicant, petitioner, corporation officer, property owner, *etc.*)

II. That deponent has read and is familiar with the provisions of the General Municipal Law, Section 809 which states:

- A. Every application, petition or request submitted for a site plan, variance, amendment, change of zoning, approval of a plat, exemption from a plat or official map, license or permit, pursuant to the provisions or any ordinance, local law, rule or regulation constituting the zoning and planning regulations of a municipality shall state the name, residence and the nature and extent of the interest of any state officer or any officer or employee of such municipality is a part, in the person, partnership or association making such application, petition or request (hereinafter called the applicant) to the extent known to such applicant.
- B. For the purpose of this action an officer or employee shall be deemed to have an interest in the applicant when (s)he, his/her spouse, or their brothers, sisters, parents, children, grandchildren, or the spouse of any of them:
 - 1) is the applicant, or
 - 2) is an officer, director, partner or employee of the applicant, or
 - 3) legally or beneficially owns or controls stock of a corporate applicant or is a member of a partnership or association applicant, or
 - 4) is a party to an agreement with such an applicant, express or implied, whereby (s) he may receive any payment or other benefit, whether or not for services rendered, or contingent upon the favorable approval of such application, petition or request.
- C. ~~Ownership of less than five percent (5%) of the stock of a corporation whose stock is listed on the New York or American Stock Exchanges shall not constitute an interest for the purposes of this section.~~
- D. A person who knowingly and intentionally violates this section shall be guilty of a misdemeanor.

III. That no Town of Manlius officer, employee or a relative of either, as defined in Section 809 General Municipal Law has any interest in this application.

-OR-

If a Town of Manlius officer, employee or relative of either as defined in Section 809 General Municipal law has any interest in this application, the full particulars are provided on an attached sheet.

Date: _____, 20 ____.

Date: _____, 20 ____.

(Print Name)

(Print Name)

(Signature)

(Signature)

(Entity Name)

(Entity Name)

By (Officer) (Title)

By (Officer) (Title)

(Mailing Address of Applicant)

(Mailing Address of Applicant)

(Telephone Number)

(Telephone Number)

ACKNOWLEDGEMENTS

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

On this _____ day of _____ in the year 20____, before me, the undersigned, a notary public in and for said state, personally appeared _____, and _____ personally known to me or proved to me on the basis of satisfactory evidence to be the individual whose name is subscribed to the within Petition and acknowledged to me the he/she/they executed the same in his/her/their capacity, and that by his/her/their signature(s) on the Petition, the individual or the persons upon behalf of which the individual acted executed the instrument.

Notary Public


CORPORATE ACKNOWLEDGEMENT

STATE OF NEW YORK)
) SS:
COUNTY OF ONONDAGA)

 Brandon Jacobson , being duly sworn, deposes and says the
s(he) is the managing member of Brolex Properties, LLC
corporation named in the within Application/Petition, that s(he) has read the foregoing affidavit and
knows the contents thereof; that the same is true of s(he) own knowledge, except as to those matters
therein stated to be alleged upon information and belief, and as to those matters s(he) believes it to be
true.


Applicant Signature

Subscribed to me before this day
Of December 30, 2019


Notary Public

TAYLOR ROESCHLAUB
NOTARY PUBLIC STATE OF NEW YORK
ONONDAGA
LIC. #01RO6399976
COMM. EXP. 11/04/2023